

N61165.AR.005005  
CNC CHARLESTON  
5090.3a

RAPID ASSESSMENT REPORT FOR SITE 25 BUILDING 1346 ZONE F CNC CHARLESTON  
SC  
01/01/2000  
TETRA TECH INC

# **Rapid Assessment Report for Site 25, Building 1346**

## **Zone F Charleston Naval Complex North Charleston, South Carolina**



**Southern Division  
Naval Facilities Engineering Command  
Contract Number N62467-94-D-0888  
Contract Task Order 0097**

January 2000

**RAPID ASSESSMENT REPORT  
AT  
SITE 25, BUILDING 1346**

**ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

**COMPREHENSIVE LONG-TERM  
ENVIRONMENTAL ACTION NAVY (CLEAN) CONTRACT**

**Submitted to:  
Southern Division  
Naval Facilities Engineering Command  
2155 Eagle Drive  
North Charleston, South Carolina 29406**

**Submitted by:  
Tetra Tech NUS, Inc.  
661 Andersen Drive  
Foster Plaza 7  
Pittsburgh, Pennsylvania 15220**

**CONTRACT NUMBER N62467-94-D-0888  
CONTRACT TASK ORDER 0097**

**JANUARY 2000**

**PREPARED UNDER THE SUPERVISION OF:**



**PAUL CALLIGAN, P.G.  
TASK ORDER MANAGER  
TETRA TECH NUS, INC.  
TALLAHASSEE, FLORIDA**

**APPROVED FOR SUBMITTAL BY:**



**DEBBIE WROBLEWSKI  
PROGRAM MANAGER  
TETRA TECH NUS, INC.  
PITTSBURGH, PENNSYLVANIA**

## CERTIFICATION PAGE

I certify that the information contained in this report and on any attachments is true, accurate, and complete to the best of my knowledge, information, and belief.

Approved By:



Gregory D. Swanson, P.E.  
South Carolina Registration No. 17132  
SCDHEC UST Site Rehabilitation Contractor Class I & II No. 24





## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
<b>EXECUTIVE SUMMARY .....</b>	<b>ES-1</b>
<b>1.0 INTRODUCTION .....</b>	<b>1-1</b>
1.1 SITE DESCRIPTION .....	1-1
1.2 SITE HISTORY .....	1-3
1.3 RECEPTOR SURVEY RESULTS .....	1-3
1.4 REGIONAL GEOLOGY AND HYDROGEOLOGY .....	1-5
1.5 SITE GEOLOGY AND HYDROGEOLOGY .....	1-6
<b>2.0 ASSESSMENT INFORMATION .....</b>	<b>2-1</b>
2.1 SITE-SPECIFIC GEOLOGY AND HYDROGEOLOGY .....	2-1
2.1.1 Site Geology .....	2-1
2.1.2 Site Hydrogeology .....	2-1
2.2 ASSESSMENT RESULTS .....	2-2
2.3 FIELD SCREENING ASSESSMENT .....	2-3
2.3.1 Soil Vapor Assessment .....	2-3
2.3.2 Soil Mobile Laboratory Results .....	2-3
2.3.3 Groundwater Mobile Laboratory Results .....	2-4
2.4 CHEMICALS OF CONCERN IN SOIL AND GROUNDWATER .....	2-4
2.4.1 Chemicals of Concern in Soil .....	2-4
2.4.2 Chemicals of Concern in Groundwater .....	2-5
2.5 ANALYTICAL DATA .....	2-5
2.6 AQUIFER CHARACTERISTICS AND EVALUATION .....	2-6
2.7 FATE AND TRANSPORT MODELING .....	2-7
2.8 PREDICTED MIGRATION AND ATTENUATION OF CHEMICALS OF CONCERN .....	2-8
<b>3.0 RISK EVALUATION .....</b>	<b>3-1</b>
3.1 TIER 1 EVALUATION .....	3-1
3.1.1 Exposure Pathway Analysis .....	3-1
3.1.2 On-Site Commercial/ Industrial Worker .....	3-1
3.1.3 On-Site Visitor .....	3-1
3.1.4 On-Site Construction Worker .....	3-2
3.1.5 On-Site Resident .....	3-2
3.1.6 Off-Site Resident .....	3-2
3.1.7 Surface Water .....	3-2
3.2 TIER 2 EVALUATION .....	3-3
3.2.1 Ingestion and Dermal Contact with Soil for a Construction Worker .....	3-3
3.2.2 Ingestion, Dermal Contact, or Inhalation of Vapors from Groundwater for a Construction Worker .....	3-4
3.2.3 Calculation of Groundwater RBSLs Protective of a Construction Worker .....	3-4
3.2.4 Risk From Soil Leaching to Groundwater for a Construction Worker .....	3-6
3.2.5 Inhalation of Volatiles from Soil for a Construction Worker .....	3-6
3.3 SUMMARY AND COMPARISON OF THE SELECTED SSTLs .....	3-8
3.4 RECOMMENDATIONS FOR FURTHER ACTION .....	3-8
<b>4.0 REFERENCES .....</b>	<b>4-1</b>

## **TABLE OF CONTENTS (Continued)**

### **TABLES**

- 1 WATER LEVEL AND SURVEY DATA**
- 2 GROUNDWATER FIELD MEASUREMENTS**
- 3 GROUNDWATER NATURAL ATTENUATION FIELD MEASUREMENTS**
- 4 SUMMARY OF SOIL BORINGS AND SOIL VAPOR SCREENING**
- 5 SUMMARY OF MOBILE LABORATORY SCREENING RESULTS FOR SOIL**
- 6 SUMMARY OF MOBILE LABORATORY SCREENING RESULTS FOR GROUNDWATER**
- 7 SUMMARY OF FIXED-BASE LABORATORY ANALYTICAL RESULTS FOR CHEMICALS OF CONCERN IN SOIL**
- 8 SUMMARY OF FIXED-BASE LABORATORY ANALYTICAL RESULTS FOR CHEMICALS OF CONCERN IN GROUNDWATER**
- 9 CURRENT LAND USE - POTENTIAL RECEPTORS AND PATHWAYS WITHIN 1,000-FOOT RADIUS**
- 10 FUTURE LAND USE - POTENTIAL RECEPTORS AND PATHWAYS WITHIN 1,000-FOOT RADIUS**

### **FIGURES**

- 1 Site Location Map**
- 2 Site Vicinity Map**
- 3 Site Map and Sampling Locations**
- 4 Soil CoC Map**
- 5 Groundwater CoC Map**
- 6 Groundwater Potentiometric Surface Map, September 11, 1999**

### **APPENDICES**

- A GEOLOGIC BORING LOGS**
- FIELD SAMPLING DATA SHEETS**
- B ANALYTICAL LABORATORY DATA**
- SOIL AND GROUNDWATER**
- C AQUIFER CHARACTERIZATION DATA**
- D RBCA CALCULATIONS**

## EXECUTIVE SUMMARY

Tetra Tech NUS, Inc. (TtNUS) has completed additional assessment activities requested by the South Carolina Department of Health and Environmental Control (SCDHEC) for Site 25 (Site Identification Number 01782) of Zone F, at the former Charleston Naval Complex (CNC), located in North Charleston, South Carolina. The site includes eight abandoned underground storage tanks (UST) located at Building 1346. The USTs provided retail gasoline to vehicles on-base since the mid-1960s and were abandoned in place from 1976 to 1991. Three new fiberglass tanks, installed in 1991, are currently being used at the site. The assessment was performed under the direction of SCDHEC Rapid Assessment (RA) guidance dated June 20, 1997, and Rapid Assessment Plan approval letter dated May 5, 1998.

In addition, SCDHEC reviewed the *Report of Findings, Vacuum Truck Extraction, Interim Corrective Action Pilot Test*, prepared by S&ME, Inc., dated May 21, 1998, and recommended "additional assessment activities to evaluate intrinsic remediation as the corrective action alternative for this site."

TtNUS has completed the additional assessment activities and has used the RA reporting format to describe the results. In addition, a Tier 1 and Tier 2 Evaluation was performed for the chemicals of concern (CoC) in soil and groundwater detected at the site in excess of the Risk-Based Screening Levels (RBSL). The risk evaluations followed the guidance set forth in the *SCDHEC Risk-Based Corrective Action (RBCA) for Petroleum Releases*, dated January 5, 1998.

### **TtNUS performed the following actions during the assessment:**

- Reviewed *Zone F, RCRA Facility Investigation Report, Charleston Naval Complex*, (E&A/H, 1996) to identify potential sources and receptors for petroleum hydrocarbons in the vicinity, to evaluate public and private potable wells, to locate utility line areas, to locate nearby surface water bodies, and to determine surface hydrology and drainage.
- Reviewed previously prepared reports by Westinghouse Environmental and Geotechnical Services, Inc., and S&ME, Inc., on site activities dating from August 1991 to May 1998.
- Conducted site survey to identify utilities and to construct a site plan.
- Installed 28 soil borings to depths ranging from 4 to 12 feet below land surface (bls) using direct push technology (DPT).
- Collected soil samples for field screening using an organic vapor analyzer.

- Installed five temporary piezometers.
- Collected soil and groundwater samples from DPT borings for on-site mobile laboratory screening analysis for benzene, toluene, ethylbenzene, and total xylenes (BTEX); naphthalene; and diesel range organics.
- Collected and analyzed nine confirmation soil samples at a fixed-base analytical laboratory for BTEX and naphthalene using U.S. Environmental Protection Agency (USEPA) Method 8260, and polynuclear aromatic hydrocarbons (PAHs) using USEPA Method 8270.
- Collected and analyzed one soil sample from one soil boring for total organic carbon using USEPA Method 415.1 and total recoverable petroleum hydrocarbons using USEPA Method 9071.
- Collected and analyzed two soil samples from one soil boring for grain size analysis using sieve and hydrometer methods.
- Collected groundwater samples from nine existing permanent monitoring wells for laboratory analysis at a fixed-base analytical laboratory.
- Collected groundwater samples from three wells for natural attenuation parameters.
- Analyzed groundwater samples for BTEX, methyl tert-butyl ether (MTBE) and naphthalene using USEPA Method 8260; PAHs using USEPA Method 8270; and lead using USEPA Method 3030.
- Collected depth to groundwater measurements to evaluate the groundwater flow direction.

### **Conclusions**

Nine soil samples were collected on July 7, 1999, and were analyzed for BTEX and PAHs by a fixed-base laboratory. Benzene concentrations exceeded RBSLs for sandy soils where groundwater depths are less than 5 feet below ground surface in all site borings except one; concentrations ranged from 6 parts per billion (ppb) to 120,000 ppb. Total naphthalene concentrations were detected above RBSL in four boring locations; concentrations ranged from 18, 000 ppb to 217, 900 ppb.

One groundwater sampling event was conducted in September 1999. Nine existing monitoring wells were sampled. BTEX, naphthalene, and MTBE constituents were detected above RBSLs in one monitoring well (CNC25-M05). In addition, the concentration of MTBE exceeded the RBSL at wells CNC25-M06 and 609004.

### **Tier 1 Evaluation**

A site conceptual model identified one possible receptor with five pathways present for Site 25:

1. A construction worker in a utility trench ingesting subsurface soil and/or having dermal contact with impacted subsurface soil.
2. A construction worker in a utility trench who might ingest, have dermal contact with contaminated groundwater, and/or inhale petroleum hydrocarbon vapors emitted from groundwater.

### **Tier 2 Evaluation**

The maximum soil concentrations of all CoCs were compared against the RBSL values for the construction worker exposed by dermal contact or incidental ingestion. Soil concentrations do not exceed the RBSLs for any of the CoCs; therefore, the construction worker ingesting or contacting impacted soil was not considered further.

The soil leachability model was used to calculate site-specific target levels (SSTLs) for the establishment of soil cleanup criteria. Benzene and naphthalene concentrations in the onsite, subsurface soil exceeded the calculated SSTLs for a construction worker in a utility trench.

Groundwater RBSLs were calculated for the additional pathways of dermal contact, incidental ingestion, and inhalation of volatiles by a construction worker in contact with shallow groundwater. The minimum RBSL for each CoC (regardless of the pathway) was used to compare to site groundwater data. Concentrations of benzene, toluene, and MTBE from MW-05 exceeded the selected minimum RBSLs. Therefore, remedial action is required at the site to protect the construction worker in the utility trench.

### **Recommendations for Further Action**

Corrective action is required at Site 25. The representative concentrations of CoCs in groundwater are above the selected minimum RBSLs calculated for a construction worker. In addition, the SSTLs for soil leaching to groundwater are exceeded. Therefore corrective action is necessary. The goal of corrective action is to prevent an impact to the identified potential receptor (the construction worker in an onsite utility trench).

## **1.0 INTRODUCTION**

Site 25 is located adjacent to Building 1346 at the intersection of Enterprise Avenue and Borie Street on the former Charleston Naval Complex (CNC), Zone F in North Charleston, South Carolina. The site functioned as a gasoline station since the mid-1960s providing gasoline for private and government vehicles. Initial evidence that a release occurred at the site was discovered in 1991 during the closure of an underground storage tank (UST) system on-site.

This Rapid Assessment (RA) was performed by Tetra Tech NUS, Inc. (TtNUS) located at 1401 Oven Park Drive, Suite 102, Tallahassee, Florida, 32308 (telephone number 850-385-9899). The assessment was performed on behalf of the U.S. Navy Southern Division (SOUTHDIR) Naval Facilities Engineering Command (NAVFAC), 2155 Eagle Drive, North Charleston, South Carolina 29406 (telephone number 843-820-7307). Authorization to conduct the assessment for the site was issued by NAVFAC under Contract Task Order (CTO) 0097. The assessment was performed under the direction of the South Carolina Department of Health and Environmental Control (SCDHEC) Rapid Assessment Plan approval letter dated May 5, 1998. Fieldwork necessary to complete the assessment was performed June 5, 1999, through September 21, 1999, by TtNUS.

### **1.1 SITE DESCRIPTION**

The CNC is in the city of North Charleston, on the western bank of the Cooper River in Charleston County, South Carolina (Figure 1). The installation consists of two major areas: an undeveloped dredge materials area on the eastern bank of the Cooper River on Daniel Island in Berkeley County and a developed area on the western bank of the Cooper River. The developed portion of the base is on a peninsula bounded to the west by the Ashley River and to the east by the Cooper River. The site is located within the developed portion of the base.

The area surrounding CNC is "mature urban," having been developed with commercial, industrial, and residential land use for many years. Commercial areas are primarily west of CNC; industrial areas are primarily to the north of the base along Shipyard Creek. A site vicinity map, which exhibits adjacent properties and structures, vicinity roads, current utilities, and vicinity surface drainage, is included as Figure 2. The subject site was a former naval exchange retail gasoline facility that had eight USTs buried onsite and later abandoned in place.

Presently the site contains eight abandoned in place USTs, three active USTs, one structure (Building 1346), and a canopy covering the current and former dispensing locations (Figure 3). Recreational baseball and football fields are located immediately adjacent to the site on the northeast, east, and south sides, a school (unknown building number) is located to the southwest (approximately 300 feet away from the tank area), and buildings to the northwest. A second school is located approximately 600 feet to the northeast (Building 199).

According to the Initial Site Characterization prepared in 1991 by Westinghouse Environmental Services, the first USTs installed consisted of four 4,000-gallon steel USTs with steel piping located within the same tank basin and one 10,000-gallon steel UST located separately. The tanks, all used for gasoline, were listed as 1346-D, -E, -F, -G, and -H. The tanks were abandoned in place around 1978.

The site was retrofitted with three 10,000-gallon steel tanks (1346-A, -B, and -C), during the period 1977 to 1981. These tanks were taken out of operation in February 1991 following a failed tank tightness test. As a result, three new 10,000-gallon fiberglass tanks with single-walled fiberglass piping were installed in 1991 (Tanks 1346-I, -J, and -K). These tanks are currently being used by SEG Fleet Maintenance, a trucking company. The USTs at the site contained various grades of unleaded gasoline, regular unleaded, unleaded plus, and super unleaded. The site is currently active. The following table summarizes the USTs at Site 25.

UST I.D.	Installed Date	Taken Out of Service Date	Type	Size (gallons)	Contents
1346-D	1960s	~1978	Steel	4,000	Gasoline
1346-E	1960s	~1978	Steel	4,000	Gasoline
1346-F	1960s	~1978	Steel	4,000	Gasoline
1346-G	1960s	~1978	Steel	4,000	Gasoline
1346-H	1960s	~1978	Steel	10,000	Gasoline
1346-A	1970s	1991	Steel	10,000	Gasoline
1346-B	1970s	1991	Steel	10,000	Gasoline
1346-C	1970s	1991	Steel	10,000	Gasoline
1346-I	1991	Active	Fiberglass	10,000	Gasoline
1346-J	1991	Active	Fiberglass	10,000	Gasoline
1346-K	1991	Active	Fiberglass	10,000	Gasoline

## **1.2 SITE HISTORY**

In 1901, the U.S. Navy acquired 2,250 acres near Charleston to build a shipyard and the first naval officer was assigned duty in early 1902. Subsequently, buildings and a dry dock were constructed in the Naval Yard. The dry dock was completed in 1909 along with several other brick buildings and the main power plant, which is still in operation today. The first ship was placed in dry dock and work began on fleet vessels in 1910. World War I brought about an expansion of the yards, facilities, land area, and work force. The yard built two gunboats, several submarine chasers, and tugs in addition to performing repairs and other services to the fleet. In 1933, building activity had increased principally in construction of several Coast Guard tugs, a Coast Guard cutter, and a Navy gunboat, creating the need for more facilities and a much larger work force. In 1943 civilian work force peaked with almost 26,000 employees divided among three daily shifts. In 1956, construction began on piers, barracks, and buildings for mine warfare ships and personnel. Later in the decade, the facility became a major home port for combat ships and submarines of the U.S. Atlantic Fleet [EnSafe/Allan & Hoshall, Inc.(E/A&H), 1996].

In 1993, major cuts in defense spending, as a result in part to the end of the Cold War, caused CNC to be added to the list of bases scheduled for closure under the Defense Base Realignment and Closure Act (BRAC). BRAC regulates the closure and transition of property back to the community (E/A&H, 1996). With the scheduled closure of the base, operations were scaled back and environmental cleanup proceeded to make the property available for redevelopment after closure.

## **1.3 RECEPTOR SURVEY RESULTS**

A survey of the site vicinity was conducted by TtNUS personnel to identify potential receptors for petroleum hydrocarbon contamination. The site plan (Figure 2) depicts all known utilities located within 250 feet of the Building 1346 location. According to facility personnel, utility lines are typically located 2 to 6 feet below land surface (bls) (SPORTENVDETHASN, 1999). The following utility receptors were located within a 250-foot radius of Building 1346.

- A water line is located at the northeast boundary of the site along South Avenue B and along the southeast side along Borie Street. The water line located between the canopy and Borie Street is approximately 50 feet southeast of the canopy and divides the area where UST basins are located. In addition, the line transects the free product interception trench located on-site near the corner of Borie Street and Enterprise Avenue.



- An 8-inch sanitary sewer line enters Building 1346 on the southwest side and extends southwesterly toward Enterprise Avenue. A sanitary sewer manhole is located approximately 30 feet south of the building. Four sanitary sewer manholes are located on Enterprise Avenue to the southwest.
- Three storm drainage catch basins are located on the north side of Building 1346. The storm drainage line originates near the canopy and extends northward toward a storm drain manhole located approximately 225 feet to the north at the corner of 9<sup>th</sup> Street and South Avenue B. Another storm drain manhole is located approximately 20 feet from the northwest corner of the canopy. A second storm utility line originates at a storm catch basin and storm manhole located approximately 20 feet from the south side of Building 1346 traversing the site northwesterly toward a storm manhole and catch basin along 9<sup>th</sup> Street.

Utilities on-site, and adjacent to the site within a 250-foot radius, that could serve as exposure points or as preferential pathways are shown in the following summary table.

Utility	On-site or Distance/Direction from site	Depth to Utility
Water Supply	On-site; ~20 feet	2 to 6 feet bls
Sanitary Sewer	On-site; ~100 feet west	2 to 6 feet bls
Storm Drainage	On-site; ~150 feet north	2 to 6 feet bls
Natural Gas	~300 feet to the northwest	2 to 6 feet bls

Potential receptors and preferential pathways within a 1000-foot radius of the site are summarized in the following table.

Description of Potential Receptor	Distance/Direction from Site
Construction workers in water supply utility trench.	~20 feet northwest of MW-05 and MW-06.
Commercial workers.	On-site. No complete pathways.
Trespassers.	Not applicable. Area is fenced.
Recreational visitors and/or residents.	Not applicable. Current and future site use is commercial.
Students/teachers/visitors at active school (located at Ave. D South & Borie St.).	~225 feet south/southwest of MW-06 (downgradient). No complete pathways.
Recreational visitors to football and baseball fields (east of Borie St. and north of South Ave. B).	~75 to 250 feet northeast, east, southeast, and south (upgradient, crossgradient, and downgradient). No complete pathways.

Description of Potential Receptor	Distance/Direction from Site
Students/teachers/visitors at active school (Building 199).	~600 feet northeast of Bldg. 1346 (upgradient). No complete pathways.
Groundwater at inactive industrial cooling water well (pump house Building 716).	~750 feet to the east of UST area (upgradient). No complete pathways.

A survey of groundwater users within a 7-mile radius of CNC was performed for the *Final RCRA Facility Investigation Report for Zone F* (E/A&H, 1996). According to this report, a survey of groundwater users within a 7-mile radius of CNC was conducted by the South Carolina Water Resources Commission to ascertain the extent of any shallow groundwater usage. Results of the water use investigation revealed that no drinking water wells, which utilize the shallow aquifer, are located within a 4-mile radius of CNC.

An industrial well, located approximately 750 feet east of the site and upgradient, supplied water to a compressor house for cooling tower operations. A recent visit to the site by TtNUS (October 1999) revealed an abandoned pump house for the well (Building 716). The industrial well is therefore believed to be inactive. Irrigation wells were not identified within 1,000 feet of the site. Numerous monitoring wells are located within 1,000 feet of the site. The nearest surface water body to Building 1346 is the Cooper River, located approximately 1,700 feet to the northeast.

There are no city, county, or state zoning ordinances as the property (CNC) is currently owned by the federal government. Information concerning zoning ordinances was obtained from the SOUTH DIV Remedial Project Manager located at 2155 Eagle Drive, North Charleston, South Carolina 29406 (telephone number 843-820-7307).

#### 1.4 REGIONAL GEOLOGY AND HYDROGEOLOGY

CNC is located in Charleston County, South Carolina, in the Lower South Carolina Coastal Plain Physiographic Province on the Cooper River side of the Charleston Peninsula. The peninsula is formed by the confluence of the Cooper and Ashley Rivers. Topography in the area is typical of the South Carolina lower coastal plain and is characterized by having low-relief plains broken by the meandering streams and rivers, flowing toward the coast past occasional marine terrace escarpments (E/A&H, 1996).

The geology of the Charleston area is typical of the southern Atlantic Coastal Plain. Cretaceous-age and younger sediments thicken seaward and are underlain by older igneous and metamorphic basement rock. Surface exposures consist of Recent or Pleistocene sands, silts, and clays of high organic content

referred to as the Wando Formation (E/A&H, 1996). Underlying the Wando Formation, increasing with age, are the Oligocene-age Cooper Group and the Eocene-age Santee Limestone. The Cooper Group is comprised of the Parkers Ferry, Ashley, and Harleyville Formations. The formation of particular importance in the Cooper Group is the Ashley Formation, which was formerly referred to as the Cooper Marl in most regional geologic literature. In more recent geologic nomenclature, the name "Cooper" has been given to a group of formations which includes the Ashley Formation, a pale green to olive-brown, sandy phosphoric limestone or marl, which is locally muddy and/or sandy. The Ashley Formation in the vicinity of Charleston is encountered at a depth of approximately 30 to 70 feet bls. The top of the Ashley Formation has been reported to be associated with an erosional basin and the entire Cooper Unit, including the Ashley Formation, is indicated to be approximately 300 feet thick (E/A&H, 1996).

Groundwater occurs under water table or poorly confined conditions within the Recent or Pleistocene deposits overlying the Ashley Formation of the Cooper Group. Transmissivity in the Pleistocene aquifer is generally less than 1,000 feet per day and well yields are variable, ranging from 0 to 200 gallons per minute (gpm). This groundwater contains high concentrations of iron and is commonly acidic at shallow depths (E/A&H, 1996).

The Cooper Group is hydrogeologically significant mainly because of its low permeability. In most locales, its sandy, finely granular limestone produces little or no water, but instead acts as confining material causing artesian conditions in the underlying Santee Limestone. Yields from wells in the Santee are usually less than 300 gpm (E/A&H, 1996).

## **1.5 SITE GEOLOGY AND HYDROGEOLOGY**

The Hydrogeologic Assessment prepared by S&ME, Inc., of Mount Pleasant, South Carolina, February 1993, stated that lagoonal sediments, which include surficial fill material of black to gray-green silty clays characteristic of back barrier island sequences, are present at the site. Soft gray-green clays are generally encountered down to the Cooper Formation. The Cooper Marl was encountered at the site at a depth of 29 feet bls.

Traversing east to west across the site, the surficial soils (upper 8 feet) graded to dense red clays with a slight increase in silt content (when compared to the eastern end of the site). Below 8 feet the dense gray-green clays were again encountered. Groundwater was generally encountered at depths of 4 to 6 feet bls. The groundwater flow direction was determined to be from the east to the west across the site.

The *RCRA Facility Investigation Report* (E/A&H, 1996) described the Zone F geologic unit immediately beneath the surficial lagoonal sediments and artificial fill as the Quaternary sand (Qs) unit. It is typically a very fine to medium-grained silty sand, well to moderately well sorted, with little clay. Coloration varies between gray, orange, and brown. Occasional laminae of brown to black silt, as well as small shell fragments, are often present. Qs deposits exhibit an average distribution of 73 percent sand, 5 percent silt, and 21 percent clay with an average porosity of 38 percent. The Qs sedimentary deposits range from depths of 5 feet to 35 feet in Zone F (E/A&H, 1996).

## **2.0 ASSESSMENT INFORMATION**

### **2.1 SITE-SPECIFIC GEOLOGY AND HYDROGEOLOGY**

#### **2.1.1 Site Geology**

Twenty-eight soil borings were advanced at Site 25 under the supervision of a TtNUS geologist between June 5 and August 3, 1999 (Figure 3). Each of the borings was completed using direct push technology (DPT). Each DPT boring was advanced to a depth ranging from 4 to 12 feet bls providing soil samples to characterize the subsurface lithology. The majority of the soil borings terminated at a depth of 8 feet below land surface. In addition, five shallow piezometers were installed between July 27, 1999, and August 2, 1999, to depths of 12 feet below land surface to confirm the site's groundwater flow direction.

Based on lithologic descriptions from the soil borings and monitoring wells, the subsurface soil generally consist of interlayers of orange to red, tan, and gray to olive-green-gray, sandy clay, silty clay and sand near the surface to the borings' terminal depth. Generally, sandy clay was encountered in the soil samples submitted for field screening. These samples were collected from 2 to 7 feet below land surface with the majority of the field screening sample collection being performed at the 3- to 5-foot interval. Boring logs are presented in Appendix A.

#### **2.1.2 Site Hydrogeology**

Five temporary, small diameter, polyvinyl chloride (PVC) piezometers, P01, P02, P03, P04, and P05 were installed on the south side of Building 1346. The piezometers were constructed of 1-1/4-inch-diameter Schedule 80 PVC casing and well screen 10 to 15 feet in length. The screen section of the piezometer was installed to bracket the water table. The piezometers were used to confirm the groundwater depth and flow direction at the site.

Six existing permanent monitoring wells installed by S&ME, and two recently installed permanent monitoring wells installed by EnSafe were used to collect groundwater samples (and to re-confirm groundwater flow direction and gradient). The recorded water-level data collected from these wells during the investigation are presented in Table 1. Groundwater elevation measurements were recorded from the site monitoring wells on September 11, 1999. The potentiometric surface map depicts a distinct southwesterly groundwater flow direction away from the Cooper River.

As part of the *Final RCRA Facility Investigation Report for Zone F* (E/A&H, 1996), a tidal survey was conducted in selected shallow wells at low and high tide, respectively. Groundwater flow patterns occur between low and high tide events with little change. Surficial aquifer groundwater flow is highly variable in gradient and direction. A narrow groundwater divide trends east to northeast from the tank farm area in nearby Zone G. Groundwater flow south of this divide is generally in an easterly direction toward the Cooper River. A groundwater depression north of this divide is associated with well SME005. Groundwater movement north of Ninth Street is from the south and west toward the north across Hobson Avenue.

## **2.2 ASSESSMENT RESULTS**

Twenty-eight soil borings were completed as part of the screening portion of the soil investigation at Site 25 between June 5 and August 3, 1999. The borings were completed using DPT, and samples were collected for screening. Screening samples were collected to evaluate subsurface soil and groundwater contaminant concentrations via an onsite mobile laboratory. The soil samples were collected from depths ranging from 2 to 7 feet bls. The soil and groundwater samples collected for mobile laboratory screening were analyzed for benzene, toluene, ethylbenzene, and xylenes (BTEX) and naphthalene and diesel range organics (DRO).

Eight soil borings (SB-09 to SB-17) were completed, and samples were collected for analysis at a fixed-base laboratory to confirm the results of the onsite mobile screening laboratory. The confirmation soil samples were collected at depths ranging from 1 to 4 feet bls on July 7, 1999. The chemicals of concern (CoCs) evaluated and analyzed were BTEX, methyl tert-butyl ether (MTBE), and naphthalene using U.S. Environmental Protection Agency (USEPA) Method 8260; polynuclear aromatic hydrocarbons (PAHs) using USEPA Method 8270; and lead using USEPA Method 3030. Two samples from one soil boring (SB-12 at depths of 2-3 feet and 7-8 feet bls) were collected for grain-size analysis using sieve and hydrometer analysis. A soil sample collected from SB-15 at a depth of 3 to 4 feet bls was analyzed for total organic carbon (TOC) analysis using USEPA Method 415.1 and total recoverable petroleum hydrocarbons (TRPH) using USEPA Method 9071. All sample collection was conducted in accordance with the SCDHEC *South Carolina Risk-Based Corrective Action for Petroleum Releases* dated January 5, 1998. Lithologic logs for each soil boring are presented in Appendix A. The soil boring locations are shown on Figure 3.

Groundwater monitoring well purging and sampling were conducted on September 12, 13, and 21, 1999. Groundwater sampling was conducted using a peristaltic pump and low flow, quiescent techniques. The monitoring wells were sampled in accordance with SCDHEC *South Carolina Risk-Based Corrective*

*Action for Petroleum Releases* dated January 5, 1998. Each well was purged of three well casing volumes until water quality parameters of pH, temperature, and conductivity stabilized. The field data sheets are included in Appendix A. A summary of the field parameter measurements is presented in Table 2. Groundwater samples were analyzed for BTEX, MTBE, ethylene dibromide (EDB), and naphthalene using USEPA Method 8260 and PAHs using USEPA Method 8270. Three of the groundwater samples were also analyzed for the following natural attenuation parameters: dissolved oxygen, alkalinity, carbon dioxide, sulfide, ferrous iron, nitrite, manganese, nitrogen/nitrate, sulfate and methane. Groundwater natural attenuation data are summarized in Table 3.

## **2.3 FIELD SCREENING ASSESSMENT**

### **2.3.1 Soil Vapor Assessment**

Twenty-eight soil borings were completed to evaluate for soil vapors as part of the soil screening assessment at Site 25. Organic vapor analyzer (OVA) headspace measurements were recorded at 1-foot intervals from ground surface to the top of the water table. Table 4 summarizes all soil borings installed and provides the maximum soil vapor screening results. Figure 3 presents the soil boring locations.

Soil vapor concentrations ranged from non-detectable to 4,900 parts per million (ppm). Vapor concentrations exceeding 1,000 ppm were detected from eight soil boring locations. The highest soil vapor concentration of 4,900 ppm occurred from CNC25-B17 at a sample depth of 3 to 4 feet bls. Most soil vapor detection occurred from soil depths of 2 to 5 feet bls.

The soil vapor assessment was used as a screening method to assist in identifying locations for collection of confirmation soil samples analyzed at a fixed-base laboratory. Soil sample locations were determined, in part, based on these data.

### **2.3.2 Soil Mobile Laboratory Results**

One soil sample collected from each soil boring was analyzed in a mobile laboratory for BTEX and diesel range organics using USEPA Method 8260. The soil samples were selected based upon the soil vapor screening results with the additional criterion that the samples originate in the vadose zone above the water table. Table 5 presents a summary of the analytical soil data from the mobile laboratory.

As indicated in Table 5, BTEX constituents were detected in the mobile laboratory soil screening for borings CNC25-SB-01, -05, -07, -19, -20, -21, and -25. Diesel range organics were detected in two borings, SB-01 and SB-20.

The mobile laboratory soil analysis was used as a screening method to assist in identifying locations for collection of soil samples for fixed-base laboratory analyses and to aid in delineating the extent of contamination in soil. Confirmation soil sample locations were determined, in part, based on these data.

### **2.3.3            Groundwater Mobile Laboratory Results**

A groundwater sample was collected from soil boring locations near the former UST systems around Building 1346. Each groundwater sample was analyzed by a mobile laboratory for BTEX and diesel range organics using USEPA Method 8260. Table 6 presents a summary of the analytical groundwater data from the mobile laboratory.

BTEX constituents were reported in groundwater samples from CNC25-SB-01, -05, -07, -19, -20, -21, -22 and -27. Diesel range organics were detected above the laboratory reporting limits in SB-05, -07, -19, -20, and -21.

The mobile laboratory groundwater analysis was used as a screening method to assist in delineating the extent of groundwater contamination.

## **2.4                CHEMICALS OF CONCERN IN SOIL AND GROUNDWATER**

### **2.4.1            Chemicals of Concern in Soil**

Nine subsurface soil samples were collected from the Site 25 area for determination of CoCs. The soil boring locations are shown on Figure 3. Table 7 summarizes the CoCs detected in the soil samples. BTEX concentrations exceeded the risk-based screening level (RBSL) for sandy soils where groundwater is less than 5 feet bls, in all but one soil sample collected at the site (CNC25-B15). Benzene concentrations ranged from an estimated 6 parts per billion (ppb) to 120,000 ppb.

Total naphthalene concentrations (naphthalene and 2-methylnaphthalene combined) were detected above RBSL in four boring locations. Concentrations ranged from 18,000 ppb to 217,900 ppb in CNC25-B10, -12, -13, and -17. The RBSL for naphthalenes in sandy soils where depth to groundwater is less than 5 feet bls is 210 µg/kg. The RBSL for soil was selected based upon a grain-size analysis completed



on sample CNC25-B12 at depths of 2 to 3 feet and 7 to 8 feet bls. Both samples confirmed the presence of a sandy soil matrix at the site. Soil analytical data sheets and grain size analysis reports are provided in Appendix B.

#### **2.4.2            Chemicals of Concern in Groundwater**

The analytical results for CoCs detected in groundwater samples are presented in Table 8. BTEX, naphthalene, and MTBE constituents were detected above RBSL at CNC25-M05 and in the duplicate sample. MTBE concentrations exceeded the RBSL at CNC25-M05, -M06, and 609004.

### **2.5                ANALYTICAL DATA**

Soil analytical data generated during this RA are summarized and compared to the RBSLs in Table 7. Groundwater analytical data generated during this RA are summarized and compared to the RBSLs in Table 8. The soil and groundwater laboratory analytical data for this RA are included in Appendix B.

### **2.6                AQUIFER CHARACTERISTICS AND EVALUATION**

Groundwater levels were measured from the site monitoring wells on September 11, 1999. The groundwater flow direction across the site was determined to be southwesterly toward Enterprise Avenue as illustrated on Figure 6.

As part of the *Final RCRA Facility Investigation Report for Zone F*, rising and falling head slug tests were conducted on several shallow monitoring wells located throughout the Zone F Quaternary sand unit to determine the hydraulic conductivity of the surficial aquifer (E/A&H, 1996). Slug tests were conducted by instantaneously adding (falling head) or removing (rising head) a volume (slug) of water from the well and measuring the recovering water level with a data logger. A hydraulic conductivity value was then calculated for the rising head test and for the falling head test. The average hydraulic conductivity for each well was determined by calculating the geometric mean of the rising and falling head values. Because hydraulic conductivity data are lognormally distributed, the geometric mean was determined to be the most representative measure of central tendency.

The well construction details and boring logs for each well tested during the RCRA investigation were reviewed to determine which wells were most representative of the conditions present at Site 25. To make this determination, the screened interval and proximity to the site were evaluated. Based on this

evaluation, monitoring wells 613004, 620002, 607001, and 613001 were selected as the most representative wells (see Appendix C for slug test data).

Potential movement of groundwater at the site may be described in terms of transportation by natural flow system in the saturated zone, assuming groundwater flow follows Darcy's Law. Using Darcy's Law the average linear groundwater velocity may be expressed as:

$$V = \left( \frac{K}{n} \right) \times i$$

where:

- V = average velocity
- K = hydraulic conductivity = 0.7 ft/day
- n = volumetric porosity = 0.36  
(based on analyses of Qs samples in the *Zone F RFI Report*)
- i = most recent hydraulic gradient measurement = 0.0096 ft/ft

therefore:

$$V = \left( \frac{0.7 \text{ ft/day}}{0.36} \right) \times 0.0096 \text{ ft/ft}$$

$$V = 0.0187 \text{ ft/day or } 6.8 \text{ ft/year}$$

In summary, the seepage velocity of the surficial aquifer was calculated to be approximately 6.8 feet per year based on a hydraulic conductivity of 0.7 feet per day, a hydraulic gradient of 0.0096 feet per foot, and a porosity of 36 percent for sandy soil.

## 2.7 FATE AND TRANSPORT MODELING

Soil and groundwater concentrations exceed the RBSL; therefore, evaluation of Site 25 will continue beyond Tier I. Fate and transport modeling is not required because both the source of contamination and the potential receptor are located onsite, however modeling was performed because of the high concentrations onsite.

The Domenico model was the fate and transport model used to determine groundwater site-specific target levels (SSTLs) in the risk analysis. The Domenico dilution/attenuation model is presented in the SCDHEC guidance document, *South Carolina Risk-Based Corrective Action for Petroleum Releases* (SCDHEC 1998). This model is very conservative in that it assumes an infinite mass, areal source

condition through which groundwater flows. The model incorporates biological decay effects through a first-order decay process; however, this mechanism was ignored because SCDHEC guidance specifies that the decay rate must be assumed to be zero if site-specific decay rates have not been determined.

The impacted groundwater source area was modeled as 50 feet (15.00 meters) wide and 6.56 feet (2.0 meters) deep; these values are conservative defaults suggested by the American Society for Testing Materials (ASTM) *Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites* (ASTM, 1997). The maximum source concentrations are assumed to exist throughout the source area, further compounding the conservatism of the estimate.

Site-specific data were used for saturated hydraulic conductivity, hydraulic gradient, porosity, and fraction of organic carbon in soil ( $2.47\text{E-}06$  m/sec,  $0.0096$  ft/ft,  $0.36$  cm<sup>3</sup>/cm<sup>3</sup>, and  $6.16\text{E-}4$  g-C/g-soil, respectively). The soil bulk density ( $1.73$  g/cm<sup>3</sup>) was determined using a porosity of  $0.36$  and assuming that the specific gravity of the soil particles is  $2.7$ .

However, because free product was previously detected in monitoring well MW05, the theoretical groundwater concentration in equilibrium with unleaded gasoline based on Raoult's Law (see Appendix D) was calculated for each of the potential CoCs. These calculated values were used for the source concentration in predicting the 10- and 20-year plume migration. This analysis showed that the theoretical concentrations of benzene ( $59.8$  mg/L), toluene ( $96.8$  mg/L), ethylbenzene ( $3.2$  mg/L), xylene ( $24.9$  mg/L), MTBE ( $5289$  mg/L), and naphthalene ( $0.22$  mg/L) each exceed the groundwater RBSLs; therefore, these CoCs were modeled. The concentration of naphthalene (i.e.,  $0.848$  mg/L) detected in well MW05 exceeds the theoretical calculated concentration for gasoline ( $0.22$  mg/L) indicating that free product may have contaminated the well at the time it was sampled and that a different petroleum product (e.g., diesel fuel) may have been released during the site's history.

The following estimates of dispersivity were used in the Domenico model as given in SCDHEC (1998):

Parameter	Estimate
Longitudinal Dispersivity, $\alpha_x$	$x/10$ , where $x$ = distance between the point of exposure and the source or compliance point
Transverse Dispersivity, $\alpha_y$	$\alpha_x/3$
Vertical Dispersivity, $\alpha_z$	$\alpha_x/20$

## 2.8 PREDICTED MIGRATION AND ATTENUATION OF CHEMICALS OF CONCERN

The Domenico model was used to predict the distance at which the leading edge of the plume is attenuated to SCDHEC RBSLs in 10 and 20 years without using degradation due to biological decay. This was done by adjusting the time to 10 years ( $3.15 \times 10^8$  sec) and 20 years ( $6.31 \times 10^8$  sec) and solving for distance (x) by trial and error. The source was assumed to be the impacted area onsite. The distance was changed until the required distance that is necessary for the concentration to attenuate to the RBSLs was determined. Model estimates for 10 and 20 years are provided in the following table:

Domenico Model Time Period	Chemical of Concern	Estimated Distance Traveled (feet)
10 year	Benzene	202
	Toluene	108
	Ethylbenzene	56
	Xylenes	26
	MTBE	287
	Naphthalene	25.5
20 year	Benzene	355
	Toluene	159
	Ethylbenzene	77
	Xylenes	36.5
	MTBE	507
	Naphthalene	34

The Domenico 10-year and 20-year simulation spreadsheets are presented in Appendix D.

## **3.0 RISK EVALUATION**

### **3.1 TIER 1 EVALUATION**

Performance of a Site Conceptual Model is required because the RBSLs for soil and groundwater were exceeded. Maximum concentrations of benzene, toluene, ethylbenzene, xylene, and naphthalene exceeded the RBSLs for sandy soil where depths to groundwater are 5 feet bls or less (table 7). Maximum concentrations of benzene, ethylbenzene, toluene, xylene, naphthalene, and MTBE exceeded the RBSLs for groundwater (Table 8). Exceeding the soil RBSL requires identification of current and future potential receptors and human exposure pathways.

#### **3.1.1 Exposure Pathway Analysis**

This section presents the receptor characterizations of the potentially exposed populations in the vicinity of the site and identifies the potentially complete exposure pathways for those receptors. SCDHEC requires that only those exposure pathways with CoC concentrations exceeding Tier 1 RBSL concentrations are examined in a Tier 2 risk-based corrective action report. Tables 9 and 10 present the exposure pathway assessments for current and future use scenarios.

#### **3.1.2 On-Site Commercial/ Industrial Worker**

An on-site commercial or industrial worker is defined as a business employee who works in a commercial/ industrial capacity at the site. The future use of the property is expected to be industrial or commercial for the foreseeable future; therefore, an on-site worker was considered as a potential receptor. Incidental ingestion and dermal contact with impacted soil are expected to be negligible for commercial/industrial workers because they are located inside a building. Drinking water at this site is provided by the city; therefore, ingestion of groundwater is not a complete exposure pathway. Building foundations are assumed sufficient to prevent volatilization from both soil and groundwater into a commercial building, and there is no history of vapors in the commercial building. It is unlikely that any additional exposure pathways will exist for future on-site workers; therefore, no complete pathways exist for either current or future commercial/ industrial workers.

#### **3.1.3 On-Site Visitor**

An on-site visitor is defined as any person other than a worker who might come on site. On-site visitors would have the same exposure pathways as commercial workers, but their exposure duration would be much shorter. This receptor does not have to be quantified because a potential on-site visitor's chemical intake would not determine risk or cleanup levels at the site.

#### **3.1.4            On-Site Construction Worker**

An on-site construction worker is defined as a laborer who would be involved in intrusive activities on or around the site, particularly in the area of subsurface utilities. On-site construction workers could be exposed to constituents in soil by the following pathways: inhalation of volatiles from soil, dermal contact with soil, and incidental ingestion of soil. On-site construction workers could be exposed to constituents in groundwater by the following pathways: inhalation of volatiles from groundwater, dermal contact with groundwater, and incidental ingestion of groundwater. A fresh water distribution line runs through the site; therefore, the point of exposure location for the on-site construction worker was considered to be at the source.

#### **3.1.5            On-Site Resident**

An on-site resident is defined as any person making his or her home at the site. This site is expected to remain a commercial/industrial facility; therefore, the on-site resident receptor was not considered further.

#### **3.1.6            Off-Site Resident**

An off-site resident is defined as any person making his or her home near the site. This receptor's location is either an actual current residence near the site or is a vacant lot or property on which a residence could be built. The site is located in an area that will likely remain commercial/industrial. Therefore, this potential receptor was not considered further.

#### **3.1.7            Surface Water**

The Cooper River is located approximately 1,700 feet upgradient and to the northeast of the site. Because of the distance to the river, this exposure pathway was not considered for ingestion of surface water.

**3.2 TIER 2 EVALUATION**

The Tier 1 Site Conceptual Model identified one possible receptor with six pathways:

1. A construction worker in a utility trench who might ingest subsurface soil, have dermal contact with impacted subsurface soil, or inhale volatilized vapors from affected soil.
2. A construction worker in a utility trench who might ingest contaminated groundwater, have dermal contact with contaminated groundwater, or inhale vapors from contaminated groundwater.

Based on the site conceptual model, a Tier 2 evaluation was performed.

**3.2.1 Ingestion and Dermal Contact with Soil for a Construction Worker in a Utility Trench**

The Site Conceptual Model identified the only potential receptor as a construction worker ingesting or having dermal contact with soil while working in a utility trench. For ingestion and dermal contact with soil while working in a utility trench, subsurface soil exposure to a construction worker is similar to surface soil exposure. The RBSLs given by SCDHEC for ingestion and dermal contact with surficial soils by a commercial worker are compared to the site soil concentrations in the table below. (RBSLs for commercial workers are conservative for construction workers. See footnote (1) below.)

CoC	RBSL*	SB-09	SB-10	SB-11	SB-12	SB-13	SB-13D	SB-14	SB-15	SB-16	SB-17
Benzene	200	0.052	9.100	.006	120.0	5.0	10.0	.007	< 0.006	0.008	32.0
Toluene	410,000	0.015	< 1.60	< 0.006	360.0	8.4	18.0	0.012	< 0.006	< 0.005	240.0
Ethylbenzene	200,000	< 0.006	63.0	0.014	560.0	73.0	130.0	0.013	< 0.006	< 0.005	49.0
Xylenes	1,000,000	< 0.006	3.0	0.019	2200.0	160.0	300.0	0.012	< 0.006	< 0.005	250
Benzo(a)-anthracene	3.9	< 0.4	< 0.46	< 0.36	< 0.43	<0.40	0.240J	< 0.40	<0.36	< 0.4	< 0.4
Benzo(b)-fluoranthene	3.9	< 0.40	< 0.46	< 0.36	< 0.43	<0.40	0.40	< 0.40	<0.36	< 0.40	< 0.40
Benzo(k)-fluoranthene	39	< 0.4	< 0.46	< 0.36	< 0.43	<0.40	<0.40	<0.40	<0.36	< 0.40	< 0.40
Chrysene	390	< 0.4	< 0.46	< 0.36	< 0.43	<0.40	<0.40	<0.40	<0.36	< 0.40	< 0.40
Dibenzo(a,h)-anthracene	0.39	< 0.4	< 0.46	< 0.36	< 0.43	<0.40	<0.40	<0.40	<0.36	< 0.40	< 0.40
Naphthalene <sup>2</sup>	41,000	0.004J	31.6	0.066	217.90	80.0	155.0	0.60	<0.006	0.004J	18.0

**Note:** All concentrations in mg/kg. Concentrations which exceed RBSL are bolded.

\* RBSLs for ingestion or dermal contact with surficial soil (RBCA, Table B6).

- (1) A commercial worker has a typically assumed exposure duration of 25 years and an exposure frequency of 250 days/year. A construction worker would be expected to have a much lower exposure duration and exposure frequency based on the nature of utility or construction work. The exposure frequency can be assumed to be 90 days/year and the exposure duration can be assumed to be 1 year. These assumptions are based on the nature of utility work. Therefore, the RBSLs for construction workers are expected to be higher than those for commercial workers.
- (2) Naphthalene (Total) combines Naphthalene (8260 value) and 2-Methylnaphthalene (8270 value).

As shown in the above table, maximum soil concentrations of constituents do not exceed the RBSLs for any CoC except dibenzo(a,h) anthracene. The concentrations for dibenzo(a,h) anthracene exceed the Commercial RBSL for ingestion or dermal contact with surficial soil. However, the RBSLs provided in the RBCA Guidance assume that a commercial worker will have an exposure duration for 25 years having an exposure frequency of 250 days per year. A construction worker would be expected to have a much lower exposure duration and exposure frequency based on the nature of utility, construction, or remediation work. The exposure frequency can be assumed to be 90 days/year or less and the exposure duration can be assumed to be 1 year or less. These assumptions are based on the nature of typical utility-type work. Furthermore, the maximum source concentrations of dibenzo(a,h)anthracene detected in soils barely exceed the above RBSLs (probably occurring because the laboratory reporting limit, or practical quantitation limit, slightly exceeds the RBSL). Therefore, dibenzo(a,h)anthracene is not considered a threat to a construction worker in a utility trench. A construction worker ingesting or contacting impacted soil is not considered at-risk and the dermal/ingestion pathway is not considered for further analysis.

### **3.2.2      Ingestion, Dermal Contact, or Inhalation of Vapors from Groundwater for a Construction Worker in a Utility Trench**

An additional completed pathway for construction workers is BTEX, naphthalene, and MTBE in the groundwater possibly exposing the workers to CoCs while working in a utility trench. The construction worker's potential exposure to groundwater containing any of these CoCs was assumed to consist of three pathways: dermal contact, incidental ingestion, and inhalation of volatiles.

### **3.2.3      Calculation of Groundwater RBSLs Protective of a Construction Worker in a Utility Trench**

Groundwater RBSLs provided by SCDHEC are for ingestion only; therefore, RBSLs were calculated for the additional pathways of dermal contact, incidental ingestion, and inhalation of volatiles.

Groundwater RBSLs for the construction worker were calculated for three pathways: dermal contact, incidental ingestion, and inhalation of volatiles. A target cancer risk of  $1 \times 10^{-6}$  and a target hazard quotient of 1 were used in the calculations. Standard defaults were used when available and applicable



to a construction worker. When no standard parameters were available, conservative assumptions were used. Where possible, site-specific parameters were used for site conditions. For all pathways, the exposure frequency was assumed to be 90 days/year and the exposure duration was assumed to be 1 year. These assumptions were considered conservative based on the nature of utility work.

The dermal contact RBSLs were calculated using procedures in *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual, Supplemental Guidance, Dermal Risk Assessment, Interim Guidance* (USEPA Peer Consultation Workshop Draft, 1998). Based on expected limited contact with groundwater, the event frequency was assumed to be one event/day and the event duration was assumed to be 1 hour/event. The skin surface area available for contact was 4500 cm<sup>2</sup>, based on one-fourth the skin surface area given in the risk assessment guidance document for a swimming adult.

The incidental ingestion RBSLs were calculated using the equation given in *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual (Interim Final)*, EPA/540/1-89/002 (EPA 1989). An incidental ingestion rate of 0.01 L/day was assumed based on a fraction (12.5 percent) of the incidental ingestion rate for a wading adult (0.01 L/hr), considered for an 8-hour work day. The incidental ingestion rate for wading adults is given in *Supplemental Guidance to RAGS: Region 4 Bulletins, Human Health Risk Assessment* (USEPA Region 4, 1995).

The inhalation RBSLs were calculated using equations given in the ASTM *Standard Guide for Risk-Based Corrective Action Applied to Petroleum Release Sites, Designation E 1739-95e1* (1997).

The following table summarizes the calculated RBSLs for the analyzed pathways and shows the minimum RBSL, regardless of the pathway (see calculations in Appendix D).

	Dermal RBSL (mg/L)	Incidental Ingestion RBSL (mg/L)	Inhalation RBSL (mg/L)	Selected Minimum Groundwater RBSL (mg/L)	Maximum Onsite Groundwater Conc. (mg/L)	Greater than the RBSL?
<b>Benzene</b>	0.85	68.52	0.15	0.15	26	Yes
<b>Toluene</b>	23.98	5677.78	5.38	5.38	38	Yes
<b>Ethylbenzene</b>	6.05	2838.89	14.50	6.05	3.2	No
<b>Xylenes</b>	102.33	56777.78	NA*	102.33	13	No
<b>Naphthalenes</b>	1.63	1135.56	2.63	1.63	0.848	No
<b>MTBE</b>	25.92	141.94	293.44	25.92	33	Yes

Note:\* No inhalation reference dose is available for xylenes; therefore, no inhalation RBSL can be calculated.

Based on the above table of calculated RBSLs, benzene, toluene, and MTBE in the groundwater pose a risk to a construction worker exposed to groundwater. Ethylbenzene, xylene, and naphthalene concentrations in groundwater do not pose a threat to the construction worker.

### 3.2.4 Risk From Soil Leaching to Groundwater for a Construction Worker in a Utility Trench

The Soil Leachability Model was used to calculate SSTLs for the establishment of soil cleanup criteria for benzene, toluene, ethylbenzene, xylenes, and naphthalene in soil. Site-specific parameters were used when available; otherwise, values were estimated from the charts on pages C2 through C5 of the SCDHEC guidance document, *Risk-Based Corrective Action for Petroleum Releases*, January 5, 1998. Grain size analysis of a representative vadose soil sample (SB-12 from 2 to 3 feet bls), showed that the soil contained 88 percent sand and 7 percent clay. The calculated RBSLs for a construction worker possibly ingesting, coming in contact with, or inhaling volatiles from the groundwater were used for calculating the SSTLs shown below. Appendix D presents the calculations for the model.

Chemical of Concern	Soil Leaching SSTL (mg/kg)	Maximum Onsite Soil Concentration (mg/kg)	Greater than the SSTL
Benzene	0.2	120	Yes
Ethylbenzene	14.5	560	Yes
Toluene	11	360	Yes
Xylenes	686	2200	Yes
Naphthalenes	24	217	Yes

Because the maximum soil concentration of benzene, ethylbenzene, toluene, xylene, and naphthalene found during the site assessment exceeds the calculated SSTLs for these CoCs, the construction worker is considered at-risk if exposed to groundwater leached through the impacted soil.

### 3.2.5 Inhalation of Volatiles from Soil for a Construction Worker in a Utility Trench

RBSLs for a construction worker in a trench inhaling volatile vapors from soil were calculated. The calculations are provided in Appendix D. The inhalation RBSLs were calculated using equations given in the ASTM *Standard Guide for Risk-Based Corrective Action Applied to Petroleum Release Sites, Designation E 1739-95E1* (1997).

The following table summarizes the calculated RBSLs for the analyzed pathway:

Chemical of Concern	Inhalation SSTL (mg/kg)	Maximum Onsite Soil Concentration (mg/kg)	Greater than the SSTL
Benzene	7,853	120	No
Ethylbenzene	226,430	360	No
Toluene	85,887	560	No
Xylenes*	NA	2200	NA
Naphthalenes	3,123	218	No

**Note:** \* No inhalation reference dose is available for xylenes; therefore, no inhalation RBSL can be calculated.

Based on the above table, the construction worker exposed to subsurface soil is not at risk if inhaling benzene, toluene, ethylbenzene, xylenes, or naphthalenes volatilizing from the soil.

### 3.3 SUMMARY AND COMPARISON OF THE SELECTED SSTLs

The following table summarizes the calculated SSTLs according to media (for exposure) and exposure pathway for the CoCs that may be a threat to the identified receptor construction worker in an onsite utility trench.

Media (for exposure)	Exposure Pathway	CoC	Unit	SSTL	Maximum Onsite Concentration	Greater than SSTL?
Groundwater	Dermal contact, inhalation, or ingestion	Benzene	mg/L	0.15	26	Yes
		Ethylbenzene	mg/L	5.38	38	Yes
		MTBE	mg/L	25.92	33	Yes
Soil (leaching from groundwater)	Dermal or incidental ingestion	Benzene	mg/kg	0.2	120	Yes
		Ethylbenzene	mg/kg	14.5	560	Yes
		Toluene	mg/kg	11	360	Yes
		Xylenes	mg/kg	686	2200	Yes
		Naphthalenes	mg/kg	24	218	Yes
Soil (leaching from groundwater)	Volatilization or inhalation	Benzene	mg/kg	0.2	120	No
		Ethylbenzene	mg/kg	14.5	560	No
		Toluene	mg/kg	11	360	No
		Xylenes	mg/kg	686	2200	No
		Naphthalenes	mg/kg	24	218	No

The above SSTLs should be used for establishing cleanup levels at the site.

### 3.4 RECOMMENDATIONS FOR FURTHER ACTION

Corrective action is required at Site 25. The benzene, ethylbenzene, and MTBE in groundwater are above the selected minimum SSTLs calculated for a construction worker. In addition, the SSTLs for soil leaching to groundwater are exceeded for benzene, toluene, ethylbenzene, xylenes, and naphthalenes; therefore, corrective action is necessary. The goal of corrective action is to prevent an impact to the identified potential receptor (the construction worker in an onsite utility trench).

## 4.0 REFERENCES

ASTM (American Society for Testing and Materials) 1997. *Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites*, Designation: E 1789-95, West Conshohocken, Pennsylvania.

Conoco Inc, 1996. Concawe Diesel Fuel/Kerosene.

E/A&H (EnSafe/Allen & Hoshall, Inc.), 1996. Zone F RCRA Facility Investigation Report, Naval Base Charleston, Charleston, South Carolina, 1996.

SCDHEC (South Carolina Department of Health and Environmental Control), 1970. Standard Limited Assessment, June 1970.

SCDHEC 1998. South Carolina Risk Based Corrective Action for Petroleum Releases, January 1998.

SPORTENDETHASN (Supervisor of Ship Building, Conversion and Repair, United States Navy, Portsmouth, Virginia, Environmental Detachment Charleston), 1996, Underground Storage Tank (UST) Assessment Report UST, Charleston Naval Base Complex, North Charleston, SC, October 7, 1996.

SPORTENDETHASN, 1999. Personal Contact between Paul Calligan TtNUS and Copes Wannamacker SPORTENDETHASN, June 17, 1999.

USEPA (U.S. Environmental Protection Agency), 1989. *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual (Interim Final)*, EPA/540/1-89/002.

USEPA REGION IV, 1995. *Supplemental Guidance to RAGS: Region 4 Bulletins, Human Health Risk Assessment, Interim*, November 1995, Atlanta, Georgia.

USEPA Environmental Research Brief, 1991. *Solubility, Sorption, and Transport of Hydrophobic Organic Chemicals in Complex Mixtures*, EPA/600/M-91/009. Robert S. Kerr Environmental Research Laboratory, Ada, Oklahoma.

USEPA PEER CONSULTATION WORKSHOP DRAFT, 1998. *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual, Supplemental Guidance, Dermal Risk Assessment, Interim Guidance*, November 1998, Washington, D.C.

## **TABLES**

**TABLE 1**

**WATER LEVEL AND SURVEY DATA  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

<b>Monitoring Well</b>	<b>Northing</b>	<b>Easting</b>	<b>TOCeL (feet)</b>	<b>Well Total Depth (feet)</b>	<b>Well Screen Depth (feet)</b>	<b>Water Level BTOC (feet)</b>	<b>Groundwater Elevation (feet)</b>
609002	373661.0421	2318340.847	7.83	12.0	1-11	5.49	2.34
609004	373737.5122	2318446.267	7.54	13.0	2-12	3.42	4.12
CNC25-MW01	373880.8929	2318417.096	7.90	12.0	1-11	3.58	4.32
CNC25-MW03	373506.6288	2318190.059	7.40	13.0	2-12	5.87	1.53
CNC24-MW04*	373760.4013	2318182.343	8.00	13.0	2-12	n/m	n/m
CNC25-MW05	373687.9653	2318295.297	8.02	13.0	2-12	5.46	2.56
CNC25-MW06	373677.0889	2318284.952	7.92	27.0	16-26	5.98	1.94
CNC25-MW07	373696.3178	2318103.999	7.41	13.0	2-12	6.44	0.97
CNC25-MW08	373978.0111	2318287.141	7.60	13.0	2-12	3.85	3.75

**Notes:**

Water level measurements were taken on September 11, 1999, and are tide-synchronous (MW06 is a deep well).

CNC25-MW02 not sampled (full of sediment)

TOCeL -- top of casing elevation

BTOC -- below top of casing

\* Site 24

n/m-- not measured

**TABLE 2**

**GROUNDWATER FIELD MEASUREMENTS  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

Well I.D.	Date Sampled	Purge method	Volume (gallons)	Temp. (° C)	pH	Conductivity (umhos/cm)	Turbidity (NTU)	Dissolved Oxygen (mg/L)
CNC25-M01	09/21/99	PP	4.5	25.9	6.50	1.04	*	0.21
CNC25-M03	09/12/99	PP	4.0	29.9	5.08	1.23	25	1.43
CNC25-M04	09/13/99	PP	3.5	28.6	6.00	2.03	< 1	1.22
CNC25-M05	09/21/99	PP	6.0	29.7	5.33	0.269	< 1	5.45
CNC25-M06	09/12/99	PP	10.0	25.7	6.47	5.72	27	1.67
CNC25-M07	09/21/99	PP	4.0	29.2	5.33	0.686	< 1	5.88
CNC25-M08	09/12/99	PP	4.0	28.7	5.36	2.40	35	1.53
609002	09/21/99	PP	4.0	26.0	6.70	4.09	3	0.11
609004	09/21/99	PP	5.0	26.6	6.45	0.98	75	1.77

**Notes:**

PP - Peristaltic pump, low flow technique

umhos/cm - micro mhos per centimeter

NTU - Nephelometric turbidity units

mg/L - milligrams per liter

\* -- instrument malfunction; water visually clear



**TABLE 3**

**GROUNDWATER NATURAL ATTENUATION FIELD MEASUREMENTS  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

Well I.D.	Date Sampled	Dissolved Oxygen (mg/L)	Alkalinity (mg/L)	Carbon Dioxide (mg/L)	Sulfide (mg/L)	Ferrous Iron (mg/L)	Nitrite (mg/L)	Manganese (mg/L)	Nitrogen/Nitrate (mg/L)*	Sulfate (mg/L)*	Methane (ug/L)*
CNC25-MW01	09/21/99	0.30	552	300	0.00	3.30	0.126	0.0	0.29	160	4400 6000 (D)
CNC25-MW05	09/21/99	0.60	136	388	0.11	3.30	0.000	0.4	<0.050	40	3500 4400 (D)
CNC25-MW07	09/21/99	0.30	63	204	0.00	0.17	0.047	0.1	0.16	160	6.5

**Notes:**

mg/L - milligrams per liter

ug/L - micrograms per liter

\* fixed-base laboratory analysis

D - laboratory duplicate

TABLE 4

**SUMMARY OF SOIL BORINGS AND SOIL VAPOR SCREENING  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA  
[PAGE 1 of 2]**

Soil Boring Location	Sample Identification	Sample Lithology	Soil Sample Condition	Soil Sample Depth (feet)	Total Boring Depth (feet)	Sample Interval Maximum OVA Reading (PPM)
CNC25-B01	25SFB010506	Sandy Clay	Moist	05-06	12	3,000
CNC25-B02	25SFB020203	Sandy Clay	Moist	02-03	12	5
CNC25-B03	25SFB030405	Silty Clay	Moist	04-05	11	19
CNC25-B04	25SFB040203	Sandy Clay	Moist	02-03	8	0
CNC25-B05	25SFB050405	Sandy Clay	Moist	04-05	11	80
CNC25-B06	25SFB060405	Silty Clay	Moist	04-05	12	1,120
CNC25-B07	25SFB070607	Sandy Clay	Moist	06-07	12	260
CNC25-B08	25SFB080304	Silty Clay	Moist	03-04	11	140
CNC25-B09	25SLB090304	Sandy Silty Clay	Moist	03-04	8	106
CNC25-B10	25SLB100102	Silty Clay	Moist	01-02	8	4,860
CNC25-B11	25SLB110203	Clayey Sand	Moist	02-03	8	1,610
CNC25-B12	25SLB120203	Silty Sandy Clay	Moist	02-03	8	4,790
CNC25-B13	25SLB130203	Clayey Sand	Moist	02-03	8	4,300
CNC25-B14	25SLB140304	Sand	Moist	03-04	8	820
CNC25-B15	25SLB150304	Sand	Moist	03-04	4	150
CNC25-B16	25SLB160304	Sandy Clay	Moist	03-04	4	250
CNC25-B17	25SLB170304	Sandy Clay	Moist	03-04	4	4,900
CNC25-B18	25SFB180405	Silty Clay	Moist	04-05	12	110
CNC25-B19	25SFB190304	Silty Clay	Dry	03-04	8	0

TABLE 4

**SUMMARY OF SOIL BORINGS AND SOIL VAPOR SCREENING  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA  
[PAGE 2 of 2]**

Soil Boring Location	Sample Identification	Sample Lithology	Soil Sample Condition	Soil Sample Depth (feet)	Total Boring Depth (feet)	Sample Interval Maximum OVA Reading (PPM)
CNC25-B20	25SFB200405	Sandy Clay	Dry to Moist	04-05	8	2,410
CNC25-B21	25SFB210506	Sandy Clay	Moist	05-06	8	60
CNC25-B22	25SFB220607	Clayey Sand	Moist	06-07	8	0
CNC25-B23	25SFB230607	Silty Clay	Moist	06-07	12	7
CNC25-B24	25SFB240607	Sandy Clay	Moist	06-07	8	0
CNC25-B25	25SFB250506	Sandy Clay	Moist	05-06	8	0
CNC25-B26	25SFB260405	Clayey Sand	Moist	04-05	8	0
CNC25-B27	25SFB270304	Sandy Clay	Moist	03-04	8	190
CNC25-B28	25SFB280304	Clayey Sand	Moist	03-04	8	0

**Notes:**

Soil Borings B09 – B17 were completed for fixed-base laboratory analysis.  
OVA - organic vapor analyzer equipped with a flame ionization detector  
PPM - parts per million

TABLE 5

SUMMARY OF MOBILE LABORATORY SCREENING RESULTS FOR SOIL  
 SITE 25, BUILDING 1346  
 ZONE F, CHARLESTON NAVAL COMPLEX  
 NORTH CHARLESTON, SOUTH CAROLINA

Sample I.D.	Benzene (ug/kg)	Toluene (ug/kg)	Ethylbenzene (ug/kg)	m&p- Xylene (ug/kg)	o-Xylene (ug/kg)	Naphthalene (ug/kg)	DRO (mg/kg)
25SFB010506	4786 E	14787 E	4368 E	15960 E	6605 E	1515 E	290
25SFB020203	ND	ND	ND	ND	ND	ND	ND
25SFB030405	ND	ND	ND	ND	ND	ND	ND
25SFB040203	ND	ND	ND	ND	ND	ND	ND
25SFB050405	80.0	ND	40.5 J	ND	ND	54.0 J	ND
25SFB060405	ND	ND	ND	ND	ND	ND	ND
25SFB070607	175	82.5	ND	ND	ND	ND	ND
25SFB080304	ND	ND	ND	ND	ND	ND	ND
25SFB180405	ND	ND	ND	ND	ND	ND	ND
25SFB190304	3025**	54000 E**	23400 E**	96800 E**	40200 E**	5620**	ND
25SFB200405	768 E	3620 E	1240 E	3950 E	1490 E	64.8	51.5
25SFB210506	234	203	156	320	99.6	29.7 J	ND
25SFB220506	ND	ND	ND	ND	ND	ND	ND
25SFB230607	ND	ND	ND	ND	ND	ND	ND
25SFB240607	ND	ND	ND	ND	ND	ND	ND
25SFB250506	ND	ND	5.03 J	20.3 J	7.72 J	ND	ND
25SFB260405	ND	ND	ND	ND	ND	ND	ND
25SFB270304	ND	ND	ND	ND	ND	ND	ND
25SFB280304	ND	ND	ND	ND	ND	ND	ND

(\*\*10X Dilution)

TABLE 6

SUMMARY OF MOBILE LABORATORY SCREENING RESULTS FOR GROUNDWATER  
 SITE 25, BUILDING 1346  
 ZONE F, CHARLESTON NAVAL COMPLEX  
 NORTH CHARLESTON, SOUTH CAROLINA

Sample I.D.	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	m&p- Xylene (ug/L)	o-Xylene (ug/L)	Naphthalene (ug/L)	DRO (mg/L)
25GFB010912	44.7	56.8	9.63 J	29.0	15.3	ND	ND
25GFB020811	ND	ND	ND	ND	ND	ND	ND
25GFB030811	ND	ND	ND	ND	ND	ND	ND
25GFB040508	ND	ND	ND	ND	ND	ND	ND
25GFB050811	631 E	27.6	251 E	141	52.2	180	4.0*
25GFB060811	ND	ND	ND	ND	ND	ND	ND
25GFB070912	2503 E	185	523 E	ND	50.8	30.9	3.0*
25GFB080407	ND	ND	ND	ND	ND	ND	ND
25GFB180512	ND	ND	ND	ND	ND	ND	ND
25GFB190408	46500 E**	33500 E**	5620 E**	17900 E**	6770 E**	3420**	17.3 *
25GFB200508	2780 E	455 E	183	440 E	228	251	2.0*
25GFB210608	5360 E	156	1420 E	877 E	272	295	4.20
25GFB220708	11.8	ND	ND	ND	ND	ND	ND
25GFB230912	ND	ND	ND	ND	ND	ND	ND
25GFB240708	ND	ND	ND	ND	ND	ND	1.34 J
25GFB250708	ND	ND	ND	ND	ND	ND	ND
25GFB260508	ND	ND	ND	ND	ND	ND	ND
25GFB270508	6.29 J	ND	ND	ND	8.90 J	ND	ND
25GFB280508	ND	ND	ND	ND	ND	ND	ND

\* Gasoline signature

\*\* 10X dilution

TABLE 7

**SUMMARY OF FIXED-BASE LABORATORY ANALYTICAL RESULTS FOR CHEMICALS OF CONCERN IN SOIL  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

Soil Boring / Sample No.	MTBE (ug/kg)	Benzene (ug/kg)	Toluene (ug/kg)	Ethyl- benzene (ug/kg)	Xylenes (total) (ug/kg)	Benzo(a) anthracene (ug/kg)	Benzo(b) fluoranthene (ug/kg)	Benzo(k) fluoranthene (ug/kg)	Chrysene (ug/kg)	Dibenzo(a,h) anthracene (ug/kg)	Naphthalene* (ug/kg)	Lead (mg/kg)
<b>RBSL <sup>(1)</sup></b>	<b>None</b>	<b>5</b>	<b>1,622</b>	<b>1,260</b>	<b>42,471</b>	<b>73,084</b>	<b>29,097</b>	<b>2.3E+05</b>	<b>12,998</b>	<b>87,899</b>	<b>210</b>	<b>None</b>
CNC25-B09 / 25SLB090304	< 6	<b>52</b>	15	< 6	< 6	< 400	< 400	< 400	< 400	< 400	4 <sup>(J)</sup>	10.5
CNC25-B10 / 25SLB100102	< 800	<b>9,100</b>	< 1600	<b>63,000</b>	3,000	< 460	< 460	< 460	< 460	< 460	<b>31,600</b>	34.7
CNC25-B11 / 25SLB110203	< 6	6 <sup>(J)</sup>	< 6	14	19	< 360	< 360	< 360	< 360	< 360	66	125
CNC25-B12 / 25SLB120203	< 750	<b>120,000</b>	<b>360,000</b>	<b>560,000</b>	<b>2.2E+06</b>	< 430	< 430	< 430	< 430	< 430	<b>217,900</b>	26.2
CNC25-B13 / 25SLB130203	< 600	<b>5,000</b>	<b>8,400</b>	<b>73,000</b>	<b>160,000</b>	< 400	< 400	< 400	< 400	< 400	<b>80,000</b>	6.2
CNC25-B13 / 25SLB130203D	< 550	<b>10,000</b>	<b>18,000</b>	<b>130,000</b>	<b>300,000</b>	240 <sup>(J)</sup>	< 400	< 400	< 400	< 400	<b>155,000</b>	10.4
CNC25-B14 / 25SLB140304	< 5	<b>7</b>	12	13	12	< 400	< 400	< 400	< 400	< 400	60	4.9
CNC25-B15 / 25SLB150304	< 6	< 6	< 6	< 6	< 6	< 360	< 360	< 360	< 360	< 360	< 6	5.9
CNC25-B16 / 25SLB160304	< 5	<b>8</b>	< 5	< 5	< 5	< 400	< 400	< 400	< 400	< 400	4 <sup>(J)</sup>	6.5
CNC25-B17 / 25SLB170304	<b>4,300</b>	<b>32,000</b>	<b>240,000</b>	<b>49,000</b>	<b>250,000</b>	< 400	< 400	< 400	< 400	< 400	<b>18,000</b>	7.4

**Notes:**

Sample Collection Date: June 10, 1999.

<sup>(1)</sup> SCDHEC Risk-Based Screening Levels for sandy soil; depth to groundwater less than 5 feet.<sup>(J)</sup> Indicates the presence of an analyte at a concentration less than the reporting limit and greater than the detection limit.

D Indicates a duplicate sample.

\* Naphthalene includes Naphthalene (8260 value) and 2-Methylnaphthalene (8270 value) for values in bold.

TABLE 8

**SUMMARY OF FIXED-BASE LABORATORY ANALYTICAL RESULTS FOR CHEMICALS OF CONCERN IN GROUNDWATER  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

Monitoring Well Sample No.	Date Sampled	Benzene (ug/L)	Ethyl- benzene (ug/L)	Toluene (ug/L)	Xylenes (total) (ug/L)	Naphthalene (ug/L)	Benzo(a) anthracene (ug/L)	Benzo(b) fluoranthene (ug/L)	Benzo(k) fluoranthene (ug/L)	Chrysene (ug/L)	Dibenzo(a,h) anthracene (ug/L)	MTBE (ug/L)	EDB (ug/L)	Lead (ug/L)
<b>RBSL<sup>(1)</sup></b>		<b>5</b>	<b>700</b>	<b>1000</b>	<b>10000</b>	<b>10<sup>(2)</sup></b>	<b>10<sup>(2)</sup></b>	<b>10<sup>(2)</sup></b>	<b>10<sup>(2)</sup></b>	<b>10<sup>(2)</sup></b>	<b>10<sup>(2)</sup></b>	<b>40</b>	<b>5</b>	<b>15</b>
CNC25M-01 25GLM0101	09/21/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	< 5	< 5	3.9
CNC25M-03 25GLM0301	09/12/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	< 5	< 5	< 1.4
CNC25M-04 25GLM0401	09/13/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	< 5	< 5	< 1.09
CNC25M-05 25GLM0501	09/21/99	<b>25000</b>	<b>3000</b>	<b>35000</b>	<b>12000</b>	<b>760<sup>(3)</sup></b>	< 10	< 10	< 10	< 10	< 10	<b>33000</b>	< 250	7.3
CNC25M-05 25GLM0501D	09/21/99	<b>26000</b>	<b>3200</b>	<b>38000</b>	<b>13000</b>	<b>848<sup>(3)</sup></b>	< 10	< 10	< 10	< 10	< 10	<b>33000</b>	< 250	7
CNC25M-06 25GLM0601	09/12/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	<b>220</b>	< 5	< 1.09
CNC25M-07 25GLM0701	09/13/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	< 5	< 5	< 1.09
CNC25M-08 25GLM0801	09/12/99	< 5	< 5	< 5	< 5	< 5	< 12	< 12	< 12	< 12	< 12	< 5	< 5	< 1.3
609002 25GLX0201	09/21/99	< 5	< 5	< 5	< 5	< 5	< 10	< 10	< 10	< 10	< 10	< 5	< 5	1.6
609004 25GLX0401	09/21/99	< 5	< 5	< 5	< 5	< 5	< 12	< 12	< 12	< 12	< 12	<b>130</b>	< 5	5.5

**Notes:**

<sup>(1)</sup> South Carolina Department of Health and Environmental Control Risk-Based Screening Levels for groundwater.

<sup>(2)</sup> The RBSL for individual PAH CoC is 10 ug/L or 25 ug/L for total PAHs.

<sup>(3)</sup> Value represents Total Naphthalene (Method 8260 value for naphthalene *plus* Method 8270 value for 2-methylnaphthalene).

**Concentrations exceeding RBSL are in bold.**

TABLE 9

**CURRENT LAND USE - POTENTIAL RECEPTORS AND PATHWAYS WITHIN 1,000-FOOT RADIUS  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

<b>Media (for exposure)</b>	<b>Exposure Route</b>	<b>Pathway Selected for Evaluation? (Yes or No)</b>	<b>Exposure point or Reason for Non-Selection</b>	<b>Data Requirements (If pathway selected)</b>
Air	Inhalation	No	No volatilization to enclosed space.	
	Explosion Hazard	No	No explosion hazard.	
Ground-Water	Ingestion	No	No water supply well downgradient.	RBSLs for construction worker exposed to groundwater.
	Dermal Contact	No	All water is supplied by city. However, construction worker could be exposed to groundwater in utility trench.	
	Volatile Inhalation	No		
Surface Water	Ingestion	No	Cooper River is 1700 feet to the east (upgradient).	
	Dermal Contact	No		
	Volatile Inhalation	No	No complete pathway.	
Surficial Soil	Ingestion	No	No impacted surface soil. Asphalt and concrete cover impacted soil.	
	Dermal Contact	No		
	Volatile Inhalation	No		
	Leaching to Groundwater	No		
Subsurface Soil	Ingestion	No	Construction worker in a utility trench could be exposed to contaminated soil and soil vapors.	
	Dermal Contact	No		
	Volatile Inhalation	No		
	Leaching to Groundwater	No	Sandy soils; groundwater is shallow: ~5 feet bls.	





TABLE 10

**FUTURE LAND USE - POTENTIAL RECEPTORS AND PATHWAYS WITHIN 1,000-FOOT RADIUS  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA**

<b>Media (for exposure)</b>	<b>Exposure Route</b>	<b>Pathway Selected for Evaluation? (Yes or No)</b>	<b>Exposure point or Reason for Non-Selection</b>	<b>Data Requirements (If pathway selected)</b>
Air	Inhalation	No	No volatilization to enclosed space.	
	Explosion Hazard	No	No explosion hazard.	
Ground-water	Ingestion	Yes	No water supply well downgradient.	RBSLs for construction worker exposed to groundwater.
	Dermal Contact	Yes	All water is supplied by city.	
	Volatile Inhalation	Yes	However, construction worker could be exposed to groundwater in utility trench.	
Surface Water	Ingestion	No	Cooper River is 1700 feet to the east (upgradient).	
	Dermal Contact	No		
	Volatile Inhalation	No	No complete pathway.	
Surficial Soil	Ingestion	No	No impacted surface soil. Asphalt and concrete cover impacted soil.	
	Dermal Contact	No		
	Volatile Inhalation	No		
	Leaching to Groundwater	No		
Subsurface Soil	Ingestion	Yes	Construction worker in a utility trench could be exposed to contaminated soil and soil vapors.	
	Dermal Contact	Yes		
	Volatile Inhalation	Yes	Sandy soils; groundwater is shallow: ~5 feet bls.	
	Leaching to Groundwater	Yes		


## FIGURES

ACAD:0219CM11.dwg 10/29/99 DT



QUADRANGLE LOCATION

SOURCE: QUADRANGLE MAP SOUTH CAROLINA, REVISED 1979  
QUADRANGLE MAP NORTH CHARLESTON REVISED, 1979



SCALE IN FEET

DRAWN BY DATE  
DLT 10/29/99

CHECKED BY DATE

COST/SCHED-AREA

SCALE  
AS NOTED




SITE LOCATION MAP  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA


CONTRACT NO.  
0219


APPROVED BY DATE

APPROVED BY DATE




DRAWING NO. REV.  
FIGURE 1 0



NO.	DATE	REVISIONS	BY	CHKD	APPD	REFERENCES	DRAWN BY DLT 10/29/99	DATE 10/29/99		SITE VICINITY MAP SITE 25, BUILDING 1346 ZONE F, CHARLESTON NAVAL COMPLEX NORTH CHARLESTON, SOUTH CAROLINA		CONTRACT NO. 0219	
							CHECKED BY	DATE		APPROVED BY	DATE	DRAWING NO. FIGURE 2	REV. 0
							COST/SCHED-AREA			APPROVED BY	DATE		
							SCALE AS NOTED						




**LEGEND:**

-  MONITORING WELL  
LOCATION AND  
DESIGNATION  
CNC25-MW01
-  SOIL BORING  
LOCATION AND  
DESIGNATION  
CNC25-B01
-  FORMER UST BASIN


NO.	DATE	REVISIONS	BY	CHKD	APPD	REFERENCES

DRAWN BY	DATE
DLT	10/29/99
CHECKED BY	DATE
COST/SCHED-AREA	
SCALE	
AS NOTED	




SITE MAP AND SAMPLING LOCATIONS  
SITE 25, BUILDING 1348  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA

CONTRACT NO. 0219	
APPROVED BY	DATE
APPROVED BY	DATE
DRAWING NO. FIGURE 3	REV. 0




NO.	DATE	REVISIONS	BY	CHKD	APPD	REFERENCES	DRAWN BY	DATE		SOIL CoC MAP SITE 25, BUILDING 1346 ZONE F, CHARLESTON NAVAL COMPLEX NORTH CHARLESTON, SOUTH CAROLINA		CONTRACT NO. 0219	
							DLT	10/29/99		APPROVED BY	DATE	APPROVED BY	DATE
							CHECKED BY	DATE					
							COST/SCHED-AREA						
							SCALE	AS NOTED			DRAWING NO. FIGURE 4	REV. 0	



**LEGEND:**


● MONITORING WELL  
CNC25-MW01 LOCATION AND  
DESIGNATION

□ FORMER UST BASIN




NO.	DATE	REVISIONS	BY	CHKD	APPD	REFERENCES

DRAWN BY	DATE
DLT	10/29/99
CHECKED BY	DATE
COST/SCHED-AREA	
SCALE	
AS NOTED	



GROUNDWATER CoC MAP  
SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA

CONTRACT NO.	0219
APPROVED BY	DATE
APPROVED BY	DATE
DRAWING NO.	FIGURE 5
REV.	0





**APPENDIX A**

**GEOLOGIC BORING LOGS  
FIELD SAMPLING DATA SHEETS**







## Page \_\_\_\_ of \_\_\_\_

DRILLER: B. Lewis

$$H.S. \omega / \text{fil.} = 0 \text{ pf}$$

Converted to Well:	Yes	No	Well I.D. #:

## Page \_\_\_\_ of \_\_\_\_

Site 25  
Columbia  
Geoprobe 540

BORING NUMBER: CNC25BØS  
DATE: 6-5-99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: B. Lewis

$H.S. \frac{W}{\% f. i} = 170 \text{ pp}$   
 $H.S. \frac{W}{\% f. i} = 120 \text{ pp}$   
 $H.S. \frac{W}{\% f. i} = 130 \text{ pp}$   
 $H.S. \frac{W}{\% f. i} = 50 \text{ pp}$

Converted to Well:	Yes	No	Well I.D. #:
--------------------	-----	----	--------------

# BORING LOG

Page \_\_\_\_ of \_\_\_\_

PROJECT NAME:  
PROJECT NUMBER:  
DRILLING COMPANY:  
DRILLING RIG:

Site 25  
Columbia  
Geoprobe 5400

BORING NUMBER: CNC25B06  
DATE: 6-5-99  
GEOLOGIST:  
DRILLER: B. Lewis

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
				0.8			Asphalt		Sampled Soil				
							Lime Rock		from 4.0-5.0				
							Greenish Gray silty clay		# 255FB060405				
232	4	2.0							Time @ 1034				
				5.5			Gray silty, clay, coarse		Moist				
				6.5			sand wet		Wet				
1034	8	3.0		7.5			Greenish Gray silty Gky		Moist				
							Red gray sandy clay						
							tr. of silt (moist)		Set Screen				
									from 8.0'-11.0'				
				12.0			W/L = 9.2'						
				B.T.					Sampled Water				
									# 255FB060451				
									Time @ 1045				

H.S. W/fil = 1400  
H.S. W/fil = 280 pp  
H.S. W/fil = 700 pp  
H.S. W/fil = 160 pp

\* When rock coring, enter rock brokenness.

\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks:

Drilling Area  
Background (ppm):

Converted to Well: Yes \_\_\_\_\_ No \_\_\_\_\_ Well I.D. #: \_\_\_\_\_

## Page \_\_\_\_ of \_\_\_\_

[illegible]

Converted to Well:	Yes	No	Well I.D. #:
--------------------	-----	----	--------------

Drilling Area  
Background (ppm):



## Page \_\_\_\_ of \_\_\_\_

Site 25  
Columbia  
Geoprobe 8400

BORING NUMBER: CXG25B08  
DATE: 5-5-99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: B. Lewis

[illegible]

\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Drilling Area  
Background (ppm):

Yes

No

Well I.D. #:



## Page \_\_\_\_ of \_\_\_\_

[illegible]

Converted to Well:    Yes                  No                  Well I.D. #: \_\_\_\_\_

## Page \_\_\_\_ of \_\_\_\_

BORING NUMBER: CNC 25B11  
DATE: 6-7-99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: R. Brown

[illegible]

Drilling Area  
Background (ppm):

Converted to Well: Yes ☐ No ☐ Well I.D. #: \_\_\_\_\_



## Page \_\_\_\_ of \_\_\_\_

BORING NUMBER: CAC 25 B13  
DATE: 6-7-99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: R. Brand

[illegible]

\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Drilling Area  
Background (ppm):

Converted to Well:    Yes        No        Well I.D. #:

## Page \_\_\_\_ of \_\_\_\_

DRILLER: R. Brand

$$H.S. \frac{w}{|F_i|} = 900$$

$$H.S. \frac{w}{|F_i|} = 80$$

Converted to Well:	Yes	No	Well I.D. #:
--------------------	-----	----	--------------

## Page \_\_\_\_ of \_\_\_\_

Site 25

BORING NUMBER: 2 CNC25 B15

**DATE:**

67-92

GRAND DISC

**GEOLOGIST:**

**DRILLER:**

R. Brand.

[illegible]

\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Drilling Area  
Background (ppm):

Yes

**No**

Well I.D. #:



## Page \_\_\_\_ of \_\_\_\_

[illegible]

Converted to Well: Yes ☐ No ☐ Well I.D. #: \_\_\_\_\_



Page 1 of 1

DRILLER: H. Grant

Well I.D. #:

Page 1 of 1

BORING NUMBER: 25 B 19  
DATE: 6/19/99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: R. B. and

140

Converted to Well: Yes Temp No        Well I.D. #:

Page 1 of 1

BORING NUMBER: 25 B26  
DATE: 6/14/99  
GEOLOGIST: \_\_\_\_\_  
DRILLER: R. Brown

१५४

Well I.D. #:

**DRILLER:**

Converted to Well: Yes Yes No Well I.D. #:

Page 1 of 1

CNE BORING NUMBER: 25B ~~22~~ 22  
DATE: 2 8 99  
Columbia GEOLOGIST: R. Franklin  
hand auger / Stratoprog DRILLER: R. Brand

Converted to Well: Yes Temp No          Well I.D. #:





Page 1 of 1

BORING NUMBER: 25 B 24  
DATE: 7 8 79  
GEOLOGIST:  
DRILLER: Rudy Ruppel

\* When rock coring, enter rock brokenness.

**\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.**

Remarks:

Drilling Area  
Background (ppm): 10

Converted to Well: Yes Temp No \_\_\_\_\_ Well I.D. #: \_\_\_\_\_

Page 1 of 1

BORING NUMBER: ZS BZS

DATE: 7/24/99

**GEOLOGIST:**

DRILLER: T. Hunt

\* When rock coring, enter rock brokenness.

\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks:

Drilling Area  
Background (ppm): 0

Converted to Well: Yes Temp No \_\_\_\_\_ Well I.D. #: \_\_\_\_\_

Page 1 of 1

**DRILLER:**

Converted to Well: Yes Temp No \_\_\_\_\_ Well I.D. #: \_\_\_\_\_

## Page 1 of 1

BORING NUMBER: 25B27

DATE: 5/3/94

**GEOLOGIST:**

DRILLER: J. Brune

\* When rock coring, enter rock brokenness.

\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks:

Converted to Well: Yes Turn No Well I.D. #:

Drilling Area  
Background (ppm): 1

Page 1 of 1

PROJECT NAME: CNE BORING NUMBER: 25 B 28  
PROJECT NUMBER: \_\_\_\_\_ DATE: 8/3/99  
DRILLING COMPANY: Cotnam GEOLOGIST: \_\_\_\_\_  
DRILLING RIG: Star-top DRILLER: A. Brown

[illegible]

\*\*\* Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Drilling Area  
Background (ppm): 6

Converted to Well: Yes True No        Well I.D. #:

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name: <u>CNC25</u> Project No.: <u>2219</u>  <input type="checkbox"/> Surface Soil <input checked="" type="checkbox"/> Subsurface Soil <input type="checkbox"/> Sediment <input type="checkbox"/> Other: <input type="checkbox"/> QA Sample Type:	Sample ID No.: <u>255613090304</u> Sample Location: <u>B09</u> Sampled By: _____ C.O.C. No.: _____  Type of Sample: <input type="checkbox"/> Low Concentration <input checked="" type="checkbox"/> High Concentration
---	--

**GRAB SAMPLE DATA:**

Date:	Time:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99	0858	3.0-4.0'	Red & Gray	Red & Gray Sandy, Silty Clay Moist
Method: DPT				
Monitor Reading (ppm): 106				

**COMPOSITE SAMPLE DATA:**

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99		0	1.3	Asphalt.
Method: DPT		3	1.0	Sub Base
		1.0	5.0	Red & Gray silty, Sandy Clay.
		5.0	6.0	" " " " " Moist
Monitor Readings (Range in ppm):		6.0	8.0	Gray to Tan clay sand & gravel Wet
W/Fil = 120				
W/Fil = 14 ppm				

**SAMPLE COLLECTION INFORMATION:**

Analysis	Container Requirements	Collected	Other
BTEX/EDB	4 encore	6-7-99	
Lead	1-4 oz jar		
PAH	1-4 oz jar		

<b>OBSERVATIONS / NOTES:</b>  <div style="text-align: center; font-size: 1.2em;">Total Depth = 12.0'</div>	<b>MAP:</b>  <div style="text-align: center; font-size: 1.5em;">J. Q. K.</div>
Circle if Applicable: <input type="checkbox"/> MS/MSD      Duplicate ID No.:	Signature(s):



# SOIL & SEDIMENT SAMPLE LOG SHEET

Page    of   

Project Site Name: CNC 25  
Project No.: 0219

Sample ID No.: 25SLB110203  
Sample Location: B11  
Sampled By: RF  
C.O.C. No.:                     

- ☐ Surface Soil  
☒ Subsurface Soil  
☐ Sediment  
☐ Other:                       
☐ QA Sample Type:

Type of Sample:  
☐ Low Concentration  
☒ High Concentration

## GRAB SAMPLE DATA:

Date:	Time:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99	0935	2.0-3.0	Brown	clayey sand
Method: DPT				
Monitor Reading (ppm): 1610				

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99		0	0.3	Asphalt
Method: DPT		0.3	1.5	Sub Base
		1.5	2.0	Brown clayey sand
Monitor Readings (Range in ppm): w/ Fil = 7500 w/ Fil = 90		2.0	5.0	gray coarse sand moist
		5.0	8.0	Wet

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
BTEX / EOB	4-Encore	6-7-99	
PAH	1-4 oz Jar		
Lead	1-4 oz Jar	↓	

## OBSERVATIONS / NOTES:

0-4' = 2.2 Rec.  
4-8' = 3.0'  
  
Total Depth 12.0' ~~7.0'~~

## MAP:

*(Blank map area)*

## Circle if Applicable:

MS/MSD ☐ Duplicate ID No.:                     

## Signature(s):

*J. Or N. H.*



# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name:	<u>CNG25</u>	Sample ID No.:	<u>256LB120703</u>
Project No.:	<u>0219</u>	Sample Location:	<u>B12</u>
<input type="checkbox"/> Surface Soil		Sampled By:	<u>R.F.</u>
<input checked="" type="checkbox"/> Subsurface Soil		C.O.C. No.:	<u>                    </u>
<input type="checkbox"/> Sediment		Type of Sample:	
<input type="checkbox"/> Other:	<u>                    </u>	<input type="checkbox"/> Low Concentration	
<input type="checkbox"/> QA Sample Type:	<u>                    </u>	<input checked="" type="checkbox"/> High Concentration	

## GRAB SAMPLE DATA:

Date:	Time:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
<u>6-7-99</u>	<u>1015</u>	<u>2.0-3.0</u>	<u>Gray</u>	<u>Silty clay w/ layers of sand.</u>
Method:	<u>DPT</u>			
Monitor Reading (ppm):				

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
<u>6-7-99</u>	<u>1013</u>	<u>0</u>	<u>.2</u>	<u>Asphalt</u>
Method:	<u>DPT</u>	<u>.2</u>	<u>1.0</u>	<u>Sub base</u>
Monitor Readings		<u>1.0-3.5</u>	<u>Gray</u>	<u>Silty clay w/ layers of med. sand</u>
(Range in ppm):		<u>3.5-8.0</u>	<u>Gray</u>	<u>f. to med sand to clay wet</u>
<u>w/F:1 = 75000</u>				
<u>w/F:1 = 210</u>				


## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
<u>BTX / EDB</u>	<u>4 - Encore</u>	<u>6-7-99</u>	
<u>PAH</u>	<u>1 - 4oz jar</u>	<u>↓</u>	
<u>Lead</u>	<u>1 - 4oz jar</u>		
<u>Grain Size</u>	<u>2 - 32oz jars</u>		

## OBSERVATIONS / NOTES:

Rec 0'-4' = 2.5'  
 4'-8' = 3.0'  
 Grain Size from 2.0'-3.0' & 7.0'-8.0'  
 Total Depth: 12.0'

## MAP:



## Circle if Applicable:

MS/MSD	Duplicate ID No.:
--------	-------------------

## Signature(s):

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page    of   

Project Site Name: <u>CNC25</u>		Sample ID No.: <u>255LB130203</u>
Project No.: <u>6219</u>		Sample Location: <u>R13</u>
		Sampled By: <u>RF</u>
		C.O.C. No.: <u>          </u>
<input type="checkbox"/> Surface Soil <input checked="" type="checkbox"/> Subsurface Soil <input type="checkbox"/> Sediment <input type="checkbox"/> Other: <u>          </u> <input type="checkbox"/> QA Sample Type: <u>          </u>		Type of Sample: <input type="checkbox"/> Low Concentration <input checked="" type="checkbox"/> High Concentration

## GRAB SAMPLE DATA:

Date:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
<u>6-7-99</u>			
Time: <u>1040</u>			
Method:	<u>2.0-3.0</u>	<u>Brown</u>	<u>Clayey Sand Tr. Gravel</u>
Monitor Reading (ppm):			

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
<u>6-7-99</u>	<u>1030</u>	<u>0-0.3</u>		<u>Asphalt</u>
Method:		<u>0.3-1.0</u>		<u>Sub base</u>
<u>DPT</u>		<u>1.0-2.0</u>	<u>Brown</u>	<u>Clayey Sand Tr. gravel</u>
Monitor Readings		<u>3.0-8.0</u>	<u>Gray</u>	<u>Gravelly f. to med Sand - 62%</u>
(Range in ppm):				
<u>% F.I. = 75000</u>				
<u>% F.I. = 700</u>				

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
<u>BTEX / EDB</u>	<u>8 - Encore</u>	<u>6-7-99</u>	
<u>PAH</u>	<u>2 - 402 Jars</u>		
<u>Lead</u>	<u>2 - 4 " "</u>		
<u>TPH</u>	<u>2 - 4 " "</u>	<u>↓</u>	

## OBSERVATIONS / NOTES:

Rec 0-4' = 2.5'  
4-8' = 2.8'  
  
Total Depth = 16.0'

## MAP:

## Circle if Applicable:

MS/MSD	Duplicate ID No.: <u>255LB130203D</u>
--------	---------------------------------------

## Signature(s):

J. R. Hill

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name: CNC 25  
Project No.: 0219

Sample ID No.: 255LB140304  
Sample Location: RM  
Sampled By: RF  
C.O.C. No.:                     

- ☐ Surface Soil  
☒ Subsurface Soil  
☐ Sediment  
☐ Other:                       
☐ QA Sample Type:

Type of Sample:  
☐ Low Concentration  
☒ High Concentration

## GRAB SAMPLE DATA:

Date:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99	3.0'-4.0'	Light Gray	Fine to med. Sand
Time: <u>1055</u>			
Method:			
Monitor Reading (ppm):			

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99		0 - 0.2	Black	Asphalt
		0.2 - 1.5	Gray	Sub base
Method: <u>DPT</u>		1.5 - 5.0	Light Gray	F. to med. Sand. Moist
Monitor Readings		5.0 - 8.0	" "	" " " Wet
(Range in ppm):				
4/FI = 900				
W/FI = 80				

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
BTEX/EDB	4-Encore	6-7-99	
PAH	1-402 jar	↓	
Lead	1-402 jar	↓	

## OBSERVATIONS / NOTES:

## MAP:

Rec. 0'-4' = 2.8

Total Depth = 8.0

## Circle if Applicable:

## Signature(s):

MS/MSD

Duplicate ID No.:

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name: CNC 25  
Project No.: 0219

Sample ID No.: 25SLB150304  
Sample Location: B15  
Sampled By: RF  
C.O.C. No.:     

- ☐ Surface Soil  
☒ Subsurface Soil  
☐ Sediment  
☐ Other:  
☐ QA Sample Type:

Type of Sample:  
☐ Low Concentration  
☒ High Concentration

## GRAB SAMPLE DATA:

Date:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99	3.0-4.0	Orange Gray	Fine to med. sand Tr. gravel
Time: 1115			
Method: DPT			
Monitor Reading (ppm): 150			

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99		0-0.2	Black	Asphalt
		0.2-1.0		Sub base
Method: DPT		1.0-4.0	Orange Gray	Fine to Med Sand - Tr. gravel
Monitor Readings				
(Range in ppm):				
4/6 F.I. = 190				
4/6 F.I. = 40				

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
BTEX/EDB	4 Encores		
PAH	1-4 oz jar		
Lead	1-4 oz jar		
TOC/POC	2-4 oz jar		

## OBSERVATIONS / NOTES:

## MAP:

Reg 0-4 = 2.7

Duped The TOC/POC only

Total Depth 4.0'

## Circle if Applicable:

## Signature(s):

MS/MSD

Duplicate ID No.:

TOC/POC only 25SLB150304D

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name: <u>CNC25</u> Project No.: <u>0219</u>  <input type="checkbox"/> Surface Soil <input checked="" type="checkbox"/> Subsurface Soil <input type="checkbox"/> Sediment <input type="checkbox"/> Other: _____ <input type="checkbox"/> QA Sample Type: _____	Sample ID No.: <u>25SLB160304</u> Sample Location: <u>B16</u> Sampled By: <u>RF</u> C.O.C. No.: _____  Type of Sample: <input type="checkbox"/> Low Concentration <input type="checkbox"/> High Concentration
---	--

## GRAB SAMPLE DATA:

Date:	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99			
Time: <u>1330</u>			
Method: <u>DPT</u>	<u>3.0'-4.0'</u>	<u>orange &amp; grey</u>	<u>sandy clay Tr. of Silt</u>
Monitor Reading (ppm):			

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
6-7-99	1330	0-2.0	Brown	fine to med sand
Method: <u>DPT</u>		2.0-4.0	orange & grey	sandy clay Tr. of Silt
Monitor Readings				
(Range in ppm):				
<u>4/Fil = 460</u>				
<u>4/Fil = 210</u>				

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
<u>BTEX / EDB</u>	<u>4 - Encase</u>	<u>6-7-99</u>	
<u>PAN</u>	<u>1 - 402 Jar</u>	<u>✓</u>	
<u>Lead</u>	<u>1 - " " "</u>	<u>✓</u>	

## OBSERVATIONS / NOTES:

## MAP:

<p><u>Rec 0'-4' = 3.0'</u></p>   <p><u>Total Depth = 4.0'</u></p>	Signature(s): 
Circle if Applicable: <input type="checkbox"/> MS/MSD	Duplicate ID No.: _____

# SOIL & SEDIMENT SAMPLE LOG SHEET

Page      of     

Project Site Name: <u>CNC 25</u>		Sample ID No.: <u>255HB170304</u>
Project No.: <u>0219</u>		Sample Location: <u>B17</u>
		Sampled By: <u>R.F.</u>
<input type="checkbox"/> Surface Soil <input checked="" type="checkbox"/> Subsurface Soil <input type="checkbox"/> Sediment <input type="checkbox"/> Other: _____ <input type="checkbox"/> QA Sample Type: _____		C.O.C. No.: _____
		Type of Sample: <input type="checkbox"/> Low Concentration <input type="checkbox"/> High Concentration

## GRAB SAMPLE DATA:

Date: <u>6-7-97</u>	Depth: <u>3.0'-4.0'</u>	Color: _____	Description (Sand, Silt, Clay, Moisture, etc.): _____
Time: <u>1352</u>			
Method: <u>DPT</u>			
Monitor Reading (ppm): _____			

## COMPOSITE SAMPLE DATA:

Date:	Time	Depth	Color	Description (Sand, Silt, Clay, Moisture, etc.)
<u>6-7-97</u>	<u>1355</u>	<u>0 - 0.2</u>		<u>Asphalt</u>
Method: <u>DPT</u>		<u>0.2 - 1.0</u>		<u>Sub base</u>
		<u>1.0 - 4.0</u>		<u>Orange &amp; Gray Sandy Clay fr. silt</u>
Monitor Readings				
(Range in ppm):				
<u>6 1/2 Fil = 75000</u>				
<u>W/Fil = 100</u>				

## SAMPLE COLLECTION INFORMATION:

Analysis	Container Requirements	Collected	Other
<u>BTEX / EDB</u>	<u>4 - ENCORE</u>	<u>6-7-97</u>	
<u>PAH</u>	<u>1-402 Jar</u>	<u>↓</u>	
<u>Lead</u>	<u>1-402 Jar</u>	<u>↓</u>	

## OBSERVATIONS / NOTES:

<u>Rec 0'-4.8 = 3.6'</u>  <u>Total Depth = 4.0'</u>		MAP: _____  Signature(s): <u>J. R. [Signature]</u>
Circle if Applicable:		
MS/MSD	Duplicate ID No.:	

# GROUNDWATER SAMPLE LOG SHEET

Page      of     

Project Site Name: Zone F  
Project No.: 0019

Sample ID No.: 25GLMP101

Sample Location: CNC 25MW1

Sampled By: JAL/JE

C.O.C. No.:                     

Type of Sample:                     

- ☐ Domestic Well Data  
☒ Monitoring Well Data  
☐ Other Well Type:                       
☐ QA Sample Type:

- ☐ Low Concentration  
☐ High Concentration

## SAMPLING DATA:

Date: <u>9-21-99</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: <u>1245</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: <u>Peristaltic</u>	<u>clear</u>	<u>6.50</u>	<u>1.04</u>	<u>25.9</u>	<u>-10</u>	<u>0.21</u>	<u>    </u>	<u>    </u>

## PURGE DATA:

Date: <u>9 21 99</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Peristaltic</u>	Initial	<u>6.40</u>	<u>.788</u>	<u>24.9</u>	<u>-10</u>	<u>1.04</u>		
Monitor Reading (ppm): <u>    </u>	1	<u>6.66</u>	<u>.796</u>	<u>25.5</u>	<u>-10</u>	<u>2.54</u>		
Well Casing Diameter & Material	2	<u>6.50</u>	<u>0.94</u>	<u>26.0</u>	<u>-10</u>	<u>0.48</u>		
Type: <u>2" PVC</u>	3	<u>6.55</u>	<u>0.99</u>	<u>26.3</u>	<u>-10</u>	<u>0.97</u>		
Total Well Depth (TD): <u>11.02</u>	4	<u>6.50</u>	<u>1.04</u>	<u>25.9</u>	<u>-10</u>	<u>0.21</u>		
Static Water Level (WL): <u>1.23</u>								
One Casing Volume (gal/L): <u>1.6</u>								
Start Purge (hrs): <u>1045</u>								
End Purge (hrs): <u>1200</u>								
Total Purge Time (min): <u>75 min</u>								
Total Vol. Purged (gal/L): <u>~4.5 gal</u>								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
<u>TCL Volatiles</u>	<u>HCl/40C</u>	<u>(3) 40 mL vials</u>	<u>YES</u>
<u>Dissolved Methane</u>	<u>HCl/40C</u>	<u>(3) 40 mL vials</u>	<u>YES</u>
<u>Lead</u>	<u>HNO3/40C</u>	<u>(1) 250 mL plastic</u>	<u>YES</u>
<u>PAHs</u>	<u>40C</u>	<u>(2) 1 L Amber</u>	<u>YES</u>
<u>Anions</u>	<u>40C</u>	<u>(1) 500 mL plastic</u>	<u>YES</u>

## OBSERVATIONS / NOTES:

11.02  
1.23  
9.79

9.79

Circle if Applicable:

MS/MSD

Duplicate ID No.:                     

Signature(s):

*[Handwritten Signature]*

## Page\_\_ of \_\_

Sample ID No.: 25GLMU301  
Sample Location: MHF3  
Sampled By: R.N.  
C.O.C. No.:  
Type of Sample:  
☐ Low Concentration  
☐ High Concentration

☐ Domestic Well Data  
☒ Monitoring Well Data  
☐ Other Well Type:  
☐ QA Sample Type:

Date: 7-12-99	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: 1510	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: Slow Pace	Sec	8.1	5					

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Slow Purge</u>	Initial	4.87	1.22	29.3	377	1.76		
Monitor Reading (ppm):	1	5.38	1.06	29.7	60	1.69		
Well Casing Diameter & Material	2	5.20	1.14	29.5	28	1.88		
Type:	3	5.08	1.23	29.9	25	1.43		
Total Well Depth (TD): <u>12.35</u>								
Static Water Level (WL): <u>5.90</u>								
One Casing Volume (gal/ft): <u>1.06</u>								
Start Purge (hrs): <u>11/48</u>								
End Purge (hrs): <u>11/46:30</u>	<u>1300</u>							
Total Purge Time (min):								
Total Vol. Purged (gal/L): <u>4.00</u>	<u>gal/15</u>							

[illegible][illegible]

**Signature(s):**

**Duplicate ID No.:**



## Page of

CNCA25

Sample ID No.: 25GLM040

Sample Location: MW-C

Sampled By: RA

**C.O.C. No.:**

**Type of Sample:**

## Domestic Well Data

### ~~X~~ Monitoring Well Data

(1) Other Well Type:

QA Sample Type:

### Low Concentration

**High Concentration**

Date: 9-13-91	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: 1145	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: gravimetric	clear	6.00	2.06	28.6	0	1.22		

**PURGE DATA:**

Date: 9-13-99

Method: Slow Purge

**Monitor Reading (ppm):**

### Well Casing Diameter & Material

Type: 2" PVC.

Total Well Depth (TD): 12.16'

Static Water Level (WL): 5.95

One Casing Volume(gal): 1.0

Start Purge (hrs): 09.52

End Purge (hrs): 1057

**Total Purge Time (min):**

Total Vol. Purged (gal/hr): 3.5

**SAMPLE COLLECTION INFORMATION:**

[illegible]**OBSERVATIONS / NOTES:**

**Circle if Applicable:**

MS/MSD

**Duplicate ID No.:**

**Signature(s):**

## GROUNDWATER SAMPLE LOG SHEET

Page 1 of 1Project Site Name: Zone FProject No.: 0019

- ☐ Domestic Well Data  
☒ Monitoring Well Data  
☐ Other Well Type:  
☐ QA Sample Type:

Sample ID No.: 25GLM0701501Sample Location: CNC 25 MW 3.5Sampled By: JAJE

C.O.C. No.:

Type of Sample:

- ☐ Low Concentration  
☐ High Concentration

## SAMPLING DATA:

Date: <u>9-21-99</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: <u>1705</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: <u>Peristaltic</u>	<u>clear</u>	<u>5.33</u>	<u>0.269</u>	<u>29.7</u>	<u>0</u>	<u>5.45</u>	<u>—</u>	<u>—</u>

## PURGE DATA:

Date: <u>9-21-99</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Peristaltic</u>	Initial	<u>5.11</u>	<u>0.194</u>	<u>29.9</u>	<u>0</u>	<u>0.57</u>		
Monitor Reading (ppm): <u>—</u>	1	<u>5.11</u>	<u>0.198</u>	<u>30.3</u>	<u>0</u>	<u>1.07</u>		
Well Casing Diameter & Material	2	<u>5.31</u>	<u>0.248</u>	<u>29.8</u>	<u>0</u>	<u>0.86</u>		
Type: <u>4" PVC</u>	3	<u>5.29</u>	<u>0.272</u>	<u>28.8</u>	<u>0</u>	<u>2.22</u>		
Total Well Depth (TD): <u>12.05</u>	<u>3.54</u>	<u>5.33</u>	<u>0.269</u>	<u>29.7</u>	<u>0</u>	<u>5.45</u>		
Static Water Level (WL): <u>4.54</u>								
One Casing Volume (gal/L): <u>4.9 gal</u>								
Start Purge (hrs): <u>1522</u>								
End Purge (hrs): <u>1716</u>								
Total Purge Time (min): <u>114 min</u>								
Total Vol. Purged (gal/L): <u>18 gal</u>								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
<u>TCH Volatiles</u>	<u>HCl/4°C</u>	<u>(3) 40 ml vials</u>	<u>yes</u>
<u>Dissolved Methane</u>	<u>HCl/4°C</u>	<u>(3) 40 ml vials</u>	
<u>Lead</u>	<u>HNO<sub>3</sub>/4°C</u>	<u>(1) 250ml plastic</u>	
<u>PAHs</u>	<u>4°C</u>	<u>(2) 1 L Amber</u>	
<u>Anions</u>	<u>4°C</u>	<u>(1) 500 ml plastic</u>	<u>↓</u>

## OBSERVATIONS / NOTES:

product sheen on the surface of the purge water bucket

Circle if Applicable:

MS/MSD

Duplicate ID No.:

25 GL 25GLM0501D

Signature(s):

**Page**        **of**       

### High Concentration

**Signature(s):**

# GROUNDWATER SAMPLE LOG SHEET

Page      of     

Project Site Name: CNC 25  
Project No.:                     

- ☐ Domestic Well Data  
☒ Monitoring Well Data  
☐ Other Well Type:                       
☐ QA Sample Type:

Sample ID No.: 2561M0701  
Sample Location: MW-7  
Sampled By: RI  
C.O.C. No.:                       
Type of Sample:  
☐ Low Concentration  
☐ High Concentration

## SAMPLING DATA:

Date: <u>9-13-99</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: <u>1115</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: <u>Gooping</u>	<u>Clear</u>	<u>5.55</u>	<u>1.18</u>	<u>28.6</u>	<u>0</u>	<u>1.10</u>		

## PURGE DATA:

Date: <u>9-13-99</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Slow Purge</u>	Initial	<u>5.56</u>	<u>2.56</u>	<u>27.2</u>	<u>418</u>	<u>1.16</u>		
Monitor Reading (ppm):	1	<u>5.58</u>	<u>1.16</u>	<u>28.3</u>	<u>4</u>	<u>1.21</u>		
Well Casing Diameter & Material	2	<u>5.57</u>	<u>1.27</u>	<u>28.5</u>	<u>2</u>	<u>1.07</u>		
Type: <u>2" PVC</u>	3	<u>5.56</u>	<u>1.18</u>	<u>28.6</u>	<u>2</u>	<u>1.11</u>		
Total Well Depth (TD): <u>12.30</u>								
Static Water Level (WL): <u>6.50</u>								
One Casing Volume (gal): <u>.98</u>								
Start Purge (hrs): <u>0949</u>								
End Purge (hrs): <u>1048</u>								
Total Purge Time (min):								
Total Vol. Purged (gal/L): <u>3 gal.</u>								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
<u>BTEX, MTBE, EDB, Naph</u>	<u>HCl</u>	<u>3 x 40 ml vials</u>	<u>9-13-99</u>
<u>Dissolved Methane</u>	<u>HCl</u>	<u>" " "</u>	<u>"</u>
<u>PAH</u>	<u>—</u>	<u>2 x 1 L amber</u>	<u>"</u>
<u>Anions</u>	<u>—</u>	<u>1 x 500 ml plastic</u>	<u>"</u>
<u>Total Pb</u>	<u>HNO3</u>	<u>1 - 250 ml</u>	<u>"</u>

Resampled  
9/21/99

## OBSERVATIONS / NOTES:

Circle if Applicable:

MS/MSD

Duplicate ID No.:                     

Signature(s):

## GROUNDWATER SAMPLE LOG SHEET

Page 1 of 1
 Project Site Name: Cove F  
 Project No.: 0219
Sample ID No.: 25GLM0701Sample Location: CNC 25 MW7Sampled By: JA/E

C.O.C. No.: \_\_\_\_\_

Type of Sample: \_\_\_\_\_

☐ Domestic Well Data☒ Monitoring Well Data☐ Other Well Type: \_\_\_\_\_☐ QA Sample Type: \_\_\_\_\_☐ Low Concentration☐ High Concentration

## SAMPLING DATA:

Date: <u>9-21-99</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: _____	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: <u>Peristaltic</u>	<u>clear</u>	<u>5.33</u>	<u>0.686</u>	<u>29.2</u>	<u>0</u>	<u>5.88</u>	—	—

## PURGE DATA:

Date: <u>9-21-99</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Peristaltic</u>	Initial	<u>5.62</u>	<u>2.50</u>	<u>28.4</u>	<u>95</u>	<u>5.03</u>		
Monitor Reading (ppm): _____	1	<u>5.33</u>	<u>0.774</u>	<u>29.2</u>	<u>0</u>	<u>4.08</u>		
Well Casing Diameter & Material	2	<u>5.31</u>	<u>0.735</u>	<u>29.2</u>	<u>0</u>	<u>4.62</u>		
Type: <u>2" PVC</u>	3	<u>5.33</u>	<u>0.686</u>	<u>29.2</u>	<u>0</u>	<u>5.88</u>		
Total Well Depth (TD): <u>12.36</u>								
Static Water Level (WL): <u>6.41</u>								
One Casing Volume (gal/L): <u>1 gal</u>								
Start Purge (hrs): <u>1513</u>								
End Purge (hrs): <u>1540</u>								
Total Purge Time (min): <u>27 min</u>								
Total Vol. Purged (gal/L): <u>4 gal</u>								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
<u>TCL Volatiles</u>	<u>HCl / 4°C</u>	<u>(3) 40 ml vials</u>	<u>yes</u>
<u>Dissolved methane</u>	<u>HCl / 4°C</u>	<u>(3) 40 ml vials</u>	<u>yes</u>
<u>Lead</u>	<u>HNO<sub>3</sub> / 4°C</u>	<u>(1) 250 ml plastic</u>	<u>yes</u>
<u>PAHS</u>	<u>4°C</u>	<u>(2) 1 L Amber</u>	<u>yes</u>
<u>Anions</u>	<u>4°C</u>	<u>(1) 500 ml plastic</u>	<u>yes</u>

## OBSERVATIONS / NOTES:

Sample Bottles were already taken in the previous session

Circle if Applicable:

MS/MSD

Duplicate ID No.: \_\_\_\_\_

Signature(s)

# GROUNDWATER SAMPLE LOG SHEET

Page    of   

Project Site Name: CNG25  
Project No.:                     

Sample ID No.: 25GLM0801

Sample Location: MW-8

Sampled By: R.H.

C.O.C. No.:                     

☐ Domestic Well Data

☒ Monitoring Well Data

☐ Other Well Type:                     

☐ QA Sample Type:                     

Type of Sample:

☐ Low Concentration

☐ High Concentration

## SAMPLING DATA:

Date: <u>9-12-99</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
Time: <u>255</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Method: <u>Geopump</u>	<u>Sec.</u>	<u>RC1042</u>						

## PURGE DATA:

Date: <u>9-12-99</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
Method: <u>Slow Purge</u>	Initial	<u>5.28</u>	<u>2.54</u>	<u>28.6</u>	<u>441</u>	<u>1.59</u>		
Monitor Reading (ppm):	<u>.1</u>	<u>5.38</u>	<u>1.06</u>	<u>29.2</u>	<u>60</u>	<u>1.69</u>	<u>5054</u>	
Well Casing Diameter & Material	<u>1 3/8</u>	<u>5.59</u>	<u>2.18</u>	<u>28.7</u>	<u>38</u>	<u>1.54</u>		
Type: <u>2" PVC</u>	<u>2 3/8</u>	<u>5.41</u>	<u>2.32</u>	<u>28.5</u>	<u>35</u>	<u>1.54</u>		
Total Well Depth (TD): <u>12.20</u>	<u>3</u>	<u>5.36</u>	<u>2.40</u>	<u>28.7</u>	<u>35</u>	<u>1.53</u>		
Static Water Level (WL): <u>3.85</u>								
One Casing Volume (gal/L): <u>1.38</u>								
Start Purge (hrs): <u>1212</u>								
End Purge (hrs): <u>1317</u>								
Total Purge Time (min):								
Total Vol. Purged (gal/L): <u>4.00</u>	<u>gals.</u>							

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
<u>RTX, MTBE, EDB, Naph</u>	<u>HCl</u>	<u>3X 40ml vials</u>	<u>9-12-99</u>
<u>PAH</u>		<u>2X 1L amber</u>	<u>"</u>
<u>Total Lead</u>	<u>HNO3</u>	<u>1X 250ml plastic</u>	<u>"</u>

## OBSERVATIONS / NOTES:

Circle if Applicable:

Signature(s):

MS/MSD

Duplicate ID No.:

## GROUNDWATER SAMPLE LOG SHEET

Page 1 of 1Project Site Name: Zone FProject No.: 0219Sample ID No.: 25GLX0201Sample Location: CPE 25-X-02 609002Sampled By: JAL/JEC.O.C. No.: 7C

Type of Sample:

☐ Low Concentration☐ High Concentration☐ Domestic Well Data☒ Monitoring Well Data☐ Other Well Type: \_\_\_\_\_☐ QA Sample Type: \_\_\_\_\_

## SAMPLING DATA:

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
9-21-99	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Time: 1615	clear	6.70	4.09	20.0	3	0.11	—	—
Method: Peristaltic	orange							

## PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
9-21-99	Initial	6.43	2.98	20.3	18	0.78	0.14	—
Method: Peristaltic	1	6.51	2.27	27.3	6	0.30	0.10	—
Monitor Reading (ppm): —	2	6.61	3.59	26.5	71	0.45	0.18	turned pump down b/c it was drawn down
Well Casing Diameter & Material Type: 2" PVC	stop pump at 1200							
Total Well Depth (TD): 11.59	restart at 1513							
Static Water Level (WL): 5.19	3.65							
One Casing Volume (gal): 1.36	3	6.83	3.69	26.4	137	6.23		stop pump at 1534
Start Purge (hrs): 1040	4	6.70	4.09	20.0	3	0.11	—	
End Purge (hrs): 1609								
Total Purge Time (min): ~2 hrs								
Total Vol. Purged (gal/L): ~4 gal								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL Volatiles	HCl/4°C	(3) 40 ml vials	yes
PHS	4°C	(2) 1L Amber	yes
Lead	HNO <sub>3</sub> /4°C	(1) 250ml plastic	yes
NA Parameters			
TCL Volatiles			
Lead JE			

## OBSERVATIONS / NOTES:

Well continued to run dry after stopping & restarting the pump 4 times--we sampled

Circle if Applicable:

MS/MSD

Duplicate ID No.: \_\_\_\_\_

Signature(s):



## GROUNDWATER SAMPLE LOG SHEET

Page 1 of 1

Project Site Name: <u>Zone F</u>	Sample ID No.: <u>25GLX0401</u>
Project No.: <u>0219</u>	Sample Location: <u>E-25X02-609004</u>
<input type="checkbox"/> Domestic Well Data	Sampled By: <u>JA/E</u>
<input checked="" type="checkbox"/> Monitoring Well Data	C.O.C. No.: _____
<input type="checkbox"/> Other Well Type: _____	Type of Sample: _____
<input type="checkbox"/> QA Sample Type: _____	<input type="checkbox"/> Low Concentration
	<input type="checkbox"/> High Concentration

## SAMPLING DATA:

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	Salinity	Other
9-21-99	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	%	NA
Time: 1210								
Method: Peristaltic	6.45	0.98	26.6	75	1.77	0.04		

## PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	Salinity	Other
9-21-99	Initial	6.51	0.91	26.8	0	1.60	0.02	
Method: Peristaltic	1	6.49	1.02	26.9	0	0.29	0.04	
Monitor Reading (ppm): -	2	6.48	0.98	26.5	243	1.54	0.04	turned
Well Casing Diameter & Material	3	6.45	0.98	26.6	75	1.77	0.04	
Type: 2" PVC								
Total Well Depth (TD): 13.07								
Static Water Level (WL): 4.12								
One Casing Volume (gal/L): 5.24/126gal								
Start Purge (hrs): 1040								
End Purge (hrs): 1000								
Total Purge Time (min): 80 min								
Total Vol. Purged (gal/L): ~5 gal								

## SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL Volatiles	HCl/4°C	(3) 40 mL vials	yes
PAHs	4°C	(2) 1 L Amber	yes
Lead	HNO <sub>3</sub> /4°C	(1) 250 mL Plastic	yes
<del>NA Parameters</del>			
<del>TCL Volatiles</del>	<del>HCl/4°C</del>	<del>(3) 40 mL vials</del>	<del>yes</del>
<del>Lead</del>	<del>HNO<sub>3</sub>/4°C</del>	<del>(1) 250 mL Plastic</del>	<del>yes</del>
<del>Anions</del>	<del>4°C</del>	<del>(1) mL Plastic</del>	<del>yes</del>

## OBSERVATIONS / NOTES:

Circle if Applicable:

MS/MSD Duplicate ID No.:

Signature(s):

ump down  
bikes it we  
drawing down



**APPENDIX B**

**ANALYTICAL LABORATORY DATA  
SOIL AND GROUNDWATER**



Site 25

GW

October 13, 1999

Mr. Paul Calligan

Tetra Tech Nus

1401 Oven Park Dr.

Suite 102

Tallahassee, FL 32308

MW-03

-04

-06

-07

-08

RE: Katahdin Lab Number: WP3906  
Project ID: CNC Charleston  
Project Manager: Ms. Andrea J. Colby  
Sample Receipt Date(s): 9/14/99

Dear Mr. Calligan:

Please find enclosed the following information:

- \* Report of Analysis
- \* Quality Control Data Summary
- \* Chain of Custody
- \* Confirmation

Should you have any questions or comments concerning this Report of Analysis, please do not hesitate to contact the project manager listed above. This cover letter is an integral part of the ROA.

We appreciate your continued use of our laboratory and look forward to working with you in the future. The following signature indicates technical review and acceptance of the data.

Sincerely,

KATAHDIN ANALYTICAL SERVICES

Patricia Homey  
Authorized Signature

10/13/99  
Date

**SDG NARRATIVE  
KATAHDIN ANALYTICAL SERVICES  
TETRA TECH NUS  
CASE CNC CHARLESTON**

**Sample Receipt**

The following samples were received on September 14, 1999 and were logged in under Katahdin Analytical Services work order number WP3906 for a hardcopy due date of October 14, 1999.

<u>Sample No.</u>	<u>Sample Identification</u>
KATAHDIN	TTNUS
WP3906-1	36GLM0101
WP3906-2	36GLO680004
WP3906-3	36GLM0701
WP3906-4	36GLM0401
WP3906-5	36GLM0501
WP3906-6	42GLM0401
WP3906-7	42GLM0301
WP3906-8	42GLM0201
WP3906-9	42GLM0501
WP3906-10	42GLM1401
WP3906-11	42GLM1701
WP3906-12	42GLM1501
WP3906-13	42GLM1601
WP3906-14	36GLM0201D
WP3906-15	22GLM0101
WP3906-16	22GLM0201
WP3906-17	22GLM0501
WP3906-18	22GLM0701
WP3906-19	42GLM1001
WP3906-20	42GLM1201
WP3906-21	42GLM0801
WP3906-22	42GLM0601
WP3906-23	42GLM0701D
WP3906-24	42GLM0101D
WP3906-25	42GLM1801
WP3906-26	42TL00101
WP3906-27	23TL00201
WP3906-28	36GLM0601
WP3906-29	36GLM0201
WP3906-30	36GLM0301
WP3906-31	42GLM0701
WP3906-32	42GLM0901
WP3906-33	42GLM1101
WP3906-34	42GLM0101

WP3906-35	42GLM1301
WP3906-36	23GLM0401
WP3906-37	23GLX0301
WP3906-38	23GLX0401
WP3906-39	23GLX0401D
WP3906-40	23GLM05D01
WP3906-41	23GLM0101
WP3906-42	25GLM0301
WP3906-43	25GLM0801
WP3906-44	25GLM0601
WP3906-45	25GLM0401
WP3906-46	25GLM0701
WP3906-47	16GLM7D01
WP3906-48	26GLP1201
WP3906-49	26GLP1301

The samples were logged in for the analyses specified on the chain of custody form. All problems encountered and resolved during sample receipt have been documented on the applicable chain of custody forms.

Sample analyses have been performed by the methods as noted herein.

#### Volatile Organic Analysis

Forty-seven aqueous samples were received by the Katahdin Analytical Services, Inc. GC/MS laboratory on September 14, 1999 and were specified to be analyzed by USEPA method 8260B for the analytes benzene, toluene, ethylbenzene, xylenes, MTBE, naphthalene, and EDB.

Analyses for this workorder were performed on the 5973-U and 5970-Q instruments. A VSTD050 (50 ppb standard) was used for the continuing calibration standard. Internal standard and surrogate compounds were also spiked at 50 ppb.

Batch QC (VBLK, and LCS) was performed in each twelve-hour window. Results are included in this data package. The LCS QC samples were spiked with the entire list of compounds quantitated for at 50 ppb. Matrix spike/matrix spike duplicate analyses were performed on samples WP3906-5, -17, and -19.

Analyses of samples WP3906-10, -11, and -13 yielded concentrations of 1,2-dichloroethene (cis) over the upper limit of the calibration curve. Since this was not a requested analyte to be reported by the client, no laboratory action was taken.

Analysis of sample WP3906-19 was performed at a 1:5 dilution due to naphthalene concentrations, resulting in elevated reporting limits.

The initial analysis of sample WP3906-30 was performed outside of the twelve hour BFB tuning window. This was recognized during data review, and the subsequent reanalysis was outside of analytical holding times. Only the reanalysis performed outside of holding times is included in this data package.

Initial analyses of samples WP3906-36 and -44 yielded concentrations of target analytes over the upper limit of the calibration curve. Reanalyses occurred at 1:50 and 1:5 dilutions, respectively. Both sets of data for each sample are included in the data package.

Analysis of the QC samples WP3906-19MS/MSD yielded target analyte concentrations over the upper limit of the calibration curve. In accordance with the method, no laboratory action was taken with these samples.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" (software-generated) on the pertinent quantitation reports. All "M" flags have been dated and initialed by the analyst performing the integration. In addition, all "M" flags have been reviewed and approved by the GC/MS supervisor. Copies of each manual integration are included in the pertinent quantitation reports.

No other protocol deviations were noted by the volatile organics staff.

#### Semivolatile Organic Analysis

Twenty-three aqueous samples were received by Katahdin Analytical Services laboratory on September 14, 1999 for analysis in accordance with 8270C for a client specified PAH list of analytes.

Extraction of samples WP3906 3-12 and 15-18 occurred following USEPA method 3510 on September 16, 1999. A laboratory control spike/laboratory control spike duplicate pair was extracted in the batch. Samples WP3906-13 and -19-25 were extracted following USEPA method 3510 on September 17, 1999. A laboratory control sample, along with a site-specific MS/MSD pair on sample WP3906-19, was extracted in this batch. The remaining sample, WP3906-14, was extracted following USEPA method 3510 on September 20, 1999. A laboratory control sample was also extracted in this batch.

Analysis of sample WP3906-19 yielded a concentration of the analyte naphthalene over the upper limit of the calibration curve. Reanalysis occurred at a 1:2 dilution successfully. Both sets of data for this sample are included in this data package.

Initial analysis of sample WP3906-22 yielded internal standard area recovery deviations. Reanalysis yielded similar results, confirming matrix interference. Both sets of data are included in this data package.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" by the data system. All manual integrations have been dated and initialed by the responsible analyst. Copies of each manual integration are included in the data package. All manual integrations have been reviewed and approved by the GC/MS supervisor.

No other protocol deviations were noted by the semivolatiles organics staff.

### Metals Analysis

The samples of Katahdin Work Order WP3906 were prepared and analyzed for metals in accordance with the "Test Methods for Evaluating Solid Waste", SW-846, November 1986, Third Edition.

### Inductively-Coupled Plasma (ICP) Atomic Emission Spectroscopic Analysis

Aqueous-matrix Katahdin Sample Nos. WP3906- (1-25, 28-46) were digested for ICP analysis on 09/17/99 (QC Batch PI17ICW0), 09/21/99 (QC Batch PI21ICW0), and 09/22/99 (QC Batch PI22ICW0) in accordance with USEPA Method 3010A. Katahdin Sample Nos. WP3906- (19, 46) were prepared with duplicate matrix-spiked aliquots during digestion.

ICP analyses of Katahdin Work Order WP3906 sample digestates were performed in accordance with USEPA Method 6010B, using a Thermo Jarrell Ash (TJA) Trace ICP spectrometer and a TJA 61 ICP spectrometer. All samples were analyzed within holding times and all QC criteria were met with the following comments or exceptions:

Some of the results for run QC samples (ICV, ICB, CCV, CCB, ICSA, and ICSAB) included in the accompanying data package may have exceeded acceptance limits for some elements. Please note that all client samples and batch QC samples associated with out-of-control results for run QC samples were subsequently reanalyzed for the analytes in question.

### Analysis of Mercury by Cold Vapor Atomic Absorption (CVAA) Spectrophotometry

Aqueous-matrix Katahdin Sample Nos. WP3906- (1-25, 28-35) were digested for mercury analysis on 09/22/99 (QC Batch PI22HGW0), 09/25/99 (QC Batch PI25HGW0), and 09/27/99 (QC Batch PI27HGW0) in accordance with USEPA Method 7470A. Katahdin Sample No. WP3906-1 was prepared with a single matrix-spiked aliquot, and Katahdin Sample Nos. WP3906- (19, 21) were prepared with duplicate matrix-spiked aliquots during digestion.

Mercury analyses of Katahdin Work Order WP3906 sample digestates were performed using a Leeman Labs PS200 automated mercury analyzer. All samples were analyzed within holding times and all run QC criteria were met.

### Wet Chemistry Analysis

Due to IC instrument failure, alternate methods were approved for work order WP3906 by Kelly Johnson-Carper for the analysis of nitrate and sulfate. Nitrate analyses (353.2) and Sulfate analyses (375.4) were performed according to the U.S. EPA, Methods for Analysis of Water and Wastes, EPA 600/4-79-020, 1979, Revised 1983. Nitrate analyses (E300) were performed according to the U.S. EPA "Methods for the Determination of Inorganic Substances in Environmental Samples", EPA 600/R-93/100, August 1993. All samples were analyzed within analytical hold times.

The Wet Chemistry staff noted no protocol deviations.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 1 OF 12

COOLER: 1 OF 12

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FED EX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ACC

CLIENT: Tetrahedron NUS

PROJECT: CNC CHARLESTON

	YES	NO	EXCEPTIONS	COMMENTS	RESOLUTION
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TEMP BLANK TEMP (°C) = <u>2.1</u>	
6. SAMPLES RECEIVED AT 4°C ± 2? (ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COOLER TEMP (°C) = <u>NA</u> (RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)	
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
8. TRIP BLANK PRESENT IN THIS COOLER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A		
13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP <u>NFESC</u> ACOE AFCEE OTHER (STATE OF ORIGIN):					

LOG - IN NOTES<sup>(1)</sup>: HNO<sub>3</sub> added to metals aliquot to bring pH < 2: 42 GLM1001, 36 GLM0301, 42 GLM0701, 42 GLM0901, 42 GLM1101, 36 GLM0601, 36 GLM0201, 36 GLM0701, 36 GLM0401, 36 GLM0101, 36 GL0680004, 42 GLM0701 D

<sup>(1)</sup> Use this (and additional sheets if necessary) to document samples that are received broken, compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 2 OF 12

COOLER: 2 OF 12

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ATC

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

*Wm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± .2?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 1.3 *ATC notified Jeff Alexander 9/14/99*

COOLER TEMP (°C) = NA  
(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

\* Sample matching discussed w/ P.M.  
No containers for 2266103010 - Jeff Alexander said to cross  
off COC  
Received Pb bottle for 256610401 - Jeff Alexander said to add to COC

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.



KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 3 OF 12

COOLER: 3 OF 12

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: AJC

CLIENT: Tetradon NUS

PROJECT: CNC CHARLESTON

Wm

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C <u>Y</u> 27	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(ICE) ICE PACKS PRESENT, <u>Y</u> or N?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) 2.6

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, or of pH check if required. If samples required pH adjustment, record volume and type of preservative a

KATAHAN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # W03906

PAGE: 4 OF 12

COOLER: 4 OF 12

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ATC

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

*mm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± 2? (ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 2.0

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

0000222

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3904

PAGE: 5 OF 12

COOLER: 5 OF 12

COC#       

SDG#       

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ALC

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

	YES	NO	EXCEPTIONS	COMMENTS	RESOLUTION
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TEMP BLANK TEMP (°C) = <u>3.2</u>	
6. SAMPLES RECEIVED AT 4°C ± 2° ICE / ICE PACKS PRESENT Y or N?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COOLER TEMP (°C) = <u>NA</u> (RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)	
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A		
13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP <u>NFESC</u> ACOE AFCEE OTHER (STATE OF ORIGIN):					

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this check list (and additional sheets if necessary) to document samples that are received broken, compromised, C-O-C discrepancies, radiation checks, residual chlorine check, re of pH  
checked. If samples required pH adjustment, record volume and type of preservative added.

0000223

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3904

PAGE: 6 OF 12

COOLER: 6 OF 12

COC# —

SDG# —

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BEK

LIMS REVIEW BY / PM: ATC

CLIENT: Tetrahedron NUS

PROJECT: CNC CHARLESTON

*Wm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± 2?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ICE ICE PACKS PRESENT Y or N?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 3.1

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 7 OF 12

COOLER: 7 OF 12

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ASC

*mm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± 2?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ICE ICE PACKS PRESENT Y or N?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 3.0

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WD3906

PAGE: 8 OF 12

COOLER: 8 OF 12

COC# —

SDG# —

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ATC

CLIENT: Tetrahedron NUS

PROJECT: CNC CHARLESTON

*mm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C +/- 2?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 2.2

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 9 OF 12

COOLER: 9 OF 12

COC# —

SDG# —

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FED EX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ASC

CLIENT: Tetratedh NUS

PROJECT: CNC CHARLESTON

	YES	NO	EXCEPTIONS	COMMENTS	RESOLUTION
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TEMP BLANK TEMP (°C) = <u>21</u>	
6. SAMPLES RECEIVED AT 4°C ± 2°?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COOLER TEMP (°C) = <u>NA</u>	
(ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)	
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A		
13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP <u>NFESC</u> ACOE AFCEE OTHER (STATE OF ORIGIN):					

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this page (and additional sheets if necessary) to document samples that are received broken, compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAJIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP3906

PAGE: 10 OF 12

COOLER: 10 OF 12

COC# \_\_\_\_\_

SDG# \_\_\_\_\_

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: AKL

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

*mm*

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± 2°	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) 2.1

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN): \_\_\_\_\_

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.



KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WD3906

PAGE: 11 OF 12

COOLER: 11 OF 12

CLIENT: Tetrahed NUS

PROJECT: CNC CHARLESTON

COC# \_\_\_\_\_

SDG# \_\_\_\_\_

DATE / TIME RECEIVED: 09-14-99 ~ 09.00

DELIVERED BY: FEDEX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: ATC

mm

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C ± 2? (ICE) ICE PACKS PRESENT (Y or N)?	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 1.7

ASC notified Jeff Alexander  
9/14/99

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN): \_\_\_\_\_

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this (and additional sheets if necessary) to document samples that are received broken, compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHAN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # W03904

PAGE: 12 OF 12

COOLER: 12 OF 12

COC# -

SDG# -

DATE / TIME RECEIVED: 09-14-99 ~ 0900

DELIVERED BY: FED EX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: AJC

CLIENT: Tetrahedron NUS

PROJECT: CNC CHARLESTON

	YES	NO	EXCEPTIONS	COMMENTS	RESOLUTION		
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>				
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>				
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	TEMP BLANK TEMP (°C) = <u>3.1</u>			
6. SAMPLES RECEIVED AT 4°C ± 0.2?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	COOLER TEMP (°C) = <u>NA</u>			
ICE / ICE PACKS PRESENT <u>Y</u> or <u>N</u> ?				(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)			
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>				
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>				
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A				
13. ANALYTICAL PROGRAMS (CIRCLE ONE)	COMMERCIAL	CLP	HAZWAP	<u>NFESC</u>	ACOE	AFCEE	OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

0000230



340 County Road No. 3  
P.O. Box 720  
Westbrook, ME 04098  
Tel: (207) 874-2400  
Fax: (207) 775-4029

# CHAIN OF CUSTODY

PLEASE PRINT IN PEN

Page \_\_\_\_ of \_\_\_\_

Client <b>Tetra Tech NUS Inc</b>		Contact <b>Rachel Calligan</b>	Phone # <b>843554-4925</b>	Fax # <b></b>
Address <b>NH 21 AVE H</b>		City <b>N. Charleston</b>	State <b>SC</b>	Zip Code <b></b>
Purchase Order #		Proj. Name / No.		Katahdin Quote #

Bill (if different than above)	Address	
Sampler (Print / Sign) <b>Serry Krupa / Jany Krupa</b>		Copies To:

LAB USE ONLY	WORK ORDER #	ANALYSIS AND CONTAINER TYPE PRESERVATIVES									
	KATAHDIN PROJECT MANAGER	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON
REMARKS:		Filt. OYON									
SHIPPING INFO: <input type="checkbox"/> FED EX <input type="checkbox"/> UPS <input type="checkbox"/> CLIENT		Filt. OYON									
AIRBILL NO:		Filt. OYON									
TEMP °C <input type="checkbox"/> TEMP BLANK <input type="checkbox"/> INTACT <input type="checkbox"/> NOT INTACT		Filt. OYON									

*	Sample Description	Date / Time coll'd	Matrix	No. of Cntrs.	BTEX, MTBE, EDB, NAPL	PAH	Total Lead	Anions Nitrate, Sulfate, Phosphate, Methane										
	23 GLM0401	9/10/99/1517	GW	6	3	2	1											
	23 GLX0301	9/10/99/1535	GW	6	3	2	1											
	23 GLX0401	9/10/99/1540	GW	6	3	2	1											
	23 GLX0401D	9/10/99/0000	GW	6	2	2	1											
	23 GLM05001	9/10/99/1600	GW	6	3	2	1											
	23 GLM0101	9/10/99/1630	GW	6	3	2	1											
	23 TL00201	9/10/99/0800	GW	1	1													
	16 GLM7D01	9/12/99/0755	GW	5	3	2												
	25 GLM0301	1/1510	GW	6	3	2	1											
	25 GLM0801	1/1555	GW	6	3	2	1											
	25 GLM0601	1/1620	GW	6	3	2	1											
	25 GLM0701	9/13/99/1115	GW	10	3	2	1	1	3									
	25 GLM0401	1/1140	GW	5	3	2	1											
	26 GLP1201	1/1345	GW	5	3	2												
	26 GLP1301	1/1355	GW	5	3	2												
		/																

COMMENTS
----------

Relinquished By: (Signature) <b>J. Krupa</b>	Date / Time <b>9/13/99 1900</b>	Received By: (Signature) <b>Felix</b>	Relinquished By: (Signature)	Date / Time <b>9-14-99 0900</b>	Received By: (Signature) <b>[Signature]</b>
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)



340 County Road No. 3  
P.O. Box 720  
Westbrook, ME 04098  
Tel: (207) 874-2400  
Fax: (207) 775-4029

# CHAIN of CUSTODY

PLEASE PRINT IN PEN

Page 2 of 3

Client **TETRA TECH NUS** Contact **PAUL CALLIGAN** Phone # **(850) 385-9899** Fax # **(850) 350-986**  
Address **1401 OVEN PARK DR 102** City **TALLAHASSEE** State **FL** Zip Code **32308**

Purchase Order # Proj. Name / No. Katahdin Quote #

Bill (if different than above) Address

Sampler (Print / Sign) **T. Thompson** Copies To:

LAB USE ONLY WORK ORDER # **WP3906** KATAHDIN PROJECT MANAGER

REMARKS:

SHIPPING INFO: ☐ FED EX ☐ UPS ☐ CLIENT

AIRBILL NO:

TEMP °C ☐ TEMP BLANK ☐ INTACT ☐ NOT INTACT

*	Sample Description	Date / Time coll'd	Matrix	No. of Cntrs.	ANALYSIS AND CONTAINER TYPE PRESERVATIVES									
					Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON
	36GLM0601	91399/1015	GW	10	3	2	1	3	1					
	36GLM0201	91399/1055	GW	10	3	2	1	3	1					
	36GLM0301	91399/1131	GW	10	3	2	1	3	1					
	36GLM0201D	91399/0000	GW	6	3	2	1							
	22GLM0101	91099/1130	GW	6	3	2	1							
	22GLM0201	91099/1110	GW	6	3	2	1							
	22GLM0501	91099/1418	GW	6	3	2	1							
	22GLM0701	91099/1420	GW	6	3	2	1							
	<del>22GLM0201D</del>	<del>91099/0000</del>	<del>GW</del>	<del>6</del>	<del>3</del>	<del>2</del>	<del>1</del>	<del>(BK)</del>						
	/	/												
	/	/												
	/	/												
	/	/												
	/	/												
	/	/												
	/	/												
	/	/												
	/	/												

COMMENTS

Placed on ice.

Relinquished By: (Signature) <b>[Signature]</b>	Date / Time <b>7/13/99 1700</b>	Received By: (Signature) <b>813458369330</b>	Relinquished By: (Signature) <b>9-14-99 0900</b>	Date / Time <b>9-14-99 0900</b>	Received By: (Signature) <b>[Signature]</b>
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)



340 County Road No. 1  
P.O. Box 720  
Westbrook, ME 04098  
Tel: (207) 874-2400  
Fax: (207) 775-4029

# CHAIN OF CUSTODY

PLEASE PRINT IN PEN

Page 3 of 3

Client <b>Tetra Tech NUS</b>	Contact <b>Paul Calligan</b>	Phone # <b>(850) 385-9899</b>	Fax # <b>(850)</b>
Address <b>1401 Oven Park Dr 102</b>	City <b>Tallahassee</b>	State <b>FL</b>	Zip Code <b>3230</b>
Purchase Order #	Proj. Name / No.	Katahdin Quote #	

Bill (if different than above)	Address
--------------------------------	---------

Sampler (Print / Sign) <b>P. Halverson</b>	Copies To:
---	------------

LAB USE ONLY	WORK ORDER #: <b>WP 3906</b>	ANALYSIS AND CONTAINER TYPE PRESERVATIVES									
KATAHDIN PROJECT MANAGER		Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON	Filt. OYON

REMARKS:	
SHIPPING INFO:	<input type="checkbox"/> FED EX <input type="checkbox"/> UPS <input type="checkbox"/> CLIENT
AIRBILL NO:	
TEMP°C	<input type="checkbox"/> TEMP BLANK <input type="checkbox"/> INTACT <input type="checkbox"/> NOT INTACT

*	Sample Description	Date / Time coll'd	Matrix	No. of Cntrs.	Metals (HNO <sub>3</sub> )	BTEX, EOB, MTBE, Total Naph. (HCl)	PAH (None)	Dissolved Metals (HCl)	Anions (None)						
	42GLM1001	9/12/99/0941	GW	6	1	3	2								
	42GLM0701	9/12/99/1000	GW	9	1	3	2	3							
	42GLM1201	9/12/99/1030	GW	6	1	3	2								
	42GLM0901	9/12/99/1030	GW	6	1	3	2	3							
	42GLM0801	9/12/99/1057	GW	6	1	3	2								
	42GLM1101	9/12/99/1106	GW	9	1	3	2	3							
	42GLM0101	9/12/99/1435	GW	10	1	3	2	3	1						
	42GLM1301	9/12/99/1449	GW	10	1	3	2	3	1						
	42GLM0601	9/12/99/1535	GW	6	1	3	2								
	42GLM0701	9/12/99/1202	GW	1					1						
	42GLM0901	9/12/99/1206	GW	1					1						
	42GLM1101	9/12/99/1204	GW	1					1						
	42GLM0701D	9/12/99/0000	GW	6	1	3	2								
	42GLM0101D	9/12/99/0000	GW	6	1	3	2								
	42GLM1001M	9/12/99/0941	GW	6	1	3	2								
	42GLM1801	9/13/99/0842	GW	6	1	3	2								

COMMENTS

Relinquished By: (Signature) 	Date / Time 9/13/99 12:44	Received By: (Signature) 813458369333	Relinquished By: (Signature)	Date / Time 9-14-99 0900	Received By: (Signature) 
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)

Client <b>TETRA TECH NUS</b>		Contact <b>PAUL CALLIGAN</b>	Phone # <b>(850) 385-9899</b>	Fax # <b>(850)</b>																									
Address <b>1401 OVEN PARK DR.</b>		City <b>TALLAHASSEE</b>	State <b>FL</b>	Zip Code <b>32308</b>																									
Purchase Order #	Proj. Name / No.		Katahdin Quote #																										
Bill (if different than above)		Address																											
Sampler (Print / Sign) <b>P. HALVERSON</b>		Copies To:																											
<b>LAB USE ONLY</b>	<b>WORK ORDER #:</b> <b>WP3906</b>		<b>ANALYSIS AND CONTAINER TYPE PRESERVATIVES</b>																										
<b>KATAHDIN PROJECT MANAGER</b>																													
REMARKS:																													
SHIPPING INFO: <input checked="" type="checkbox"/> FED EX <input type="checkbox"/> UPS <input type="checkbox"/> CLIENT																													
AIRBILL NO:																													
TEMP °C <input type="checkbox"/> TEMP BLANK <input type="checkbox"/> INTACT <input type="checkbox"/> NOT INTACT																													
* Sample Description	Date / Time coll'd	Matrix	No. of Cntrs.	METALS	HNO3	PERMITS EDB TOTAL NAPEL	CHCL3	PAH	LOI	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON	Filt. YOYON										
36GLM0101	91099/1110	GW	1	1																									
36GLO680004	91099/1115	GW	1	1																									
36GLM0701	91099/1120	GW	6	1	3	2																							
36GLM0401	91099/1510	GW	6	1	3	2																							
36GLM0501	91099/1515	GW	6	1	3	2																							
42GLM0401	91199/1055	GW	6	1	3	2																							
42GLM0301	91199/1050	GW	6	1	3	2																							
42GLM0201	91199/1045	GW	6	1	3	2																							
42GLM0501	91199/1035	GW	6	1	3	2																							
✓ 42GLM1401	91199/1125	GW	6	1	3	2																							
✓ 42GLM1701	91199/1110	GW	6	1	3	2																							
✓ 42GLM1501	91199/1110	GW	6	1	3	2																							
✓ 42GLM1601	91199/1125	GW	6	1	3	2																							
42TLΦΦ1Φ1	9/13/94	gg	2		2																								
/	/																												
/	/																												
COMMENTS																													
Relinquished By: (Signature) <i>[Signature]</i>					Date / Time 9/13/94 1700					Received By: (Signature) 813458369334					Relinquished By: (Signature) 9-14-94 0900					Received By: (Signature) <i>[Signature]</i>									
Relinquished By: (Signature)					Date / Time					Received By: (Signature)					Relinquished By: (Signature)					Date / Time					Received By: (Signature)				

New England-ME Laboratory (207) 874-2400  
CONFIRMATION

Page 1

ORDER NO WP-3906

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/14/99  
PHONE: 850/385-8899  
FAX: 850/385-1150  
DUE: 14 OCT  
FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090  
PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: P.HALVERSON/T.THOMPSON/J.KRIEGERDELIVERED BY: FEDEXDISPOSE: AFTER 13

ITEM	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
1	WP3906-1	36GLM0101	10 SEP 1110	14 SEP	AQ
	WP3906-2	36GLO680004	10 SEP 1115		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Target Analyte List Metals, Total		2	100.00	200.00

LABORATORY ORDER CONTINUED ON PAGE 2

119099235

ORDER NO WP-3906

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/14/99

PHONE: 850/385-9899

FAX: 850/385-9860

DUE: 14 OCT

FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090

PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: P.HALVERSON/T.THOMPSON/J.KRIEGERDELIVERED BY: FEDEXDISPOSE: AFTER 13

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
2	WP3906-3	36GLM0701	10 SEP 1120	14 SEP	AQ
	WP3906-4	36GLM0401	10 SEP 1510		
	WP3906-5	36GLM0501	10 SEP 1515		
	WP3906-6	42GLM0401	11 SEP 1055		
	WP3906-7	42GLM0301	11 SEP 1050		
	WP3906-8	42GLM0201	11 SEP 1045		
	WP3906-9	42GLM0501	11 SEP 1035		
	WP3906-10	42GLM1401	11 SEP 1125		
	WP3906-11	42GLM1701	11 SEP 1110		
	WP3906-12	42GLM1501	11 SEP 1110		
	WP3906-13	42GLM1601	11 SEP 1125		
	WP3906-14	36GLM0201D	13 SEP		
	WP3906-15	22GLM0101	10 SEP 1130		
	WP3906-16	22GLM0201	10 SEP 1110		
	WP3906-17	22GLM0501	10 SEP 1418		
	WP3906-18	22GLM0701	10 SEP 1420		
	WP3906-19	42GLM1001	12 SEP 0941		
	WP3906-20	42GLM1201	12 SEP 1030		
	WP3906-21	42GLM0801	12 SEP 1057		
	WP3906-22	42GLM0601	12 SEP 1535		
	WP3906-23	42GLM0701D	12 SEP 0000		
	WP3906-24	42GLM0101D	12 SEP 0000		
	WP3906-25	42GLM1801	13 SEP 0842		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Target Analyte List Metals, Total		23	100.00	2300.00
Volatile Organics by 8260B	SW8260	23	75.00	1725.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	23	125.00	2875.00
TOTALS		23	300.00	6900.00

LABORATORY ORDER CONTINUED ON PAGE 3

0000236  
10/21/99



ORDER NO WP-3906

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/14/99

PHONE: 850/385-0899

FAX: 850/385- 60

DUE: 14 OCT

FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090

PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: P.HALVERSON/T.THOMPSON/J.KRIEGERDELIVERED BY: FEDEXDISPOSE: AFTER 13

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
3	WP3906-26	42TL00101	13 SEP	14 SEP	AQ
	WP3906-27	23TL00201	10 SEP 0800		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	2	75.00	150.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
4	WP3906-28	36GLM0601	13 SEP 1015	14 SEP	AQ
	WP3906-29	36GLM0201	13 SEP 1055		
	WP3906-30	36GLM0301	13 SEP 1131		
	WP3906-31	42GLM0701	12 SEP 1202		
	WP3906-32	42GLM0901	12 SEP 1206		
	WP3906-33	42GLM1101	12 SEP 1204		
	WP3906-34	42GLM0101	12 SEP 1435		
	WP3906-35	42GLM1301	12 SEP 1449		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Target Analyte List Metals, Total		8	100.00	800.00
Volatile Organics by 8260B	SW8260	8	75.00	600.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	8	125.00	1000.00
Nitrate as N	353.2	8	30.00	240.00
Sulfate	375.4	8	0.00	0.00
Methane Subcontract		8	95.00	760.00

TOTALS		8	425.00	3400.00
--------	--	---	--------	---------

LABORATORY ORDER CONTINUED ON PAGE 4

11 0999237

ORDER NO WP-3906

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/14/99

PHONE: 850/385-9899

FAX: 850/385-9860

DUE: 14 OCT

FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090

PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: P.HALVERSON/T.THOMPSON/J.KRIEGERDELIVERED BY: FEDEXDISPOSE: AFTER 13

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
5	WP3906-36	23GLM0401	10 SEP 1517	14 SEP	AQ
	WP3906-37	23GLX0301	10 SEP 1535		
	WP3906-38	23GLX0401	10 SEP 1540		
	WP3906-39	23GLX0401D	10 SEP		
	WP3906-40	23GLM05D01	10 SEP 1600		
	WP3906-41	23GLM0101	10 SEP 1630		
	WP3906-42	25GLM0301	12 SEP 1510		
	WP3906-43	25GLM0801	12 SEP 1555		
	WP3906-44	25GLM0601	12 SEP 1620		
	WP3906-45	25GLM0401	13 SEP 1140		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	10	75.00	750.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	10	125.00	1250.00
Lead, Total	200.7/6010	10	20.00	200.00
Elements Sample Preparation		10	0.00	0.00
TOTALS		10	220.00	2200.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
6	WP3906-46	25GLM0701	13 SEP 1115	14 SEP	AQ

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	1	75.00	75.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	1	125.00	125.00
Lead, Total	200.7/6010	1	20.00	20.00
Elements Sample Preparation		1	0.00	0.00
Nitrate as N	353.2	1	30.00	30.00
Sulfate	375.4	1	0.00	0.00
Methane Subcontract		1	95.00	95.00
TOTALS		1	345.00	345.00

LABORATORY ORDER CONTINUED ON PAGE 5

9/14/99 0000238

ORDER NO WP-3906

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/14/99  
PHONE: 850/385-9999  
FAX: 850/385- 50  
DUE: 14 OCT  
FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090  
PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: P.HALVERSON/T.THOMPSON/J.KRIEGERDELIVERED BY: FEDEXDISPOSE: AFTER 13

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
7	WP3906-47	16GLM7D01	12 SEP 0755	14 SEP	AQ
	WP3906-48	26GLP1201	13 SEP 1345		
	WP3906-49	26GLP1301	13 SEP 1355		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	3	75.00	225.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	3	125.00	375.00
TOTALS		3	200.00	600.00

ORDER NOTE: QC-II+ W/NARRATIVE  
DD(KAS007QC-DB3)  
CNC CHARLESTON

REPORT COPY: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PLAZA 7  
661 ANDERSEN DR.  
PITTSBURGH, PA. 15220  
REPORT AND DISK

INVOICE: With Report

TOTAL ORDER AMOUNT \$13,795.00  
This is NOT an Invoice

AJC/BKR

09-14Please contact KATAHDIN ANALYTICAL SERVICES promptly if you have any questi

0000239  
KATAHDIN

# KATAHDIN ANALYTICAL SERVICES

## Summary of Report Notes

Report Note	Note Text
A-1	Insufficient sample was provided to enable laboratory to achieve the laboratory's standard Practical Quantitation Level.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.

# KATAHDIN ANALYTICAL SERVICES

## Summary of Report Notes

Report Note	Note Text
B	'B' flag denotes detection of this analyte in the laboratory method blank analyzed concurrently with the sample.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0301

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-042

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.4	B		P	1

Comments:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP3906-42  
SDG: WP3906  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/29/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0301	AQ	9/12/99	9/14/99	9/17/99	DPD	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	81	%	1.0		
2-FLUOROBIPHENYL	80	%	1.0		
TERPHENYL-D14	69	%	1.0		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-42  
**SDG:** WP3906  
**Report Date:** 10/12/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/20/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0301	AQ	9/12/99	9/14/99	9/20/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	99	%	1.0		
1,2-DICHLOROETHANE-D4	92	%	1.0		
TOLUENE-D8	101	%	1.0		
P-BROMOFLUOROBENZENE	104	%	1.0		

**Report Notes:**



## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0801

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-043

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.3	B		P	1

Comments:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-43  
**SDG:** WP3906  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 9/29/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0801	AQ	9/12/99	9/14/99	9/17/99	DPD	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<12	ug/L	1.2	12	10
2-METHYLNAPHTHALENE	<12	ug/L	1.2	12	10
ACENAPHTHYLENE	<12	ug/L	1.2	12	10
ACENAPHTHENE	<12	ug/L	1.2	12	10
FLUORENE	<12	ug/L	1.2	12	10
PHENANTHRENE	<12	ug/L	1.2	12	10
ANTHRACENE	<12	ug/L	1.2	12	10
FLUORANTHENE	<12	ug/L	1.2	12	10
PYRENE	<12	ug/L	1.2	12	10
BENZO[A]ANTHRACENE	<12	ug/L	1.2	12	10
CHRYSENE	<12	ug/L	1.2	12	10
BENZO[B]FLUORANTHENE	<12	ug/L	1.2	12	10
BENZO[K]FLUORANTHENE	<12	ug/L	1.2	12	10
BENZO[A]PYRENE	<12	ug/L	1.2	12	10
INDENO[1,2,3-CD]PYRENE	<12	ug/L	1.2	12	10
DIBENZ[A,H]ANTHRACENE	<12	ug/L	1.2	12	10
BENZO[G,H,I]PERYLENE	<12	ug/L	1.2	12	10
NITROBENZENE-D5	74	%	1.2		
2-FLUOROBIPHENYL	88	%	1.2		
TERPHENYL-D14	104	%	1.2		

**Report Notes:** A-1



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP3906-43  
SDG: WP3906  
Report Date: 10/12/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/21/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0801	AQ	9/12/99	9/14/99	9/21/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	109	%	1.0		
1,2-DICHLOROETHANE-D4	104	%	1.0		
TOLUENE-D8	106	%	1.0		
P-BROMOFLUOROBENZENE	103	%	1.0		

Report Notes:

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0601

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-044

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.09	U		P	1

Comments:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-44  
**SDG:** WP3906  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 9/29/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0601	AQ	9/12/99	9/14/99	9/17/99	DPD	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	81	%	1.0		
2-FLUOROBIPHENYL	104	%	1.0		
TERPHENYL-D14	95	%	1.0		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-44  
**SDG:** WP3906  
**Report Date:** 10/12/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/21/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0601	AQ	9/12/99	9/14/99	9/21/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	E260	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	108	%	1.0		
1,2-DICHLOROETHANE-D4	104	%	1.0		
TOLUENE-D8	106	%	1.0		
P-BROMOFLUOROBENZENE	103	%	1.0		

Report Notes: E



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-44DL  
**SDG:** WP3906  
**Report Date:** 10/12/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/22/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0601	AQ	9/12/99	9/14/99	9/22/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<25	ug/L	5.0	25	5
TOLUENE	<25	ug/L	5.0	25	5
1,2-DIBROMOETHANE	<25	ug/L	5.0	25	5
ETHYLBENZENE	<25	ug/L	5.0	25	5
NAPHTHALENE	<25	ug/L	5.0	25	5
MTBE	220	ug/L	5.0	25	5
TOTAL XYLENES	<25	ug/L	5.0	25	5
DIBROMOFLUOROMETHANE	111	%	5.0		
1,2-DICHLOROETHANE-D4	102	%	5.0		
TOLUENE-D8	107	%	5.0		
P-BROMOFLUOROBENZENE	104	%	5.0		

**Report Notes:** O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0401

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-045

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.09	U		P	1

Comments:

FORM I - IN

0000144





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP3906-45  
SDG: WP3906  
Report Date: 10/6/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/29/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0401	AQ	9/13/99	9/14/99	9/20/99	DS	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	70	%	1.0		
2-FLUOROBIPHENYL	80	%	1.0		
TERPHENYL-D14	100	%	1.0		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP3906-45  
**SDG:** WP3906  
**Report Date:** 10/12/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/21/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0401	AQ	9/13/99	9/14/99	9/21/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	110	%	1.0		
1,2-DICHLOROETHANE-D4	106	%	1.0		
TOLUENE-D8	106	%	1.0		
P-BROMOFLUOROBENZENE	104	%	1.0		

**Report Notes:**

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0701

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-046

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.09	U		P	1

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-3906-46  
Report Date: 10/13/99  
PO No. : N7912-P99264  
Project : CIO #68

WICH#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 9 of 9

SAMPLE DESCRIPTION	MATRIX	SAMPLED BY	SAMPLED DATE RECEIVED	
25GLM0701	Aqueous	P.HALVERSON/ T.THOMPSON/ J.KRIEGER	09/13/99	09/14/99

PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Nitrate as N	0.16	mg/L	1.0	0.050	353.2	09/14/99	KW	
Sulfate	160.	mg/L	10	1.0	300.0	09/24/99	CF	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.

10/13/99

LJO/baeajc(dw)/msm  
PI14NOW1  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PLAZA 7  
661 ANDERSEN DR.



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

Proj. ID: CNC CHARLESTON

Lab Number: WP3906-46  
SDG: WP3906  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0701	AQ	9/13/99	9/14/99	9/20/99	DS	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	49	%	1.0		
2-FLUOROBIPHENYL	58	%	1.0		
TERPHENYL-D14	103	%	1.0		

Report Notes:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

Proj. ID: CNC CHARLESTON

Lab Number: WP3906-46  
SDG: WP3906  
Report Date: 10/12/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/21/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0701	AQ	9/13/99	9/14/99	9/21/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	109	%	1.0		
1,2-DICHLOROETHANE-D4	104	%	1.0		
TOLUENE-D8	105	%	1.0		
P-BROMOFLUOROBENZENE	103	%	1.0		

Report Notes:

3P  
PREPARATION BLANKS

**Lab Name:** Katahdin Analytical Services

**Sample ID:** PBWPI22ICW0

**Matrix:** WATER

**SDG Name:** WP3906

**QC Batch ID:** PI22ICW0

**Concentration Units (ug/L or mg/Kg dry weight): ug/L**

<b>Analyte</b>	<b>RESULT</b>	<b>C</b>
LEAD	1.090	U

## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSWPI22ICW0

Matrix: WATER

SDG Name: WP3906

QC Batch ID: PI22ICW0

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	TRUE	FOUND	% R	LIMITS (%)	
LEAD	500.0	552.13	110.4	80	120



## SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0701S

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-046S

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	Spiked		Sample		Spike	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
LEAD	538.0900		0.6200	U	500	107.6		75	125	P

Comments:

## SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0701S

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-046P

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	Spiked		Sample		Spike	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
LEAD	504.6900		0.6200	U	500	100.9		75	125	P

Comments:

5D  
SPIKE DUPLICATES

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0701

Matrix: WATER

SDG Name: WP3906

Percent Solids: 0.00

Lab Sample ID: WP3906-046

Concentration Units (ug/L or mg/Kg dry weight): ug/L							
Analyte	Control Limits	Spike Result	C	Spike Dup. Result	C	RPD	Q M
LEAD		538.0900		504.6900		6.4	P

Comments:

# Katahdin Analytical Services, Inc.

## Quality Control Report

### Method Blank and Laboratory Control Sample Results

Client: Tetra Tech NUS

Work Order: WP3906

#### METHOD BLANK RESULTS

#### LABORATORY CONTROL SAMPLE RESULTS

Parameter	Date of Prep	Date of Analysis	Concentration				Practical Quantitation Level**	LABORATORY CONTROL SAMPLE RESULTS					
			Units	Measured in Blank	Acceptance Range			Units	True Value	Measured Value	Percent Recovered	Acceptance Range (%)	Acceptance Range (mg/kg)
Nitrate-Nitrogen	14-Sep-99	14-Sep-99	mg/L	< 0.050	< 0.050		0.050	mg/L	1.00	0.931	93.1	80-120	
Sulfate	24-Sep-99	24-Sep-99	mg/L	< 1.0	< 1.0		1.0	mg/L	10	10	100.0	80-120	
	04-Oct-99	04-Oct-99	mg/L	< 1.0	< 1.0		1.0	mg/L	250	223	89.2	83-112	@

\*\* Practical quantitation level is the lowest concentration measurable for samples with normal chemical and physical composition during routine laboratory operations.

#### DATA QUALITY COMMENTS:

Results of all quality control measurements are within the laboratory and method specified acceptance range except as noted.

@ The laboratory uses the internally established statistical 99% confidence range as the acceptance range for this LCS.

# Katahdin Analytical Services, Inc. Quality Control Report

## Duplicate and Matrix Spike/Matrix Spike Duplicate Results

Client: Tetra Tech NUS

Work Order: WP3906

### DUPLICATE RESULTS

### MATRIX SPIKE/MATRIX SPIKE DUPLICATE RESULTS

Parameter	Katahdin Sample No	Sample Measurements						Concentration or Quantity						Matrix Spike Recovery (%)			
		Units	Rep		Mean Conc	RPD (%)	Acceptance Range for RPD (%)	Units	Sampl Only	Spike Added	Sample +Spike Dup 1	Sample +Spike Dup 2	Sample +Spike Dup 1	Sample +Spik Dup	Acceptance Range (%)	RPD (%)	Acceptance Range (%)
			1	2													
Nitrate - N	WP3906-46	mg/L	0.161	0.163	0.162	1.2	0-20	mg/L	0.16	0.5	0.396		47.2	*	75-125		0-20

RPD = Relative percent difference, which is the absolute value of the difference between two replicate results divided by the mean concentration then multiplied by 100%.

#### DATA QUALITY COMMENTS:

Results of all quality control measurements are within the laboratory or contract specified acceptance range except as noted. The laboratory does not use the sample duplicate and matrix spike acceptance ranges as acceptance criteria for a specific analysis. Sample duplicate and matrix spike data are used to evaluate method performance in the environmental sample matrix only. Please refer to LCS data for assessment of quality control for each parameter.

\* Matrix spike recovery is outside the laboratory's specified acceptance range indicating potential sample matrix interference and potential bias of reported value for this parameter.

0000181

4B  
SEMIVOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

**SBLK;091799**

Lab Name: Katahdin Analytical Services

SDG No.: WP3906

Lab File ID: X2921

Lab Sample ID: SBLK;091799

Instrument ID: 5970-X

Date Extracted: 9/17/99

GC Column: RTX-5 ID: 0.25 (mm)

Date Analyzed: 09/27/99

Matrix: (soil/water) WATER

Time Analyzed: 16:30

Level: (low/med) LOW

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCS;091799	LCS;091799	X2922	9/27/99	5:14:00 PM
42GLM1601	WP3906-13	X2923	9/27/99	5:59:00 PM
42GLM1001	WP3906-19	X2924	9/27/99	6:43:00 PM
42GLM1001MS	WP3906-19MS	X2925	9/27/99	7:27:00 PM
42GLM1001MSD	WP3906-19MSD	X2926	9/27/99	8:11:00 PM
42GLM0801	WP3906-21	X2928	9/27/99	9:39:00 PM
42GLM1001	WP3906-19DL	X2933	9/28/99	11:59:00 AM
42GLM1201	WP3906-20	X2934	9/28/99	12:43:00 PM
42GLM0601	WP3906-22	X2935	9/28/99	1:27:00 PM
42GLM0701D	WP3906-23	X2936	9/28/99	2:12:00 PM
42GLM0101D	WP3906-24	X2937	9/28/99	2:56:00 PM
42GLM1801	WP3906-25	X2938	9/28/99	3:40:00 PM
36GLM0601	WP3906-28	X2939	9/28/99	4:24:00 PM
36GLM0201	WP3906-29	X2940	9/28/99	5:09:00 PM
36GLM0301	WP3906-30	X2941	9/28/99	5:53:00 PM
42GLM0901	WP3906-32	X2943	9/28/99	7:22:00 PM
42GLM0101	WP3906-34	X2945	9/28/99	8:50:00 PM
42GLM0601	WP3906-22RA	X2947	9/29/99	10:07:00 AM
42GLM0701	WP3906-31	X2948	9/29/99	10:51:00 AM
42GLM1101	WP3906-33	X2949	9/29/99	11:35:00 AM
42GLM1301	WP3906-35	X2950	9/29/99	12:20:00 PM
25GLM0301	WP3906-42	X2951	9/29/99	1:04:00 PM
25GLM0801	WP3906-43	X2952	9/29/99	1:48:00 PM
25GLM0601	WP3906-44	X2953	9/29/99	2:32:00 PM
16GLM7D01	WP3906-47	X2954	9/29/99	3:17:00 PM



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: SBLK;091799  
SDG: WP3906  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/27/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
SBLK;091799	AQ	-	-	9/17/99	DPD	EPA 3510	SW

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	82	%	1.0		
2-FLUOROBIPHENYL	81	%	1.0		
TERPHENYL-D14	112	%	1.0		

Report Notes:

# Katahdin Analytical Services

## 8270 LCS Recovery Sheet

Lab File: X2922

Sample ID: LCS;091799

Date Run: 9/27/99

Analyst: SW

Time Injected: 5:14:00 PM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
2-METHYLNAPHTHALENE	50	33.1	*66	70-130
ACENAPHTHENE	50	34.4	*69	70-130
ACENAPHTHYLENE	50	34.5	*69	70-130
ANTHRACENE	50	45.7	91	70-130
BENZO[A]ANTHRACENE	50	44.5	89	70-130
BENZO[A]PYRENE	50	44.6	89	70-130
BENZO[B]FLUORANTHENE	50	44.5	89	70-130
BENZO[G,H,I]PERYLENE	50	46.5	93	70-130
BENZO[K]FLUORANTHENE	50	46.5	93	70-130
CHRYSENE	50	53.3	106	70-130
DIBENZ[A,H]ANTHRACENE	50	44.1	88	70-130
FLUORANTHENE	50	43.5	87	70-130
FLUORENE	50	35.5	71	70-130
INDENO[1,2,3-CD]PYRENE	50	41.0	82	70-130
NAPHTHALENE	50	31.3	*62	70-130
PHENANTHRENE	50	47.5	95	70-130
PYRENE	50	48.8	98	70-130

\* Out of Limits

1

0000187



# Katahdin Analytical Services

## MS/MSD Report

Sample	File Name	Date Acquired	Time inj	Analyst	Matrix	Method
WP3906-19	X2924	9/27/99	6:43:00 PM	SW	AQ	8270_99
WP3906-19MS	X2925	9/27/99	7:27:00 PM	SW	AQ	8270_99
WP3906-19MSD	X2926	9/27/99	8:11:00 PM	SW	AQ	8270_99

Compound Name	Native (ug/L)	MS Spk Amount (ug/L)	MSD Spk Amount (ug/L)	MS Result (ug/L)	MSD Result (ug/L)	MS REC (%)	MSD REC (%)	Recovery Limits (%)	RPD (%)	RPD Limit (%)
CHRYSENE	0	56	54	45.8	44.6	82	82	60-140	2.6	30
ACENAPHTHENE	57.8	56	54	104	97.8	82	74	60-140	6.1	30
ACENAPHTHYLENE	0	56	54	35.9	37.2	64	69	60-140	3.6	30
ANTHRACENE	9.96	56	54	50.1	45.9	72	66	60-140	8.8	30
BENZO[A]ANTHRACENE	0	56	54	37.2	39.2	66	72	60-140	5.2	30
BENZO[A]PYRENE	0	56	54	35.2	41.3	63	76	60-140	16	30
BENZO[B]FLUORANTHENE	0	56	54	34.5	43.5	62	80	60-140	23	30
2-METHYLNAPHTHALENE	34.7	56	54	74.6	52.1	71	*32	60-140	*36	30
BENZO[K]FLUORANTHENE	0	56	54	34.0	42.4	61	78	60-140	22	30
PYRENE	13.2	56	54	57.6	58.9	79	85	60-140	2.2	30
DIBENZ[A,H]ANTHRACENE	0	56	54	35.2	37.8	63	70	60-140	7.1	30
FLUORANTHENE	20.8	56	54	59.1	61.9	68	76	60-140	4.6	30
FLUORENE	32.4	56	54	72.3	60.0	71	*51	60-140	18	30
INDENO[1,2,3-CD]PYRENE	0	56	54	38.2	32.0	68	*59	60-140	18	30
NAPHTHALENE	255	56	54	365	356	*197	*187	60-140	2.5	30
PHENANTHRENE	66.0	56	54	116	98.8	89	61	60-140	16	3
BENZO[G,H,I]PERYLENE	0	56	54	39.3	40.8	70	76	60-140	3.7	30

RPD = [(ms res - msd res) / (ms res + msd res)/2] \* 100

\* Out of Limits

1

0000188

4B  
SEMIVOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

Lab Name: Katahdin Analytical Services

SDG No.: WP3906

**SBLK;092099**

Lab File ID: X2931

Lab Sample ID: SBLK;092099

Instrument ID: 5970-X

Date Extracted: 9/20/99

GC Column: RTX-5 ID: 0.25 (mm)

Date Analyzed: 09/28/99

Matrix: (soil/water) WATER

Time Analyzed: 10:30

Level: (low/med) LOW

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCS;092099	LCS;092099	X2932	9/28/99	11:14:00 AM
36GLM0201D	WP3906-14	X2955	9/29/99	4:01:00 PM
25GLM0401	WP3906-45	X2956	9/29/99	4:45:00 PM
26GLP1201	WP3906-48	X2958	9/29/99	6:13:00 PM
26GLP1301	WP3906-49	X2959	9/29/99	6:58:00 PM
25GLM0701	WP3906-46	X2962	9/30/99	8:46:00 AM



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: SBLK;092099  
SDG: WP3906  
Report Date: 10/6/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/28/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
SBLK;092099	AQ	-	-	9/20/99	DS	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	84	%	1.0		
2-FLUOROBIPHENYL	93	%	1.0		
TERPHENYL-D14	90	%	1.0		

Report Notes:

# Katahdin Analytical Services

## 8270 LCS Recovery Sheet

Lab File: X2932

Sample ID: LCS;092099

Date Run: 9/28/99

Analyst: SW

Time Injected: 11:14:00 AM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
2-METHYLNAPHTHALENE	50	37.9	76	70-130
ACENAPHTHENE	50	38.6	77	70-130
ACENAPHTHYLENE	50	40.3	80	70-130
ANTHRACENE	50	42.9	86	70-130
BENZO[A]ANTHRACENE	50	41.3	82	70-130
BENZO[A]PYRENE	50	41.0	82	70-130
BENZO[B]FLUORANTHENE	50	40.5	81	70-130
BENZO[G,H,I]PERYLENE	50	43.8	88	70-130
BENZO[K]FLUORANTHENE	50	42.3	84	70-130
CHRYSENE	50	50.7	101	70-130
DIBENZ[A,H]ANTHRACENE	50	39.2	78	70-130
FLUORANTHENE	50	42.4	85	70-130
FLUORENE	50	37.0	74	70-130
INDENO[1,2,3-CD]PYRENE	50	40.7	81	70-130
NAPHTHALENE	50	37.1	74	70-130
PHENANTHRENE	50	44.5	89	70-130
PYRENE	50	46.0	92	70-130

\* Out of Limits

1

0000191

4A  
VOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

**VBULKU21B**

Lab Name: Katahdin Analytical Services

SDG No.: WP3906

Lab File ID: U1000

Lab Sample ID: VBLKU21B

Date Analyzed: 09/21/99

Time Analyzed: 16:31

GC Column: RTX-624 ID: 0.18 (mm)

Heated Purge: (Y/N) N

Instrument ID: 5973-U

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCSU21B	LCSU21B	U0999	9/21/99	3:50:00 PM
25GLM0801	WP3906-43	U1009	9/21/99	10:05:00 PM
25GLM0601	WP3906-44	U1010	9/21/99	10:40:00 PM
25GLM0401	WP3906-45	U1011	9/21/99	11:16:00 PM
25GLM0701	WP3906-46	U1012	9/21/99	11:52:00 PM

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKU21B  
**SDG:** WP3906  
**Report Date:** 10/12/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/21/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKU21B	AQ	-	-	9/21/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	105	%	1.0		
1,2-DICHLOROETHANE-D4	99	%	1.0		
TOLUENE-D8	104	%	1.0		
P-BROMOFLUOROBENZENE	102	%	1.0		

**Report Notes:**

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: U0999**

**Sample ID: LCSU21B**

**Date Run: 9/21/99**

**Analyst: JSS**

**Time Injected: 3:50:00 PM**

**Matrix: AQ**

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	50.2	100	60-140
BENZENE	50	50.3	101	60-140
ETHYLBENZENE	50	49.0	98	60-140
MTBE	50	43.1	86	60-140
NAPHTHALENE	50	45.4	91	60-140
TOLUENE	50	52.7	105	60-140
TOTAL XYLENES	150	143	96	60-140

**\* Out of Limits**

**1**

**0000211**

4A  
VOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

VBLKU22A

Lab Name: Katahdin Analytical Services

SDG No.: WP3906

Lab File ID: U1018

Lab Sample ID: VBLKU22A

Date Analyzed: 09/22/99

Time Analyzed: 10:44

GC Column: RTX-624 ID: 0.18 (mm)

Heated Purge: (Y/N) N

Instrument ID: 5973-U

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCSU22A	LCSU22A	U1017	9/22/99	9:54:00 AM
25GLM0601	WP3906-44DL	U1019	9/22/99	11:32:00 AM
23GLM0401	WP3906-36DL	U1021	9/22/99	12:47:00 PM
36GLM0501MS	WP3906-5MS	U1025	9/22/99	3:14:00 PM
36GLM0501MSD	WP3906-5MSD	U1026	9/22/99	3:50:00 PM





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: VBLKU22A  
SDG: WP3906  
Report Date: 10/12/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/22/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKU22A	AQ	-	-	9/22/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample	Method
				PQL	PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	110	%	1.0		
1,2-DICHLOROETHANE-D4	99	%	1.0		
TOLUENE-D8	107	%	1.0		
P-BROMOFLUOROBENZENE	104	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

Lab File: U1017

Sample ID: LCSU22A

Date Run: 9/22/99

Analyst: KMC

Time Injected: 9:54:00 AM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	49.7	99	60-140
BENZENE	50	51.1	102	60-140
ETHYLBENZENE	50	48.6	97	60-140
MTBE	50	41.8	84	60-140
NAPHTHALENE	50	41.2	82	60-140
TOLUENE	50	53.6	107	60-140
TOTAL XYLENES	150	141	94	60-140

\* Out of Limits

1

0000214

## MS/MSD Report

Sample	File Name	Date Acquired	Time inj	Analyst	Matrix	Method
WP3906-5	Q6636	9/15/99	7:27:00 PM	HMP	AQ	8260_99
WP3906-5MS	U1025	9/22/99	3:14:00 PM	KMC	AQ	8260_99
WP3906-5MSD	U1026	9/22/99	3:50:00 PM	KMC	AQ	8260_99

Compound Name	Native (ug/L)	MS Spk Amount (ug/L)	MSD Spk Amount (ug/L)	MS Result (ug/L)	MSD Result (ug/L)	MS REC (%)	MSD REC (%)	Recovery Limits (%)	RPD (%)	RPD Limit (%)
TOTAL XYLENES	0	150	150	134	123	89	82	60-140	8.6	20
TOLUENE	0	50	50	51.1	46.5	102	93	60-140	9.4	20
NAPHTHALENE	0	50	50	45.6	42.6	91	85	60-140	6.8	20
MTBE	0	50	50	45.4	43.4	91	87	60-140	4.5	20
ETHYLBENZENE	0	50	50	45.6	41.8	91	84	60-140	8.7	20
BENZENE	0	50	50	48.5	44.6	97	89	60-140	8.4	20
1,2-DIBROMOETHANE	0	50	50	53.6	48.8	107	98	60-140	9.4	20



ENSR  
Air Toxics Specialty Laboratory  
42 Nagog Park  
Acton, MA 01720

DATE: October 12, 1999

TO: Andrea Colby  
Katahdin Analytical  
340 County Road No. 5  
P.O. Box 720  
Westbrook, ME 04098

Re: Organic Analyses of Aqueous Samples for Methane by Gas  
Chromatography/ Flame Ionization Detection (GC/FID)- **WP3906**

PROJECT #: **8601-008-200**

LAB ID #: **990175**

**ANALYTICAL PROCEDURE:**

Nine (9) aqueous samples were analyzed for methane under the guidelines of SW-846 Method 3810.

A Hewlett Packard 5890 series II gas chromatograph (GC) equipped with a Hewlett Packard flame ionization detector (FID) was used for the analysis. A 1.0 mL headspace aliquot of each sample was injected into the column for analysis. The operating conditions of the GC/FID are listed in Table 1. A five point calibration was performed for the target analyte, methane.

No problems occurred during sample receipt, log-in, or analysis.



**QUALITY CONTROL:**

1. A laboratory blank was analyzed daily in the same manner as the samples. Methane was not detected in the blank.
2. MS/MSD analyses were performed on the following sample:  
WP3906-28


The recoveries and relative percent differences of methane were within the QC acceptance limits.

3. A duplicate analysis was performed on the following sample:  
WP3906-34(A)
4. A laboratory control spike was analyzed daily. The recovery of methane was within the QC acceptance limits.

Date Samples Received by the Laboratory: 9/16/99

Date Analysis Started: 9/24/99

C:\My Documents\Kat 990175 990178 990180\katrpt3.doc



**PLEASE PRINT IN PEN**

Page \_\_\_\_ of \_\_\_\_

Client	Contact	Phone #	Fax #
Katridin Analytical Services	Andrea Colby	( )	( )
Address	City	State	Zip Code
107 Grove			

Purchase Order #	Proj. Name / No.	Katahdin Quote #
------------------	------------------	------------------

Bill (if different than above)	Address
--------------------------------	---------

Sampler (Print / Sign)	Copies To:
------------------------	------------

LAB USE ONLY	WORK ORDER #:	ANALYSIS AND CONTAINER TYPE PRESERVATIVES
--------------	---------------	--

[illegible][illegible]

SHIPPING INFO: ☒ FED EX ☐ UPS ☐ CLIENT









AIRBILL NO: _____																	
-------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

TEMP°C \_\_\_\_\_ ☐ TEMP BLANK ☐ INTACT ☐ NOT INTACT

★	Sample Description	Date / Time col'd	Matrix	No. of Centres
---	--------------------	----------------------	--------	-------------------

[illegible]

COMMENTS  
QC-II + w/inactive DL (KAL007QC-DB3) Results Due: 10-13-99

Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)
	7-15-95 11:35			7-15-95 14:40	
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)
					

**DUPLICATE**

# SAMPLE LOG-IN & RECEIPT CHECKLIST

Client/Proj #: Katahdin WP3906 / 8601-008-200

Proj Mgr: M. Hoyt

Lab Pool #: 990175

Inspected & Logged in by: A. MacDuff

Date Time: 9/16/99 @ 1440

Sample Matrix	Number of Samples	Analysis Requested	Analyze by (date)	Storage Location
Aqueous	9	CH <sub>4</sub>	9/30/99 Due 10/13	R1

## Circle the appropriate response:

- 1) Shipped / Hand delivered
- 2) COC present / not present on receipt
- 3) COC Tape present / not present on shipping container
- 4) Samples broken / intact on receipt
- 5) Samples ambient / chilled on receipt Temp blank = 5°C
- 6) Samples preserved correctly / incorrectly / none recommended
- 7) Received within / outside holding time
- 8) COC tapes present / not present on samples
- 9) Discrepancies / NO discrepancies noted between COCs and samples

Additional Comments: 3 VOA's per sample

1  
ORGANICS ANALYSIS DATA SHEET

25GLM10701

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_ EPA SAMPLE NO. \_\_\_\_\_  
WP3906-46(C)

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: 990175-9

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_\_\_\_ KAT\_008 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_\_\_\_ 9/16/99 \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (μg/L or PPMv) _____ μg/L _____	Q
---------	----------	---	---

74-82-8	Methane	6.5	
---------	---------	-----	--



1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

VBLK01

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: MB990175

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_\_\_\_ KAT\_006 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_\_\_\_ NA \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(μg/L or PPMv) \_\_\_\_\_ μg/L \_\_\_\_\_

Q

74-82-8	Methane	5.2	U
---------	---------	-----	---

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. \_\_\_\_\_

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

LCS01

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: LCS990175

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_\_\_\_ KAT\_007 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_\_\_\_ NA \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(µg/L or PPMv) \_\_\_\_\_ µg/L \_\_\_\_\_

Q

74-82-8	Methane	210	
---------	---------	-----	--

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

WP3906-28(B) MS

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: 990175-1 MS

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_KAT\_023\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_9/16/99\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_9/24/99\_\_

GC Column: \_ Carboxen 1004 \_ OD: \_\_ 1/16" \_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(µg/L or PPMv) \_\_ µg/L \_\_

Q

74-82-8	Methane	340	
---------	---------	-----	--

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. \_\_\_\_\_  
**WP3906-28(C) MSD**

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_ Lab Sample ID: 990175-1 MSD

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml) Lab File ID: \_\_\_\_\_ KAT\_024 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_ Date Received: \_\_\_\_\_ 9/16/99 \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_ Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_ Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl) Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(µg/L or PPMv) _____ µg/L _____	Q
74-82-8	Methane	350	

## LABORATORY CONTROL SPIKE RECOVERY

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_

Contract: \_\_\_\_\_

Lab Code: \_\_\_\_\_ Case NO.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Laboratory Control Sample No: \_\_\_\_\_ LCS01 \_\_\_\_\_

COMPOUND	SPIKE ADDED (µg/L)	LCS CONCENTRATION (µg/L)	LCS % REC    #	QC LIMITS REC.
Methane	205.0	206.7	101%	50 - 150

\* - Values outside of QC limits.

## MATRIX SPIKE / MATRIX SPIKE DUPLICATE RECOVERY

Lab Name: \_\_\_\_ ENSR \_\_\_\_\_

Contract: \_\_\_\_\_

Lab Code: \_\_\_\_\_ Case NO.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix Spike - EPA Sample NO.: \_\_WP3906-28 \_\_\_\_\_

COMPOUND	SPIKE ADDED (µg/L)	SAMPLE CONCENTRATION (µg/L)	MS CONCENTRATION (µg/L)	MS % REC	#	QC LIMITS REC.
Methane	205.0	189	344.8	76%		50-150

COMPOUND	SPIKE ADDED (µg/L)	MSD CONCENTRATION (µg/L)	MSD % REC	#	% RPD #	QC LIMITS RPD	REC.
Methane	205.0	345.8	77%		0.68%	50	50-150

Spike recovery: \_\_\_\_ 0 \_\_\_\_ out of \_\_\_\_ 2 \_\_\_\_ outside limits.

RPD: \_\_\_\_ 0 \_\_\_\_ out of \_\_\_\_ 1 \_\_\_\_ outside limits.

Comments:

---



---



SITE 25

GW

October 20, 1999

Mr. Paul Calligan  
Tetra Tech Nus  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

RE: Katahdin Lab Number: WP4035  
Project ID: CNC Charleston  
Project Manager: Ms. Andrea J. Colby  
Sample Receipt Date(s): 9/22/99

Dear Mr. Calligan:

Please find enclosed the following information:

- \* Report of Analysis
- \* Quality Control Data Summary
- \* Chain of Custody
- \* Confirmation

Should you have any questions or comments concerning this Report of Analysis, please do not hesitate to contact the project manager listed above. This cover letter is an integral part of the ROA.

We appreciate your continued use of our laboratory and look forward to working with you in the future. The following signature indicates technical review and acceptance of the data.

Sincerely,

KATAHDIN ANALYTICAL SERVICES

Patricia Honey  
Authorized Signature

10/20/99  
Date

**SDG NARRATIVE  
KATAHDIN ANALYTICAL SERVICES  
TETRA TECH NUS  
CASE CNC CHARLESTON**

**Sample Receipt**

The following samples were received on September 22, 1999 and were logged in under Katahdin Analytical Services work order number WP4035 for a hardcopy due date of October 22, 1999.

KATAHDIN <u>Sample No.</u>	TTNUS <u>Sample Identification</u>	GEL <u>Sample Identification</u>
WP4035-1	22GLM0301	
WP4035-2	22GLM0401	
WP4035-3	22GLM0601	
WP4035-4	25GLM0101	
WP4035-5	25GLM0501	
WP4035-6	25GLM0501D	
WP4035-7	25GLX0201	
WP4035-8	25GLX0401	
WP4035-9	22GLM0301D	
WP4035-10	25TL00201	
WP4035-11	36SLB020405	9909644-05
WP4035-12	36SLB050405	9909644-06
WP4035-13	36SLB030405	9909644-07

The samples were logged in for the analyses specified on the chain of custody form. All problems encountered and resolved during sample receipt have been documented on the applicable chain of custody forms.

Sample analyses have been performed by the methods as noted herein.

**Volatile Organic Analysis**

Three soil/sediment and ten aqueous samples were received by the Katahdin Analytical Services, Inc. GC/MS laboratory on September 22, 1999 and were specified to be analyzed by USEPA method 8260B for the analytes benzene, toluene, ethylbenzene, xylenes, MTBE, naphthalene, and EDB.

Analyses for this workorder were performed on the 5973-U (aqueous), 5970-Q (aqueous), and 5972-M (low level soils) instruments. A VSTD050 (50 ppb standard) was used for the continuing calibration standard. Internal standard and surrogate compounds were also spiked at 50 ppb.



Batch QC (VBLK, and LCS) was performed in each twelve-hour window. Results are included in this data package. The LCS QC samples were spiked with the entire list of compounds quantitated for at 50 ppb. No matrix spike/matrix spike duplicate analysis was performed on any of the samples in this workorder.

Analyses of samples WP4035-1 and -9 yielded concentrations of 1,1-dichloroethane over the upper limit of the calibration curve. Since this analyte was not requested by the client to be reported, no laboratory action was taken.

Initial analyses of samples WP4035-5 and -6 were performed at 1:50 dilutions due to the matrix, with target analyte concentrations still over the upper limit of the calibration curve, as well as surrogate recovery deviations. Reanalyses occurred at 1:200 dilutions successfully. For each sample, both sets of data are included in this data package.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" (software-generated) on the pertinent quantitation reports. All "M" flags have been dated and initialed by the analyst performing the integration. In addition, all "M" flags have been reviewed and approved by the GC/MS supervisor. Copies of each manual integration are included in the pertinent quantitation reports.

No other protocol deviations were noted by the volatile organics staff.

#### Semivolatile Organic Analysis

Three soil/sediment and nine aqueous samples were received by Katahdin Analytical Services laboratory on September 22, 1999 for analysis in accordance with 8270C for a client specified PAH list of analytes.

Extraction of the soil samples occurred following USEPA method 3550 on September 24 and 27, 1999. A laboratory control spike was extracted in each batch. Extraction of all of the aqueous samples occurred following USEPA method 3510 on September 23, 1999. A laboratory control sample/laboratory control sample duplicate was extracted in the batch.

Initial analyses of samples WP4035-5 and -6 yielded target analyte concentrations over the upper limit of the calibration curve. Reanalyses occurred at 1:4 dilutions successfully. For each sample, both sets of data are included in this data package.

Initial analysis of sample WP4035-3 yielded internal standard area recovery deviations. Reanalysis yielded similar results, confirming matrix interference. Both sets of data are included in the data package for this sample.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" by the data system. All manual integrations have been dated and initialed by the responsible analyst. Copies of each manual integration are included in the data package. All manual integrations have been reviewed and approved by the GC/MS supervisor.

No other protocol deviations were noted by the semivolatiles organics staff.

### Metals Analysis

The samples of Katahdin Work Order WP4035 were prepared and analyzed for metals in accordance with the "Test Methods for Evaluating Solid Waste", SW-846, November 1986, Third Edition.

### Inductively-Coupled Plasma (ICP) Atomic Emission Spectroscopic Analysis

Aqueous-matrix Katahdin Sample Nos. WP4035-(1-9) were digested for ICP analysis on 09/24/99 (QC Batch PI24ICW1) in accordance with USEPA Method 3010A. Katahdin Sample No. WP4035-3 was prepared with duplicate matrix-spiked aliquots during digestion.

Soil-matrix Katahdin Sample Nos. WP4035-(11-13) were digested for ICP analysis on 10/01/99 (QC Batch PJ01ICS0) in accordance with USEPA Method 3050B. The measured calcium (16.3 mg/kg) and sodium (11.5 mg/kg) concentrations of the preparation blank that is associated with this QC batch exceed the laboratory's acceptance limits. However, because the measured calcium and sodium concentrations of all associated samples are more than ten times those of the preparation blank, no corrective action was required.

ICP analyses of Katahdin Work Order WP4035 sample digestates were performed in accordance with USEPA Method 6010B, using a Thermo Jarrell Ash (TJA) Trace ICP spectrometer and a TJA 61 ICP spectrometer. All samples were analyzed within holding times and all QC criteria were met with the following comments or exceptions:

Some of the results for run QC samples (ICV, ICB, CCV, CCB, ICSA, and ICSAB) included in the accompanying data package may have exceeded acceptance limits for some elements. Please note that all client samples and batch QC samples associated with out-of-control results for run QC samples were subsequently reanalyzed for the analytes in question.

### Analysis of Mercury by Cold Vapor Atomic Absorption (CVAA) Spectrophotometry

Aqueous-matrix Katahdin Sample Nos. WP4035-(1, 2, 3, 9) were digested for mercury analysis on 09/25/99 (QC Batch PI25HGW0) in accordance with USEPA Method 7470A.

Soil-matrix Katahdin Sample Nos. WP4035-(11-13) were digested for mercury analysis on 10/07/99 (QC Batch PJ07HGS1) in accordance with USEPA Method 7471A. Katahdin Sample No. WP4035-11 was prepared with duplicate matrix-spiked aliquots.

Mercury analyses of Katahdin Work Order WP4035 sample digestates were performed using a Leeman Labs PS200 automated mercury analyzer. All samples were analyzed within holding times and all run QC criteria were met.

### Wet Chemistry Analysis

Due to IC instrument failure, alternate methods were approved for work order WP3906 by Kelly Johnson-Carper for the analysis of nitrate and sulfate. Nitrate analyses (353.2) and Sulfate analyses (375.4) were performed according to the U.S. EPA, Methods for Chemical Analysis of Water and Wastes, EPA 600/4-79-020, 1979, Revised 1983. Sulfate analyses (E300) were performed according to the U.S. EPA "Methods for the Determination of Inorganic Substances in Environmental Samples", EPA 600/R-93/100, August 1993. Analyses for Solids-Total Residue (TS) have been performed in accordance with "Contract Laboratory Program Statement of Work for Inorganic Analysis".

All samples were analyzed within analytical hold times. No protocol deviations were noted by the Wet Chemistry laboratory staff.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP4035

PAGE: 1 OF 3

COOLER: 1 OF 3

COC# -

SDG# -

DATE / TIME RECEIVED: 09-22-99 ~ 0930

DELIVERED BY: FEDC

RECEIVED BY: BKR

LIMS ENTRY BY: BKH

LIMS REVIEW BY / PM: ADL

CLIENT: TERRATECH UUS

PROJECT: CTD 68

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C +/- 2?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
ICE PACKS PRESENT <u>(Y)</u> or <u>N</u> ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 1.0

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

ADL notified VanLettigan 6  
for 9/22/99

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

4 ID 256LXC401 → Pb only container → pH > 2.0  
→ Adj. pH to pH ≤ 2.0

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP4035

PAGE: 2 OF 3

COOLER: 2 OF 3

COC# —

SDG# —

DATE / TIME RECEIVED: 09-22-99 ~ 0930

DELIVERED BY: FEDX

RECEIVED BY: BKR

LIMS ENTRY BY: BKR

LIMS REVIEW BY / PM: AL

CLIENT: T-TECH NUS

PROJECT: CTD 68

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C +/- 2?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/> ICE / ICE PACKS PRESENT <input checked="" type="checkbox"/> Y or N?			
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 0.6

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

AJC notified VanCattigan  
for 9/22/99

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

0000105

<sup>(1)</sup> Use this sheet (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

KATAHDIN ANALYTICAL SERVICES, INC.  
SAMPLE RECEIPT CONDITION REPORT  
Tel. (207) 874-2400  
Fax (207) 775-4029

LAB (WORK ORDER) # WP 4035

PAGE: 3 OF 3

COOLER: 3 OF 3

COC# -

SDG# -

DATE / TIME RECEIVED: 09-22-99 ~ 0930

DELIVERED BY: FED EX

RECEIVED BY: BKK

LIMS ENTRY BY: BKK

LIMS REVIEW BY / PM: APC

CLIENT: T-TECHNUS

PROJECT: CTD 68

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C +/- 2?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
ICE/ ICE PACKS PRESENT <input checked="" type="checkbox"/> N?			
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

TEMP BLANK TEMP (°C) = 0.6

APC notified David Calligen 6.  
for 9/22/99

COOLER TEMP (°C) = NA

(RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NPESO ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG - IN NOTES<sup>(1)</sup>:

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.

Client <b>TETRA TECH NUS</b>	Contact <b>PAUL CALLIGAN</b>	Phone # <b>(850) 385-9899</b>	Fax # <b>( )</b>
Address <b>1401 OVEN PARK DR 102</b>		City <b>TALLAHASSEE</b>	State <b>FL</b>
Purchase Order #		Proj. Name / No. <b>0219</b>	Katahdin Quote #
Zip Code <b>32306</b>			

Bill (if different than above) <b>813458369319</b>	Address
Sampler (Print / Sign) <b>Thomas Thompson</b>	
Copies To:	

LAB USE ONLY	WORK ORDER # <b>WP4035</b>	ANALYSIS AND CONTAINER TYPE PRESERVATIVES
KATAHDIN PROJECT MANAGER		

REMARKS:			
SHIPPING INFO: <input type="checkbox"/> FED EX <input type="checkbox"/> UPS <input type="checkbox"/> CLIENT			
AIRBILL NO:			
TEMP°C <input type="checkbox"/> TEMP BLANK <input type="checkbox"/> INTACT <input type="checkbox"/> NOT INTACT			

*	Sample Description	Date / Time col'd	Matrix	No. of Cntrs.	BTX Total	PAH	Met	Diss	Ani	To						
	22 GLM Ø3Ø1	9-21-99/1137	GW	10	3	2	1	3	1							
	22 GLM Ø4Ø1	9-21-99/1149	GW	10	3	2	1	3	1							
	22 GLM Ø6Ø1	9-21-99/11Ø4	GW	10	3	2	1	3	1							
	22 GLM Ø3Ø1 D	9-21-99/ØØØØ	GW	6	3	2	1									
	25 GLM Ø1Ø1	/12Ø5	GW	10	3	2		3	1	1						
	25 GLM Ø5Ø1	/17Ø5	GW	10	3	2		3	1	1						
	25 GLM Ø5Ø1 D	/—	GW	6	3	2				1						
	<del>25 GLM Ø7Ø1</del>	<del>/</del>	<del>GW</del>	<del>10</del>	<del>3</del>	<del>2</del>		<del>3</del>	<del>1</del>	<del>1</del>						
	25 GLX Ø2Ø1	/1615	GW	6	3	2				1						
	25 GLX Ø4Ø1	↓ /121Ø	GW	6	3	2				1						
	25 TL ØØ2Ø1	9-21-99 —	<del>GW</del> 99	2	2											
	/															
	/															
	/															
	/															
	/															
	/															

COMMENTS

Relinquished By: (Signature) 	Date / Time <b>9-21-99 1805</b>	Received By: (Signature) <b>813458369319</b>	Relinquished By: (Signature)	Date / Time <b>09-21-99 0920</b>	Received By: (Signature) 
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)

[illegible]



ORDER NO WP-4035

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/22/99

PHONE: 850/385-9899

FAX: 850/385- 50

DUE: 22 OCT

FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090

PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: T.THOMPSON

DELIVERED BY: FEDEX

DISPOSE: AFTER 21 NOV

ITEM	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
1	WP4035-1	22GLM0301	21 SEP 1137	22 SEP	AQ
	WP4035-2	22GLM0401	21 SEP 1149		
	WP4035-3	22GLM0601	21 SEP 1104		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Target Analyte List Metals, Total		3	100.00	300.00
Nitrate as N	353.2	3	30.00	90.00
Sulfate	375.4	3	0.00	0.00
Volatile Organics by 8260B	SW8260	3	75.00	225.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	3	125.00	375.00
Methane Subcontract		3	95.00	285.00
TOTALS		3	425.00	1275.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
2	WP4035-6	25GLM0501D	21 SEP	22 SEP	AQ
	WP4035-7	25GLX0201	21 SEP 1615		
	WP4035-8	25GLX0401	21 SEP 1210		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	3	75.00	225.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	3	125.00	375.00
Lead, Total	200.7/6010	3	20.00	60.00
TOTALS		3	220.00	660.00

ORDER NO WP-4035

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308ORDER DATE: 09/22/99  
PHONE: 850/385-9899  
FAX: 850/385-9860  
DUE: 22 OCT  
FAC.ID: CNC CHARLESTONINVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220PHONE: 412/921-7090  
PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: T.THOMPSON

DELIVERED BY: FEDEX

DISPOSE: AFTER 21 NOV

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
3	WP4035-9	22GLM0301D	21 SEP 0000	22 SEP	AQ

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	1	75.00	75.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	1	125.00	125.00
Target Analyte List Metals, Total		1	100.00	100.00
TOTALS		1	300.00	300.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
4	WP4035-10	25TL00201	21 SEP	22 SEP	AQ

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	1	75.00	75.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
5	WP4035-11	36SLB020405	21 SEP 1600	22 SEP	SL
	WP4035-12	36SLB050405	21 SEP 1120		
	WP4035-13	36SLB030405	21 SEP 1430		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	3	85.00	255.00
Solids-Total Residue (TS)	CLP/CIP SO	3	0.00	0.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	3	135.00	405.00
Target Analyte List Metals, Total		3	100.00	300.00
TPH Subcontract		3	75.00	225.00
TOTALS		3	395.00	1185.00

LABORATORY ORDER CONTINUED ON PAGE 3

10/22/99

ORDER NO WP-4035

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 09/22/99  
PHONE: 850/385-9999  
FAX: 850/385-9 J  
DUE: 22 OCT  
FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
FOSTER PLAZA 7, 661 ANDERSEN DR.  
PITTSBURGH, PA 15220

PHONE: 412/921-7090  
PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: T.THOMPSON

DELIVERED BY: FEDEX

DISPOSE: AFTER 21 NOV

LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
6 WP4035-4	25GLM0101	21 SEP 1205	22 SEP	AQ
WP4035-5	25GLM0501	21 SEP 1705		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	2	75.00	150.00
Polynuclear Aromatic Hydrocarbons	EPA 8270	2	125.00	250.00
Methane Subcontract		2	95.00	190.00
Nitrate as N	353.2	2	30.00	60.00
Sulfate	375.4	2	0.00	0.00
Lead, Total	200.7/6010	2	20.00	40.00
TOTALS		2	345.00	690.00

ORDER NOTE: QC-II+ W/NARRATIVE  
DD(KAS007QC-DB3)  
CNC CHARLESTON

REPORT COPY: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PLAZA 7  
661 ANDERSEN DR.  
PITTSBURGH, PA 15220  
REPORT & DISK

INVOICE: With Report

TOTAL ORDER AMOUNT \$4,185.00  
This is NOT an Invo:

AJC/BKR/WEST.AJC(dw)

09-29Please contact KATAHDIN ANALYTICAL SERVICES promptly if you have any questi

0999111  
1/21/00

KATAHDIN ANALYTICAL SERVICES  
Summary of Report Notes

Report Note	Note Text
#	'#' flag denotes surrogate compound recovery is out of criteria.
B	'B' flag denotes detection of this analyte in the laboratory method blank analyzed concurrently with the sample.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.



# KATAHDIN ANALYTICAL SERVICES

## Summary of Report Notes

Report Note	Note Text
A-1	Insufficient sample was provided to enable laboratory to achieve the laboratory's standard Practical Quantitation Level.
DL	'DL' flag denotes inability to calculate surrogate recovery due to sample dilution.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-13	Internal standard area(s) are out of criteria. Reanalysis confirmed matrix interference.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0101

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-004

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	3.9	B		P	1

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-4035-4  
Report Date: 10/20/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 7 of 8

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25GLM0101	Aqueous			T.THOMPSON		09/21/99	09/22/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Nitrate as N	0.29	mg/L	1.0	0.050	353.2	09/23/99	KW	
Sulfate	160.	mg/L	10	1.0	300.0	09/24/99	CF	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.

10/20/99

LJO/ejnajc(dw)/bad/msm  
PI23NOW1  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PLAZA 7  
661 ANDERSEN DR.

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-4  
**SDG:** WP4035  
**Report Date:** 10/7/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0101	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	64	%	1.0		
2-FLUOROBIPHENYL	72	%	1.0		
TERPHENYL-D14	97	%	1.0		

**Report Notes:**





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP4035-4  
SDG: WP4035  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/22/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0101	AQ	9/21/99	9/22/99	9/22/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	96	%	1.0		
1,2-DICHLOROETHANE-D4	101	%	1.0		
TOLUENE-D8	98	%	1.0		
P-BROMOFLUOROBENZENE	106	%	1.0		

Report Notes:

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0501

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-005

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	7.3			P	1

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-4035-5  
Report Date: 10/20/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 8 of 8

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25GLM0501	Aqueous			T.THOMPSON		09/21/99	09/22/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Nitrate as N	<0.050	mg/L	1.0	0.050	353.2	09/23/99	KW	
Sulfate	40.	mg/L	10	1.0	300.0	09/24/99	CF	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.

10/20/99

LJO/ejnajc(dw)/bad/msm  
PI23NOW1

CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PLAZA 7  
661 ANDERSEN DR.

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

Proj. ID: CNC CHARLESTON

Lab Number: WP4035-5  
SDG: WP4035  
Report Date: 10/7/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	E280	ug/L	1.1	10	10
2-METHYLNAPHTHALENE	100	ug/L	1.1	10	10
ACENAPHTHYLENE	<10	ug/L	1.1	10	10
ACENAPHTHENE	<10	ug/L	1.1	10	10
FLUORENE	<10	ug/L	1.1	10	10
PHENANTHRENE	<10	ug/L	1.1	10	10
ANTHRACENE	<10	ug/L	1.1	10	10
FLUORANTHENE	<10	ug/L	1.1	10	10
PYRENE	<10	ug/L	1.1	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.1	10	10
CHRYSENE	<10	ug/L	1.1	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.1	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.1	10	10
BENZO[A]PYRENE	<10	ug/L	1.1	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.1	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.1	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.1	10	10
NITROBENZENE-D5	60	%	1.1		
2-FLUOROBIPHENYL	100	%	1.1		
TERPHENYL-D14	79	%	1.1		

Report Notes: E, A-1



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP4035-5DL  
SDG: WP4035  
Report Date: 10/7/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 10/1/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	480	ug/L	4.2	42	10
2-METHYLNAPHTHALENE	160	ug/L	4.2	42	10
ACENAPHTHYLENE	<42	ug/L	4.2	42	10
ACENAPHTHENE	<42	ug/L	4.2	42	10
FLUORENE	<42	ug/L	4.2	42	10
PHENANTHRENE	<42	ug/L	4.2	42	10
ANTHRACENE	<42	ug/L	4.2	42	10
FLUORANTHENE	<42	ug/L	4.2	42	10
PYRENE	<42	ug/L	4.2	42	10
BENZO(A)ANTHRACENE	<42	ug/L	4.2	42	10
CHRYSENE	<42	ug/L	4.2	42	10
BENZO(B)FLUORANTHENE	<42	ug/L	4.2	42	10
BENZO(K)FLUORANTHENE	<42	ug/L	4.2	42	10
BENZO(A)PYRENE	<42	ug/L	4.2	42	10
INDENO[1,2,3-CD]PYRENE	<42	ug/L	4.2	42	10
DIBENZ[A,H]ANTHRACENE	<42	ug/L	4.2	42	10
BENZO[G,H,I]PERYLENE	<42	ug/L	4.2	42	10
NITROBENZENE-D5	DL	%	4.2		
2-FLUOROBIPHENYL	DL	%	4.2		
TERPHENYL-D14	DL	%	4.2		

Report Notes: O-2, DL

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-5  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501	AQ	9/21/99	9/22/99	9/23/99	HMP	5030	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	E27000	ug/L	50	250	5
TOLUENE	E30000	ug/L	50	250	5
1,2-DIBROMOETHANE	<250	ug/L	50	250	5
ETHYLBENZENE	4300	ug/L	50	250	5
NAPHTHALENE	660	ug/L	50	250	5
MTBE	E23000	ug/L	50	250	5
TOTAL XYLENES	14000	ug/L	50	250	5
DIBROMOFLUOROMETHANE	83	%	50		
1,2-DICHLOROETHANE-D4	#64	%	50		
TOLUENE-D8	98	%	50		
P-BROMOFLUOROBENZENE	100	%	50		

**Report Notes:** E, #, O-2



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-SDL  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/24/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501	AQ	9/21/99	9/22/99	9/24/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	25000	ug/L	200	1000	5
TOLUENE	35000	ug/L	200	1000	5
1,2-DIBROMOETHANE	<1000	ug/L	200	1000	5
ETHYLBENZENE	3000	ug/L	200	1000	5
NAPHTHALENE	J700	ug/L	200	1000	5
MTBE	33000	ug/L	200	1000	5
TOTAL XYLENES	12000	ug/L	200	1000	5
DIBROMOFLUOROMETHANE	105	%	200		
1,2-DICHLOROETHANE-D4	111	%	200		
TOLUENE-D8	102	%	200		
P-BROMOFLUOROBENZENE	100	%	200		

**Report Notes:** J, O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLM0501D

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-006

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	7.0			P	1

Comments:





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

Proj. ID: CNC CHARLESTON

Lab Number: WP4035-6  
SDG: WP4035  
Report Date: 10/7/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: EPA 8270  
Date Analyzed: 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501D	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	E220	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	68	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	48	%	1.0		
2-FLUOROBIPHENYL	73	%	1.0		
TERPHENYL-D14	61	%	1.0		

Report Notes: E

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-6DL  
**SDG:** WP4035  
**Report Date:** 10/7/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 10/1/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501D	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	470	ug/L	4.0	40	10
2-METHYLNAPHTHALENE	170	ug/L	4.0	40	10
ACENAPHTHYLENE	<40	ug/L	4.0	40	10
ACENAPHTHENE	<40	ug/L	4.0	40	10
FLUORENE	<40	ug/L	4.0	40	10
PHENANTHRENE	<40	ug/L	4.0	40	10
ANTHRACENE	<40	ug/L	4.0	40	10
FLUORANTHENE	<40	ug/L	4.0	40	10
PYRENE	<40	ug/L	4.0	40	10
BENZO[A]ANTHRACENE	<40	ug/L	4.0	40	10
CHRYSENE	<40	ug/L	4.0	40	10
BENZO[B]FLUORANTHENE	<40	ug/L	4.0	40	10
BENZO[K]FLUORANTHENE	<40	ug/L	4.0	40	10
BENZO[A]PYRENE	<40	ug/L	4.0	40	10
INDENO[1,2,3-CD]PYRENE	<40	ug/L	4.0	40	10
DIBENZ[A,H]ANTHRACENE	<40	ug/L	4.0	40	10
BENZO[G,H,I]PERYLENE	<40	ug/L	4.0	40	10
NITROBENZENE-D5	DL	%	4.0		
2-FLUOROBIPHENYL	DL	%	4.0		
TERPHENYL-D14	DL	%	4.0		

**Report Notes:** O-2, DL



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP4035-6  
SDG: WP4035  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501D	AQ	9/21/99	9/22/99	9/23/99	HMP	5030	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	E26000	ug/L	50	250	5
TOLUENE	E31000	ug/L	50	250	5
1,2-DIBROMOETHANE	<250	ug/L	50	250	5
ETHYLBENZENE	4300	ug/L	50	250	5
NAPHTHALENE	780	ug/L	50	250	5
MTBE	E23000	ug/L	50	250	5
TOTAL XYLENES	15000	ug/L	50	250	5
DIBROMOFLUOROMETHANE	82	%	50		
1,2-DICHLOROETHANE-D4	#63	%	50		
TOLUENE-D8	97	%	50		
P-BROMOFLUOROBENZENE	101	%	50		

Report Notes: E, #, O-2

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-6DL  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
  
**Method:** SW8260  
**Date Analyzed:** 9/24/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLM0501D	AQ	9/21/99	9/22/99	9/24/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	26000	ug/L	200	1000	5
TOLUENE	38000	ug/L	200	1000	5
1,2-DIBROMOETHANE	<1000	ug/L	200	1000	5
ETHYLBENZENE	3200	ug/L	200	1000	5
NAPHTHALENE	J760	ug/L	200	1000	5
MTBE	33000	ug/L	200	1000	5
TOTAL XYLENES	13000	ug/L	200	1000	5
DIBROMOFLUOROMETHANE	103	%	200		
1,2-DICHLOROETHANE-D4	108	%	200		
TOLUENE-D8	103	%	200		
P-BROMOFLUOROBENZENE	100	%	200		

**Report Notes:** J, O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25GLX0201

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-007

Concentration Units (ug/L or mg/Kg dry weight): ug/L

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	1.6	B		P	1

Comments:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-7  
**SDG:** WP4035  
**Report Date:** 10/7/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLX0201	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	46	%	1.0		
2-FLUOROBIPHENYL	56	%	1.0		
TERPHENYL-D14	61	%	1.0		

Report Notes:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP4035-7  
SDG: WP4035  
Report Date: 10/6/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLX0201	AQ	9/21/99	9/22/99	9/23/99	HMP	5030	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	83	%	1.0		
1,2-DICHLOROETHANE-D4	73	%	1.0		
TOLUENE-D8	93	%	1.0		
P-BROMOFLUOROBENZENE	92	%	1.0		

Report Notes:

## PREPARATION BLANKS

Lab Name: Katahdin Analytical Services

Sample ID: PBWPI24ICW1

Matrix: WATER

SDG Name: WP4035

QC Batch ID: PI24ICW1

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	RESULT	C
ALUMINUM	19.080	B
ANTIMONY	1.810	U
ARSENIC	2.070	U
BARIUM	1.810	B
BERYLLIUM	0.330	U
CADMIUM	1.940	U
CALCIUM	27.640	B
CHROMIUM	4.310	U
COBALT	4.450	U
COPPER	1.620	U
IRON	8.920	B
LEAD	1.090	U
MAGNESIUM	17.160	U
MANGANESE	0.970	U
NICKEL	13.210	U
POTASSIUM	449.540	U
SELENIUM	2.570	U
SILVER	2.540	U
SODIUM	84.140	B
THALLIUM	4.490	U
VANADIUM	3.580	U
ZINC	5.190	B





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-8  
**SDG:** WP4035  
**Report Date:** 10/7/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 10/1/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLX0401	AQ	9/21/99	9/22/99	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<12	ug/L	1.2	12	10
2-METHYLNAPHTHALENE	<12	ug/L	1.2	12	10
ACENAPHTHYLENE	<12	ug/L	1.2	12	10
ACENAPHTHENE	<12	ug/L	1.2	12	10
FLUORENE	<12	ug/L	1.2	12	10
PHENANTHRENE	<12	ug/L	1.2	12	10
ANTHRACENE	<12	ug/L	1.2	12	10
FLUORANTHENE	<12	ug/L	1.2	12	10
PYRENE	<12	ug/L	1.2	12	10
BENZO[A]ANTHRACENE	<12	ug/L	1.2	12	10
CHRYSENE	<12	ug/L	1.2	12	10
BENZO[B]FLUORANTHENE	<12	ug/L	1.2	12	10
BENZO[K]FLUORANTHENE	<12	ug/L	1.2	12	10
BENZO[A]PYRENE	<12	ug/L	1.2	12	10
INDENO[1,2,3-CD]PYRENE	<12	ug/L	1.2	12	10
DIBENZ[A,H]ANTHRACENE	<12	ug/L	1.2	12	10
BENZO[G,H,I]PERYLENE	<12	ug/L	1.2	12	10
NITROBENZENE-D5	54	%	1.2		
2-FLUOROBIPHENYL	64	%	1.2		
TERPHENYL-D14	74	%	1.2		

**Report Notes:** A-1

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-8  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25GLX0401	AQ	9/21/99	9/22/99	9/23/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	130	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	88	%	1.0		
1,2-DICHLOROETHANE-D4	87	%	1.0		
TOLUENE-D8	96	%	1.0		
P-BROMOFLUOROBENZENE	101	%	1.0		

Report Notes:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP4035-10  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25TL00201	AQ	9/21/99	9/22/99	9/23/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	88	%	1.0		
1,2-DICHLOROETHANE-D4	84	%	1.0		
TOLUENE-D8	96	%	1.0		
P-BROMOFLUOROBENZENE	99	%	1.0		

Report Notes:

## PREPARATION BLANKS

Lab Name: Katahdin Analytical Services

Sample ID: PBSPJ01ICS0

Matrix: SOIL

SDG Name: WP4035

QC Batch ID: PJ01ICS0

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	RESULT	C
ALUMINUM	9.223	B
ANTIMONY	-0.205	B
ARSENIC	0.210	U
BARIUM	0.061	B
BERYLLIUM	0.020	U
CADMIUM	0.190	U
CALCIUM	16.324	
CHROMIUM	0.407	B
COBALT	0.060	U
COPPER	0.060	U
IRON	0.669	B
LEAD	0.110	U
MAGNESIUM	1.770	B
MANGANESE	0.053	B
NICKEL	1.320	U
POTASSIUM	44.950	U
SELENIUM	0.260	U
SILVER	0.070	U
SODIUM	11.547	
THALLIUM	0.450	U
VANADIUM	0.060	U
ZINC	0.153	B

## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSSPJ01ICS0

Matrix: SOIL

SDG Name: WP4035

QC Batch ID: PJ01ICS0

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	TRUE	FOUND	% R	LIMITS (%)	
ALUMINUM	5720.0	5284.82	92.4	66	134
ANTIMONY	26.6	30.85	116.0	13	186
ARSENIC	163.0	179.02	109.8	62	138
BARIUM	195.0	246.23	126.3	66	134
BERYLLIUM	78.9	86.75	109.9	72	128
CADMIUM	114.0	115.92	101.7	74	124
CALCIUM	1280.0	1286.99	100.5	70	130
CHROMIUM	175.0	202.59	115.8	69	131
COBALT	73.7	83.62	113.5	70	130
COPPER	91.0	95.87	105.4	71	128
IRON	9080.0	8892.45	97.9	53	146
LEAD	66.0	83.22	126.1	68	132
MAGNESIUM	1210.0	1178.63	97.4	73	126
MANGANESE	261.0	289.32	110.9	78	122
NICKEL	68.3	75.55	110.6	56	144
POTASSIUM	1500.0	1373.71	91.6	64	136
SELENIUM	123.0	123.79	100.6	74	126
SILVER	57.2	53.95	94.3	71	128
SODIUM	1380.0	1402.75	101.6	68	133
THALLIUM	80.0	99.81	124.8	57	142
VANADIUM	95.4	108.52	113.8	68	132
ZINC	190.0	210.74	110.9	76	124

## PREPARATION BLANKS

Lab Name: Katahdin Analytical Services

Sample ID: PBSPJ07HGS1

Matrix: SOIL

SDG Name: WP4035

QC Batch ID: PJ07HGS1

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	RESULT	C
MERCURY	0.010	U

## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSSPJ07HGS1

Matrix: SOIL

SDG Name: WP4035

QC Batch ID: PJ07HGS1

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	TRUE	FOUND	% R	LIMITS (%)	
MERCURY	1.8	2.32	128.9	54	146

## PREPARATION BLANKS

Lab Name: Katahdin Analytical Services

Sample ID: PBWPI24ICW1

Matrix: WATER

SDG Name: WP4035

QC Batch ID: PI24ICW1

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	RESULT	C
ALUMINUM	19.080	B
ANTIMONY	1.810	U
ARSENIC	2.070	U
BARIUM	1.810	B
BERYLLIUM	0.330	U
CADMIUM	1.940	U
CALCIUM	27.640	B
CHROMIUM	4.310	U
COBALT	4.450	U
COPPER	1.620	U
IRON	8.920	B
LEAD	1.090	U
MAGNESIUM	17.160	U
MANGANESE	0.970	U
NICKEL	13.210	U
POTASSIUM	449.540	U
SELENIUM	2.570	U
SILVER	2.540	U
SODIUM	84.140	B
THALLIUM	4.490	U
VANADIUM	3.580	U
ZINC	5.190	B



## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSWPI24ICW1

Matrix: WATER

SDG Name: WP4035

QC Batch ID: PI24ICW1

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	TRUE	FOUND	% R	LIMITS (%)	
ALUMINUM	2000.0	1957.03	97.9	80	120
ANTIMONY	500.0	501.39	100.3	80	120
ARSENIC	2000.0	1935.06	96.8	80	120
BARIUM	2000.0	2102.62	105.1	80	120
BERYLLIUM	50.0	52.87	105.7	80	120
CADMIUM	50.0	53.05	106.1	80	120
CALCIUM	2500.0	2678.37	107.1	80	120
CHROMIUM	200.0	212.83	106.4	80	120
COBALT	500.0	527.54	105.5	80	120
COPPER	250.0	248.67	99.5	80	120
IRON	1000.0	1070.93	107.1	80	120
LEAD	500.0	550.63	110.1	80	120
MAGNESIUM	5000.0	4828.88	96.6	80	120
MANGANESE	500.0	527.50	105.5	80	120
NICKEL	500.0	539.85	108.0	80	120
POTASSIUM	25000.0	23749.69	95.0	80	120
SELENIUM	2000.0	1853.45	92.7	80	120
SILVER	50.0	43.11	86.2	80	120
SODIUM	7500.0	7501.04	100.0	80	120
THALLIUM	2000.0	2216.78	110.8	80	120
VANADIUM	500.0	524.53	104.9	80	120
ZINC	500.0	499.80	100.0	80	120

## PREPARATION BLANKS

Lab Name: Katahdin Analytical Services

Sample ID: PBWPI25HGW0

Matrix: WATER

SDG Name: WP4035

QC Batch ID: PI25HGW0

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	RESULT	C
MERCURY	0.020	U

## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSWPI25HGW0

Matrix: WATER

SDG Name: WP4035

QC Batch ID: PI25HGW0

Concentration Units (ug/L or mg/Kg dry weight): ug/L				
Analyte	TRUE	FOUND	% R	LIMITS (%)
MERCURY	5.0	4.86	97.2	80 120

5A  
SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 22GLM0601S

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-003S

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	Spiked		Sample		Spike	%R	Q	Control Limits (%R)		
	Sample	Result	Result	C				Low	High	M
ALUMINUM	2346.3500		136.5400		2000	110.5		75	125	P
ANTIMONY	545.4400		-1.4000	U	500	109.1		75	125	P
ARSENIC	2239.4800		6.0600	B	2000	111.7		75	125	P
BARIUM	2226.8100		65.3700		2000	108.1		75	125	P
BERYLLIUM	55.9100		0.2500	U	50	111.8		75	125	P
CADMIUM	59.5000		1.0800	U	50	119.0		75	125	P
CALCIUM	395830.5000		397131.8300		2500	-52.1		75	125	P
CHROMIUM	216.7400		-3.8000	U	200	108.4		75	125	P
COBALT	642.8200		102.4300		500	108.1		75	125	P
COPPER	269.6900		-0.9900	U	250	107.9		75	125	P
IRON	18672.9600		17767.2500		1000	90.6		75	125	P
LEAD	527.4600		1.3400	B	500	105.2		75	125	P
MAGNESIUM	152163.8000		147898.0800		5000	85.3		75	125	P
MANGANESE	6093.8900		5608.3500		500	97.1		75	125	P
NICKEL	588.7900		31.0100	B	500	111.6		75	125	P
POTASSIUM	41558.4200		14461.4900		25000	108.4		75	125	P
SELENIUM	2109.6200		0.2100	U	2000	105.5		75	125	P
SILVER	47.5900		-3.9200	U	50	95.2		75	125	P
SODIUM	1587538.3300		1600947.6300		7500	-178.8		75	125	P
THALLIUM	2070.8200		-0.3700	U	2000	103.5		75	125	P
VANADIUM	550.5300		-1.6200	U	500	110.1		75	125	P
ZINC	573.9200		29.1400		500	109.0		75	125	P

Comments:

5A  
SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 22GLM0601S

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-003P

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	Spiked		Sample		Spike	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
ALUMINUM	2349.6500		136.5400		2000	110.7		75	125	P
ANTIMONY	546.4900		-1.4000	U	500	109.3		75	125	P
ARSENIC	2246.7500		6.0600	B	2000	112.0		75	125	P
BARIUM	2248.6000		65.3700		2000	109.2		75	125	P
BERYLLIUM	57.0300		0.2500	U	50	114.1		75	125	P
CADMIUM	61.1500		1.0800	U	50	122.3		75	125	P
CALCIUM	397133.0500		397131.8300		2500	0.0		75	125	P
CHROMIUM	217.6200		-3.8000	U	200	108.8		75	125	P
COBALT	652.8700		102.4300		500	110.1		75	125	P
COPPER	272.5500		-0.9900	U	250	109.0		75	125	P
IRON	19120.2600		17767.2500		1000	135.3		75	125	P
LEAD	521.9400		1.3400	B	500	104.1		75	125	P
MAGNESIUM	155943.0800		147898.0800		5000	160.9		75	125	P
MANGANESE	6243.1600		5608.3500		500	127.0		75	125	P
NICKEL	594.4000		31.0100	B	500	112.7		75	125	P
POTASSIUM	42151.4700		14461.4900		25000	110.8		75	125	P
SELENIUM	2112.5200		0.2100	U	2000	105.6		75	125	P
SILVER	47.9100		-3.9200	U	50	95.8		75	125	P
SODIUM	1639213.8600		1600947.6300		7500	510.2		75	125	P
THALLIUM	2059.0100		-0.3700	U	2000	103.0		75	125	P
VANADIUM	555.3900		-1.6200	U	500	111.1		75	125	P
ZINC	584.0600		29.1400		500	111.0		75	125	P

Comments:

## SPIKE DUPLICATES

Lab Name: Katahdin Analytical Services

Client Field ID: 22GLM0601

Matrix: WATER

SDG Name: WP4035

Percent Solids: 0.00

Lab Sample ID: WP4035-003

Concentration Units (ug/L or mg/Kg dry weight): ug/L

Analyte	Control Limits	Spike Result	C	Spike Dup. Result	C	RPD	Q	M
ALUMINUM		2346.3500		2349.6500		0.1		P
ANTIMONY		545.4400		546.4900		0.2		P
ARSENIC		2239.4800		2246.7500		0.3		P
BARIUM		2226.8100		2248.6000		1.0		P
BERYLLIUM		55.9100		57.0300		2.0		P
CADMIUM		59.5000		61.1500		2.7		P
CALCIUM		395830.5000		397133.0500		0.3		P
CHROMIUM		216.7400		217.6200		0.4		P
COBALT		642.8200		652.8700		1.6		P
COPPER		269.6900		272.5500		1.1		P
IRON		18672.9600		19120.2600		2.4		P
LEAD		527.4600		521.9400		1.1		P
MAGNESIUM		152163.8000		155943.0800		2.5		P
MANGANESE		6093.8900		6243.1600		2.4		P
NICKEL		588.7900		594.4000		0.9		P
POTASSIUM		41558.4200		42151.4700		1.4		P
SELENIUM		2109.6200		2112.5200		0.1		P
SILVER	15	47.5900		47.9100		0.7		P
SODIUM		1587538.3300		1639213.8600		3.2		P
THALLIUM		2070.8200		2059.0100		0.6		P
VANADIUM		550.5300		555.3900		0.9		P
ZINC		573.9200		584.0600		1.8		P

Comments:

## SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 36SLB020405S

Matrix: SOIL

SDG Name: WP4035

Percent Solids: 75.5

Lab Sample ID: WP4035-011S

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	Spiked		Sample	C	Spike	%R	Q	Control Limits (%R)		M
	Sample	Result	Result		Added			Low	High	
MERCURY		0.3277	0.1696		0.18	87.8		75	125	CV

Comments:

## SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 36SLB020405S

Matrix: SOIL

SDG Name: WP4035

Percent Solids: 75.5

Lab Sample ID: WP4035-011P

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	Spiked		Sample		Spike Added	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
MERCURY		0.3739	0.1696		0.18	113.5		75	125	CV

Comments:



5D

SPIKE DUPLICATES

Lab Name: Katahdin Analytical Services

Client Field ID: 36SLB020405

Matrix: SOIL

SDG Name: WP4035

Percent Solids: 75.5

Lab Sample ID: WP4035-011

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	Control Limits	Spike Result	C	Spike Dup. Result	C	RPD	Q	M
MERCURY		0.3277		0.3739		13.2		CV

Comments:



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LABORATORY METHOD BLANK RESULTS

SAMPLE DESCRIPTION		MATRIX		
METHOD BLANK		Aqueous		
ANALYTE	ANALYZED UNITS	METHOD	RESULT	NOTES
Nitrate as N	09-23-99 mg/L	353.2	<0.050	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-5



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LAB CONTROL SPIKE RESULTS

SAMPLE DESCRIPTION					MATRIX		
LAB CONTROL SPIKE					Aqueous		
ANALYTE	ANALYZED UNITS	METHOD	SPK	SPK RES	% REC	LIMITS	NOTES
Nitrate as N	09-23-99 mg/L	353.2	1.00	0.906	91		

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-5



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF DUPLICATE SAMPLE RESULTS

SAMPLE DESCRIPTION						MATRIX		
QC DUPLICATE						Aqueous		
ANALYTE	ANALYZED UNITS	METHOD	*PQL	RESULT	DUP #1	RPD	LIMITS	NOTES
Nitrate as N	09-23-99 mg/L	353.2	0.050	<0.050	<0.050	-0.00		

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-5



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF SAMPLE MATRIX SPIKE RESULTS

SAMPLE DESCRIPTION					MATRIX			
QC SPIKE					Aqueous			
ANALYTE	ANALYZED UNITS	METHOD	SPK	RESULT	SPK RES	% REC	LIMITS	NOTES
Nitrate as N	09-23-99 mg/L	353.2	0.500	<0.050	0.397	79		

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-5



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LABORATORY METHOD BLANK RESULTS

SAMPLE DESCRIPTION		MATRIX		
METHOD BLANK		Aqueous		
ANALYTE	ANALYZED UNITS	METHOD	RESULT	NOTES
Sulfate	10-11-99 mg/L	375.4	<1.0	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-1



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LAB CONTROL SPIKE RESULTS

SAMPLE DESCRIPTION				MATRIX			
LAB CONTROL SPIKE				Aqueous			
ANALYTE	ANALYZED UNITS	METHOD	SPK	SPK RES	% REC	LIMITS	NOTES
Sulfate	10-11-99 mg/L	375.4	250	221	88		

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-1



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LABORATORY METHOD BLANK RESULTS

SAMPLE DESCRIPTION		MATRIX		
METHOD BLANK		Aqueous		
ANALYTE	ANALYZED UNITS	METHOD	RESULT	NOTES
Sulfate	09-24-99 mg/L	300.0	<1.0	

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-4





CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LAB CONTROL SPIKE RESULTS

SAMPLE DESCRIPTION

MATRIX

LAB CONTROL SPIKE

Aqueous

ANALYTE	ANALYZED UNITS	METHOD	SPK	SPK RES	% REC	LIMITS	NOTES
Sulfate	09-24-99 mg/L	300.0	10.0	9.90	99		

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

10/19/99

Lab Number: WP4035-4

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LABORATORY METHOD BLANK RESULTS

SAMPLE DESCRIPTION		MATRIX		
METHOD BLANK		Solid/Soil/Sludge		
ANALYTE	ANALYZED UNITS	METHOD	RESULT	NOTES
Solids-Total Residue (TS)	09-28-99 wt %	CLP/CI	<0.10	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
See cover letter for additional information

[1] Sample Preparation on 09-27-99 by JF

10/19/99

Lab Number: WP4035-11



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF LAB CONTROL SPIKE RESULTS

SAMPLE DESCRIPTION

MATRIX

LAB CONTROL SPIKE

Solid/Soil/Sludge

ANALYTE	ANALYZED UNITS	METHOD	SPK	SPK RES	% REC	LIMITS	NOTES
Solids-Total Residue (TS)	09-28-99 wt %	CLP/CI	90	88.7	99		1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

[1] Sample Preparation on 09-27-99 by JF

10/19/99

Lab Number: WP4035-11



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

PROJECT: CTO #68

REPORT OF DUPLICATE SAMPLE RESULTS

SAMPLE DESCRIPTION						MATRIX			
QC DUPLICATE						Solid/Soil/Sludge			
ANALYTE	ANALYZED UNITS	METHOD	*PQL	RESULT	DUP #1	RPD	LIMITS	NOTES	
Solids- Total Residue (TS)	09-28-99 wt %	CLP/CI	0.10	75.	75.5	0.66			1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values. See cover letter for additional information

[1] Sample Preparation on 09-27-99 by JF

10/19/99

Lab Number: WP4035-11

4B  
SEMIVOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

**SBLK;092399**

Lab Name: Katahdin Analytical Services

SDG No.: WP4035

Lab File ID: X2963

Lab Sample ID: SBLK;092399

Instrument ID: 5970-X

Date Extracted: 9/23/99

GC Column: RTX-5 ID: 0.25 (mm)

Date Analyzed: 09/30/99

Matrix: (soil/water) WATER

Time Analyzed: 9:31

Level: (low/med) LOW

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCS;092399	LCS;092399	X2964	9/30/99	10:16:00 AM
LCSD;092399	LCSD;092399	X2965	9/30/99	11:00:00 AM
22GLM0401	WP4035-2	X2967	9/30/99	12:29:00 PM
22GLM0601	WP4035-3	X2968	9/30/99	1:14:00 PM
25GLM0101	WP4035-4	X2969	9/30/99	1:58:00 PM
25GLM0501	WP4035-5	X2970	9/30/99	2:43:00 PM
25GLM0501D	WP4035-6	X2971	9/30/99	3:28:00 PM
25GLX0201	WP4035-7	X2972	9/30/99	4:13:00 PM
22GLM0301D	WP4035-9	X2974	9/30/99	5:42:00 PM
22GLM0301	WP4035-1	X2975	9/30/99	6:26:00 PM
22GLM0601	WP4035-3RA	X2976	9/30/99	7:11:00 PM
25GLX0401	WP4035-8	X2982	10/1/99	1:03:00 PM
25GLM0501D	WP4035-6DL	X2986	10/1/99	4:01:00 PM
25GLM0501	WP4035-5DL	X2987	10/1/99	4:46:00 PM

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** SBLK;092399  
**SDG:** WP4035  
**Report Date:** 10/7/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** EPA 8270  
**Date Analyzed:** 9/30/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
SBLK;092399	AQ	-	-	9/23/99	LAP	EPA 3510	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<10	ug/L	1.0	10	10
2-METHYLNAPHTHALENE	<10	ug/L	1.0	10	10
ACENAPHTHYLENE	<10	ug/L	1.0	10	10
ACENAPHTHENE	<10	ug/L	1.0	10	10
FLUORENE	<10	ug/L	1.0	10	10
PHENANTHRENE	<10	ug/L	1.0	10	10
ANTHRACENE	<10	ug/L	1.0	10	10
FLUORANTHENE	<10	ug/L	1.0	10	10
PYRENE	<10	ug/L	1.0	10	10
BENZO[A]ANTHRACENE	<10	ug/L	1.0	10	10
CHRYSENE	<10	ug/L	1.0	10	10
BENZO[B]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[K]FLUORANTHENE	<10	ug/L	1.0	10	10
BENZO[A]PYRENE	<10	ug/L	1.0	10	10
INDENO[1,2,3-CD]PYRENE	<10	ug/L	1.0	10	10
DIBENZ[A,H]ANTHRACENE	<10	ug/L	1.0	10	10
BENZO[G,H,I]PERYLENE	<10	ug/L	1.0	10	10
NITROBENZENE-D5	76	%	1.0		
2-FLUOROBIPHENYL	66	%	1.0		
TERPHENYL-D14	73	%	1.0		

Report Notes:

# Katahdin Analytical Services

## LCS/LCSD Report

Sample	File Name	Date Acquired	Time inj	Analyst	Matrix	Method
LCS;092399	X2964	9/30/99	10:16	KRT	AQ	8270
LCSD;092399	X2965	9/30/99	11:00	KRT	AQ	8270

Compound Name	Spk Amt ug/L	LCS Result ug/L	LCSD Result ug/L	LCS Rec (%)	LCSD Rec (%)	Rec. Limits (%)	RPD (%)	RPD Limit (%)
2-METHYLNAPHTHALENE	50	22.6	22.6	*45	*45	70-130	0	30
ACENAPHTHENE	50	29.3	34.9	*59	70	70-130	17	30
ACENAPHTHYLENE	50	27.3	33.5	*55	*67	70-130	20	30
ANTHRACENE	50	29.0	38.8	*58	78	70-130	29	30
BENZO[A]ANTHRACENE	50	28.8	33.4	*58	*67	70-130	14	30
BENZO[A]PYRENE	50	29.0	41.7	*58	83	70-130	*35	30
BENZO[B]FLUORANTHENE	50	30.5	45.3	*61	91	70-130	*39	30
BENZO[G,H,I]PERYLENE	50	27.3	38.6	*55	77	70-130	*33	30
BENZO[K]FLUORANTHENE	50	29.5	47.9	*59	96	70-130	*48	30
CHRYSENE	50	33.3	42.8	*67	86	70-130	25	30
DIBENZ[A,H]ANTHRACENE	50	27.1	39.2	*54	78	70-130	*36	30
FLUORANTHENE	50	31.6	44.4	*63	89	70-130	*34	30
FLUORENE	50	25.8	32.3	*52	*65	70-130	22	30
INDENO[1,2,3-CD]PYRENE	50	22.9	24.8	*46	*50	70-130	8.3	30
NAPHTHALENE	50	30.9	33.9	*62	*68	70-130	9.2	30
PHENANTHRENE	50	29.5	40.0	*59	80	70-130	30	30
PYRENE	50	35.9	46.2	72	92	70-130	24	30

RPD = (lcs rec - lcsd rec) / [(lcsd rec + lcsd rec)/2] \* 100

\* Out of Limits

0000085

4A  
VOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

Lab Name: Katahdin Analytical Services

SDG No.: WP4035

VBKQ22B

Lab File ID: Q6709

Lab Sample ID: VBKQ22B

Date Analyzed: 09/22/99

Time Analyzed: 18:34

GC Column: RTX-502 ID: 0.53 (mm)

Heated Purge: (Y/N) N

Instrument ID: 5970-Q

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCSQ22A	LCSQ22A	Q6707	9/22/99	5:07:00 PM
22GLM0301	WP4035-1	Q6712	9/22/99	8:34:00 PM
22GLM0401	WP4035-2	Q6713	9/22/99	9:12:00 PM
22GLM0601	WP4035-3	Q6714	9/22/99	9:49:00 PM
25GLM0101	WP4035-4	Q6715	9/22/99	10:27:00 PM
25GLX0401	WP4035-8	Q6719	9/23/99	1:02:00 AM
22GLM0301D	WP4035-9	Q6720	9/23/99	1:40:00 AM
25TL00201	WP4035-10	Q6721	9/23/99	2:19:00 AM





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: VBLKQ22B  
SDG: WP4035  
Report Date: 10/6/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 9/22/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKQ22B	AQ	-	-	9/22/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	92	%	1.0		
1,2-DICHLOROETHANE-D4	84	%	1.0		
TOLUENE-D8	92	%	1.0		
P-BROMOFLUOROBENZENE	91	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

Lab File: Q6707

Sample ID: LCSQ22A

Date Run: 9/22/99

Analyst: JSS

Time Injected: 5:07:00 PM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	43.4	87	60-140
BENZENE	50	47.4	95	60-140
ETHYLBENZENE	50	53.3	106	60-140
MTBE	50	46.4	93	60-140
NAPHTHALENE	50	61.6	123	60-140
TOLUENE	50	44.2	88	60-140
TOTAL XYLENES	150	140	93	60-140

\* Out of Limits

1

0000094

4A  
VOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

Lab Name: Katahdin Analytical Services

SDG No.: WP4035

VBLKQ23A

Lab File ID: Q6724

Lab Sample ID: VBLKQ23A

Date Analyzed: 09/23/99

Time Analyzed: 10:57

GC Column: RTX-502 ID: 0.53 (mm)

Heated Purge: (Y/N) N

Instrument ID: 5970-Q

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCSQ23A	LCSQ23A	Q6723	9/23/99	10:03:00 AM
25GLX0201	WP4035-7	Q6726	9/23/99	1:41:00 PM
25GLM0501	WP4035-5	Q6731	9/23/99	4:51:00 PM
25GLM0501D	WP4035-6	Q6732	9/23/99	5:28:00 PM

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKQ23A  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKQ23A	AQ	-	-	9/23/99	HMP	5030	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	86	%	1.0		
1,2-DICHLOROETHANE-D4	78	%	1.0		
TOLUENE-D8	97	%	1.0		
P-BROMOFLUOROBENZENE	97	%	1.0		

**Report Notes:**

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: Q6723**

**Sample ID: LCSQ23A**

**Date Run: 9/23/99**

**Analyst: HMP**

**Time Injected: 10:03:00 AM**

**Matrix: AQ**

<b>Compound Name</b>	<b>Spike Amt (ug/L)</b>	<b>Result (ug/L)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	54.6	109	60-140
BENZENE	50	50.7	101	60-140
ETHYLBENZENE	50	56.9	114	60-140
MTBE	50	58.6	117	60-140
NAPHTHALENE	50	54.7	109	60-140
TOLUENE	50	51.4	103	60-140
TOTAL XYLENES	150	157	105	60-140

**\* Out of Limits**

**1**

**0000097**

4A  
VOLATILE ORGANICS METHOD BLANK SUMMARY

EPA SAMPLE NO.

Lab Name: Katahdin Analytical Services

SDG No.: WP4035

VBLKU24A

Lab File ID: U1070

Lab Sample ID: VBLKU24A

Date Analyzed: 09/24/99

Time Analyzed: 9:12

GC Column: RTX-624 ID: 0.18 (mm)

Heated Purge: (Y/N) N

Instrument ID: 5973-U

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES, LCS'S, MS AND MSD'S :

Client Sample ID	Lab Sample ID	Lab Data File	Date Injected	Time Injected
LCSU24A	LCSU24A	U1069	9/24/99	8:28:00 AM
25GLM0501	WP4035-5DL	U1080	9/24/99	3:29:00 PM
25GLM0501D	WP4035-6DL	U1081	9/24/99	4:08:00 PM



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKU24A  
**SDG:** WP4035  
**Report Date:** 10/6/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 9/24/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKU24A	AQ	-	-	9/24/99	KMC	5030	KMC

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	102	%	1.0		
1,2-DICHLOROETHANE-D4	104	%	1.0		
TOLUENE-D8	101	%	1.0		
P-BROMOFLUOROBENZENE	98	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

Lab File: U1069

Sample ID: LCSU24A

Date Run: 9/24/99

Analyst: KMC

Time Injected: 8:28:00 AM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	54.9	110	60-140
BENZENE	50	52.0	104	60-140
ETHYLBENZENE	50	54.0	108	60-140
MTBE	50	49.7	99	60-140
NAPHTHALENE	50	55.4	111	60-140
TOLUENE	50	53.6	107	60-140
TOTAL XYLENES	150	159	106	60-140

\* Out of Limits

1

0000100





ENSR  
Air Toxics Specialty Laboratory  
42 Nagog Park  
Acton, MA 01720

DATE: October 12, 1999

TO: Andrea Colby  
Katahdin Analytical  
340 County Road No. 5  
P.O. Box 720  
Westbrook, ME 04098

Re: Organic Analyses of Aqueous Samples for Methane by Gas  
Chromatography/Flame Ionization Detection (GC/FID)- **WP4035**

PROJECT #: **8601-008-200**

LAB ID #: **990178**

**ANALYTICAL PROCEDURE:**

Five (5) aqueous samples were analyzed for methane under the guidelines of SW-846 Method 3810.

A Hewlett Packard 5890 series II gas chromatograph (GC) equipped with a Hewlett Packard flame ionization detector (FID) was used for the analysis. A 1.0 mL headspace aliquot of each sample was injected into the column for analysis. The operating conditions of the GC/FID are listed in Table 1. A five point calibration was performed for the target analyte, methane.

It should be noted that all samples were received at 10°C.



#### QUALITY CONTROL:

1. A laboratory blank was analyzed daily in the same manner as the samples. Methane was not detected in the blank.
2. MS/MSD analyses were performed on a sample from another Katahdin job (WP3906). The recoveries and relative percent differences of methane were within QC limits.
3. A laboratory control spike was analyzed daily. The recovery of methane was within the QC acceptance limits.

Date Samples Received by the Laboratory: 9/23/99

Date Analysis Started: 9/24/99

C:\My Documents\Kat 990175 990178 990180\katrpt4.doc



# SAMPLE LOG-IN & RECEIPT CHECKLIST

Client/Proj #: Katahdin WP4035

Proj Mgr: M. Hoyt

Lab Pool #: 990178

Inspected & Logged in by: A. MacDuff

Date Time: 9/23/99 @ 1025

Sample Matrix	Number of Samples	Analysis Requested	Analyze by (date)	Storage Location
<u>Aqueous</u>	<u>5</u>	<u>CH<sub>4</sub></u>	<u>10/7/99</u>	<u>R1</u>

Circle the appropriate response:

- 1) Shipped ~~Hand delivered~~
- 2) COC present / not present on receipt
- 3) COC Tape present / not present on shipping container
- 4) Samples broken / intact on receipt
- 5) Samples ambient / chilled on receipt Temp blank @ 10°C
- 6) Samples preserved correctly / incorrectly / none recommended
- 7) Received within / outside holding time
- 8) COC tapes present / not present on samples
- 9) Discrepancies / NO discrepancies noted between COCs and samples

Additional Comments: 3 vials per sample, no individual vial numbers

1  
ORGANICS ANALYSIS DATA SHEET

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_ EPA SAMPLE NO. **WP4035-4**  
Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_  
Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_ Lab Sample ID: 990178-4  
Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml) Lab File ID: \_\_\_\_\_ KAT\_030 \_\_\_\_\_  
Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_ Date Received: \_\_\_\_\_ 9/23/99 \_\_\_\_\_  
% Moisture: \_\_\_\_\_ NA \_\_\_\_\_ Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_  
GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_ Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_  
Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl) Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(µg/L or PPMv) _____ µg/L _____	Q
74-82-8	Methane	4400	E

1  
ORGANICS ANALYSIS DATA SHEET

25GLM0101

Lab Name:        ENSR        Contract:        EPA SAMPLE NO. **WP4035-4 D**

Lab Code:        Case No.:        SAS NO.:        SDG NO.:       

Matrix: (soil/water)        water        Lab Sample ID: 990178-4 DIL

Sample wt / vol:        32.5 ml        (g/ml) Lab File ID:        KAT\_031       

Level: (low/med)        low        Date Received:        9/23/99       

% Moisture:        NA        Date Analyzed:        9/24/99       

GC Column:        Carboxen 1004        OD:        1/16"        Dilution Factor:        10       

Soil Extract Volume:        NA        (μl) Soil Aliquot Volume:        NA        (μl)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (μg/L or PPMv) <u>      </u> μg/L <u>      </u>	Q
74-82-8	Methane	6000	D

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.  
**WP4035-5**

Lab Name:        ENSR        Contract:       

Lab Code:        Case No.:        SAS NO.:        SDG NO.:       

Matrix: (soil/water)        water        Lab Sample ID: 990178-5

Sample wt / vol:        32.5 ml        (g/ml) Lab File ID:        KAT\_032       

Level: (low/med)        low        Date Received:        9/23/99       

% Moisture:        NA        Date Analyzed:        9/24/99       

GC Column:        Carboxen 1004        OD:        1/16"        Dilution Factor:        1       

Soil Extract Volume:        NA        (μl) Soil Aliquot Volume:        NA        (μl)

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(μg/L or PPMv) <u>      </u> μg/L <u>      </u>	Q
74-82-8	Methane	3500	E

1  
ORGANICS ANALYSIS DATA SHEET

259200001

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_ EPA SAMPLE NO. **WP4035-5 D**

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_ Lab Sample ID: 990178-5 DIL

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml) Lab File ID: \_\_\_\_\_ KAT\_033 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_ Date Received: \_\_\_\_\_ 9/23/99 \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_ Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_ Dilution Factor: \_\_\_\_\_ 5 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl) Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(µg/L or PPMv) _____ µg/L _____	Q
74-82-8	Methane	4400	D



1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

VBLK01

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: MB990178

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_\_\_\_ KAT\_006 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_\_\_\_ NA \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(μg/L or PPMv) \_\_\_\_\_ μg/L \_\_\_\_\_

Q

74-82-8	Methane	5.2	U
---------	---------	-----	---

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. \_\_\_\_\_

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

LCS01

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: LCS990178

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_\_\_\_\_ KAT\_007 \_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_\_\_\_\_ NA \_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_\_\_\_\_ 9/24/99 \_\_\_\_\_

GC Column: \_\_\_\_\_ Carboxen 1004 \_\_\_\_\_ OD: \_\_\_\_\_ 1/16" \_\_\_\_\_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (µl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(µg/L or PPMv) \_\_\_\_\_ µg/L \_\_\_\_\_

Q

74-82-8

Methane

210

1  
ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. \_\_\_\_\_

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_ Contract: \_\_\_\_\_

WP3906-28(B) MS

Lab Code: \_\_\_\_\_ Case No.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix: (soil/water) \_\_\_\_\_ water \_\_\_\_\_

Lab Sample ID: 990175-1 MS

Sample wt / vol: \_\_\_\_\_ 32.5 ml \_\_\_\_\_ (g/ml)

Lab File ID: \_KAT\_023\_\_\_\_\_

Level: (low/med) \_\_\_\_\_ low \_\_\_\_\_

Date Received: \_9/16/99\_\_\_\_\_

% Moisture: \_\_\_\_\_ NA \_\_\_\_\_

Date Analyzed: \_9/24/99\_\_\_\_\_

GC Column: \_ Carboxen 1004 \_ OD: \_ 1/16" \_

Dilution Factor: \_\_\_\_\_ 1 \_\_\_\_\_

Soil Extract Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

Soil Aliquot Volume: \_\_\_\_\_ NA \_\_\_\_\_ (μl)

CAS NO.

COMPOUND

CONCENTRATION UNITS:  
(μg/L or PPMv) \_\_\_\_\_ μg/L \_\_\_\_\_

Q

74-82-8	Methane	340	
---------	---------	-----	--

1  
ORGANICS ANALYSIS DATA SHEET

Lab Name:       ENSR       Contract:                      EPA SAMPLE NO.       WP3906-28(C) MSD      

Lab Code:                      Case No.:                      SAS NO.:                      SDG NO.:                     

Matrix: (soil/water)       water       Lab Sample ID: 990175-1 MSD

Sample wt / vol:       32.5 ml       (g/ml) Lab File ID:       KAT\_024      

Level: (low/med)       low       Date Received:       9/16/99      

% Moisture:       NA       Date Analyzed:       9/24/99      

GC Column:       Carboxen 1004       OD:       1/16"       Dilution Factor:       1      

Soil Extract Volume:       NA       (μl) Soil Aliquot Volume:       NA       (μl)

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(μg/L or PPMv) <u>      μg/L      </u>	Q
74-82-8	Methane	350	

3  
LABORATORY CONTROL SPIKE RECOVERY

Lab Name: \_\_\_\_\_ ENSR \_\_\_\_\_

Contract: \_\_\_\_\_

Lab Code: \_\_\_\_\_ Case NO.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Laboratory Control Sample No: \_\_\_\_\_ LCS01 \_\_\_\_\_

COMPOUND	SPIKE ADDED (µg/L)	LCS CONCENTRATION (µg/L)	LCS % REC    #	QC LIMITS REC.
Methane	205.0	206.7	101%	50 - 150

\* - Values outside of QC limits.

## MATRIX SPIKE / MATRIX SPIKE DUPLICATE RECOVERY

Lab Name: ENSUR

Contract: \_\_\_\_\_

Lab Code: \_\_\_\_\_ Case NO.: \_\_\_\_\_ SAS NO.: \_\_\_\_\_ SDG NO.: \_\_\_\_\_

Matrix Spike - EPA Sample NO.: WP3906-28

COMPOUND	SPIKE ADDED (µg/L)	SAMPLE CONCENTRATION (µg/L)	MS CONCENTRATION (µg/L)	MS % REC	#	QC LIMITS REC.
Methane	205.0	189	344.8	76%		50-150

COMPOUND	SPIKE ADDED (µg/L)	MSD CONCENTRATION (µg/L)	MSD % REC	#	% RPD #	RPD	QC LIMITS REC.
Methane	205.0	345.8	77%		0.68%	50	50-150

Spike recovery: 0 out of 2 outside limits.RPD: 0 out of 1 outside limits.

Comments:

---



---

4  
METHOD BLANK SUMMARY

Lab Name:        ENSR        Contract:        EPA SAMPLE NO.  
**VBLK01**

Lab Code:        Case No.:        SAS NO.:        SDG NO.:       

Lab File ID:   KAT\_006   Lab Sample I MB990175

Instrument ID:        HPGC#3        Date Analyzed:   9/24/99  

Matrix: (soil/water)        water        Level: (low/med)        low       

THIS METHOD BLANK APPLIES TO THE FOLLOWING SAMPLES; MS AND MSD

	EPA SAMPLE NO.	LAB SAMPLE ID	LAB FILE ID	DATE ANALYZED
01	LCS01	LCS990175	KAT_007	09/24/99
02	WP3906-28(B) MS	990175-1 MS	KAT_023	09/24/99
03	WP3906-28(C) MSD	990175-1 MSD	KAT_024	09/24/99
04	WP4035-1	990178-1	KAT_025	09/24/99
05	WP4035-1 D	990178-1 DIL	KAT_026	09/24/99
06	WP4035-2	990178-2	KAT_028	09/24/99
07	WP4035-3	990178-3	KAT_029	09/24/99
08	WP4035-4	990178-4	KAT_030	09/24/99
09	WP4035-4 D	990178-4 DIL	KAT_031	09/24/99
10	WP4035-5	990178-5	KAT_032	09/24/99
11	WP4035-5 D	990178-5 DIL	KAT_033	09/24/99
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				

COMMENTS:

SDG NARRATIVE  
KATAHDIN ANALYTICAL SERVICES  
TETRA TECH NUS  
CASE CNC CHARLESTON

Sample Receipt

The following samples were received on June 8, 1999 and were logged in under Katahdin Analytical Services work order number WP2792 for a hardcopy due date of July 8, 1999.

KATAHDIN <u>Sample No.</u>	TTNUS <u>Sample Identification</u>	GEL <u>Sample No.</u>
WP2792-1	25SLB090304	
WP2792-2	25SLB100102	
WP2792-3	25SLB110203	
WP2792-4	25SLB130203	9906242-01
WP2792-5	25SLB130203D	9906242-02
WP2792-6	25SLB140304	
WP2792-7	25SLB160304	
WP2792-8	25SLB170304	
WP2792-9	25SLB120203	
WP2792-10	25SLB120708	
WP2792-11	25TL00501	
WP2792-12	25SLB150304	9906242-03
WP2792-13	25SLB150304D	9906242-04

→ GRAIN SIZE

The samples were logged in for the analyses specified on the chain of custody form. All problems encountered and resolved during sample receipt have been documented on the applicable chain of custody forms.

Sample analyses have been performed by the methods as noted herein.

Volatile Organic Analysis

Twelve soil samples were received by the Katahdin Analytical Services, Inc. GC/MS laboratory on June 8, 1999 and were specified to be analyzed by USEPA method 8260B for the analytes benzene, toluene, ethylbenzene, xylenes, MTBE, naphthalene, and EDB.

Analyses for this workorder were performed on the 5972-F, 5972-M, and 5972-Z instruments. A VSTD050 (50 ppb standard) was used for the continuing calibration standard. Internal standard and surrogate compounds were also spiked at 50 ug/l.

Batch QC (VBLK, and LCS) was performed in each twelve-hour window. Results are included



in this data package. The LCS QC samples were spiked with the entire list of compounds quantitated for at 50 ppb. No matrix spike/matrix spike duplicate was performed on any sample in this workorder.

Method 8000B, section 7.5.1.2.1 (Revision 2, 12/96) states, "in those instances where the RSD for one or more analytes exceeds 20%, the initial calibration curve may still be acceptable if the mean of the RSD values for all analytes in the calibration is less than or equal to 20%." Method 8260B narrows this 20% maximum to 15%.

The calibration curves in this workorder had several analytes exceeding the maximum allowable 15% RSD. Since the average %RSDs were 8.3%, 12.3%, 10.9%, and 13.3%, the curves were acceptable.

Initial analyses of samples WP2792-2, -4, -5, -8, and -9 following medium level protocols yielded target analyte concentrations over the upper limit of the calibration curve. Analyses of samples WP2792-5 and -9 also yielded surrogate recovery deviations. Reanalyses occurred at 1:2, 1:10, 1:50, 1:20, and 1:100 dilutions, respectively, successfully. Both sets of data are included in this data package for each sample.

Initial analysis of sample WP2792-6 following low level protocols yielded internal standard area and surrogate recovery deviations. Reanalysis yielded internal standard area recovery deviations, confirming matrix interference. Both sets of data are included in this data package.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" (software-generated) on the pertinent quantitation reports. All "M" flags have been dated and initialed by the analyst performing the integration. In addition, all "M" flags have been reviewed and approved by the GC/MS supervisor. Copies of each manual integration are included in the pertinent quantitation reports.

No other protocol deviations were noted by the volatile organics staff.

#### Semivolatile Organic Analysis

Nine soil/sediment samples were received by Katahdin Analytical Services laboratory on June 8, 1999 for analysis in accordance with 8270C for the PAH list of analytes.

Extraction of the samples occurred following USEPA method 3550 on June 16, 1999. A laboratory control spike consisting of all PAH analytes spiked into organic free sand, was extracted in the batch.

The initial calibration curve analyzed in this SDG had some of the target analyte %RSD values exceeding 15 %.

Method 8000B, section 7.5.1.2.1 (Revision 2, 12/96) states, "in those instances where the RSD for one or more analytes exceeds 20%, the initial calibration curve may still be acceptable if the

mean of the RSD values for all analytes in the calibration is less than or equal to 20%." Section 7.3.7.1 of method 8270C (revision 3, 12/96) narrows this 20% maximum to 15%.

In the calibration curve analyzed in this SDG, the average %RSD for all analytes was 9.1%, making the curve acceptable.

Initial analyses of samples WP2792-4, -5, and -9 yielded target analyte concentrations over the upper limit of the calibration curve. Analysis of sample WP2792-9 also yielded an internal standard area recovery deviation. Reanalyses occurred at 1:5, 1:100, and 1:5 dilutions, respectively. Both sets of data for each sample are included in this data package.

Several manual integrations were performed due to split peaks; all have been flagged with a "M" by the data system. All manual integrations have been dated and initialed by the responsible analyst. Copies of each manual integration are included in the data package. All manual integrations have been reviewed and approved by the GC/MS supervisor.

No other protocol deviations were noted by the semivolatiles organics staff.

#### Metals Analysis

The samples of Katahdin Work Order WP2792 were prepared and analyzed for metals in accordance with the "Test Methods for Evaluating Solid Waste", SW-846, November 1986, Third Edition.

#### Inductively-Coupled Plasma (ICP) Atomic Emission Spectroscopic Analysis

Soil-matrix Katahdin Sample Nos. WP2792-(1-5) were originally digested for lead analysis on 07/07/99 (QC Batch PG07ICS0) in accordance with USEPA Method 3050B. Katahdin Sample No. WP2989-1 was prepared with duplicate matrix-spiked aliquots.

ICP analyses of Katahdin Work Order WP2792 sample digestates were performed in accordance with USEPA Method 6010B, using a Thermo Jarrell Ash Trace ICP. All samples were analyzed within holding times and all QC criteria were met with the following comments or exceptions:

Some of the results for run QC samples (ICV, ICB, CCV, CCB, ICSA, and ICSAB) included in the accompanying data package may have exceeded acceptance limits for some elements. Please note that all client samples and batch QC samples associated with out-of-control results for run QC samples were subsequently reanalyzed for the analytes in question.

#### Wet Chemistry Analysis

For work order WP2792 the analyses for Total Combustible Organics (TCO) have been performed in accordance with the "Annual Book of ASTM Standards", 1987. Analyses for Solids-Total Residue (TS) for work order WP2792 samples have been performed in accordance


with "Contract Laboratory Program Statement of Work for Inorganic Analysis".

All analyses were performed within analytical hold time. No protocol deviations were noted by the Wet Chemistry laboratory staff.

**Subcontracted Analysis**

Analyses for Total Organic Carbon, Total Petroleum Hydrocarbon and Grain size were subcontracted to outside laboratories. All sets of data are included as separate sections to the data package.

I certify that this data package is in compliance with the terms and conditions of the contract, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package has been authorized by the Laboratory Manager and/or his designee, as verified by the following signature.

  
Authorized Signature  
8.12.99

**KATAHDIN ANALYTICAL SERVICES, INC.**  
**SAMPLE RECEIPT CONDITION REPORT**

Tel. (207) 874-2400  
 Fax (207) 775-4029

LAB (WORK ORDER) # WP 2792

PAGE: 1 OF 1

COOLER: 1 OF 1

COC# —

SDG# —

DATE / TIME RECEIVED: 6-8-99 1015

DELIVERED BY: FedEx

RECEIVED BY: Sam

LIMS ENTRY BY: BKA

LIMS REVIEW BY / PM: APC

CLIENT: Tetra Tech - SC

PROJECT: CNC Charleston

	YES	NO	EXCEPTIONS
1. CUSTODY SEALS PRESENT / INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2. CHAIN OF CUSTODY PRESENT IN THIS COOLER?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3. CHAIN OF CUSTODY SIGNED BY CLIENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. CHAIN OF CUSTODY MATCHES SAMPLES?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5. TEMPERATURE BLANKS PRESENT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6. SAMPLES RECEIVED AT 4°C N-27	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
ICE / ICE PACKS PRESENT (Y or N)?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7. VOLATILES FREE OF HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
8. TRIP BLANK PRESENT IN THIS COOLER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. PROPER SAMPLE CONTAINERS AND VOLUME?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
10. SAMPLES WITHIN HOLD TIME UPON RECEIPT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11. SAMPLES PROPERLY PRESERVED <sup>(1)</sup> ?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> <u>APC 6/8/99</u>
12. CORRECTIVE ACTION REPORT FILED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A

COMMENTS

RESOLUTION

(1)

TEMP BLANK TEMP (°C) = 1.0  
 temp blank under bag of ice.  
 COOLER TEMP (°C) = NA  
 (RECORD COOLER TEMP ONLY IF TEMP BLANK IS NOT PRESENT)

Client send to add 25SLB120708 to COC for grain size

APC contacted Bryan Henze by phone & Paul Calligan by fax 6/8/99

13. ANALYTICAL PROGRAMS (CIRCLE ONE) COMMERCIAL CLP HAZWRAP NFESC ACOE AFCEE OTHER (STATE OF ORIGIN):

LOG-IN NOTES<sup>(1)</sup>: Sample ID 25SLB120203 only has 7 containers, there is an extra container ID 25SLB120708 for grain size that is not on the chain (no time on container but date matches); Sample ID 25SLB150304 has 6 containers but none labeled for FCC 6/8/99

<sup>(1)</sup> Use this space (and additional sheets if necessary) to document samples that are received broken or compromised, C-O-C discrepancies, radiation checks, residual chlorine check, results of pH check if required. If samples required pH adjustment, record volume and type of preservative added.



340 County Road No. 5  
P.O. Box 720  
Westbrook, ME 04098  
Tel: (207) 874-2400  
Fax: (207) 775-4029

# CHAIN of CUSTODY

PLEASE PRINT IN PEN

Page 1 of 1

Client	<u>Tetra Tech US</u>	Contact	<u>Bryn Howze</u>	Phone #	<u>(843) 814-9080</u>	Fax #	<u>( )</u>
Address	<u>NH21 Ave H</u>	City	<u>N. Charleston</u>	State	<u>SC</u>	Zip Code	<u>2940</u>
Purchase Order #		Proj. Name / No.		Katahdin Quote #			

Bill (if different than above)	Address		
Sampler (Print / Sign)	<u>Roger Franklin / [Signature]</u>	Copies To:	

LAB USE ONLY	WORK ORDER #: <u>WP 2792</u>	ANALYSIS AND CONTAINER TYPE PRESERVATIVES											
KATAHDIN PROJECT MANAGER		Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.
REMARKS:		YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON	YOYON
SHIPPING INFO: <input checked="" type="checkbox"/> FED EX <input type="checkbox"/> UPS <input type="checkbox"/> CLIENT													
AIRBILL NO: <u>809609650221</u>													
TEMP °C <input type="checkbox"/> TEMP BLANK <input type="checkbox"/> INTACT <input type="checkbox"/> NOT INTACT													

* Sample Description	Date / Time coll'd	Matrix	No. of Cntrs.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.	Filt.
				PAHs	13TEX	59an	Lead	402	Grain Size	3202	FOC		FID Readings
25SLB090304	6/7/99/0858	Soil	6	X	X	X							106
25SLB100102	6/7/99/0915	Soil	6	X	X	X							>5000
25SLB110203	6/7/99/0935	Soil	6	X	X	X							1610
25SLB120203	6/7/99/1015	Soil	8	X	X	X	X						>5000
25SLB130203	6/7/99/1040	Soil	6	X	X	X							250
25SLB130203D	6/7/99/1040	Soil	6	X	X	X							820
25SLB140304	6/7/99/1035	Soil	6	X	X	X							820
25SLB150304	6/7/99/1115	Soil	6	X	X	X		X					150
25SLB160304	6/7/99/1330	Soil	6	X	X	X							250
25SLB170304	6/7/99/1355	Soil	6	X	X	X							>5000
25TL00501	6/7/99/-	Water	2		2								
25SLB120708	6/7/99/							X					
	/												
	/												
	/												
	/												

COMMENTS

Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)
<u>[Signature]</u>	<u>6/7/99 1800</u>	<u>Fed Ex</u>		<u>6-8-99 1015</u>	<u>Shelley Williams</u>
Relinquished By: (Signature)	Date / Time	Received By: (Signature)	Relinquished By: (Signature)	Date / Time	Received By: (Signature)
					<u>0000007</u>

ORDER NO WP-2792

Project Manager: Andrea J. Colby  
ORDER DATE: 06/08/99  
PHONE: 850/385-9899  
FAX: 850/385-9860  
DUE: 08 JUL  
FAC.ID: CNC CHARLESTONREPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
661 ANDERSEN DRIVE, FOSTER PLAZA VII  
PITTSBURGH, PA 15220-2745  
PHONE: 412/921-7090  
PO: N7912-P99264  
PROJECT: CTO #68

SAMPLED BY: ROGER FRANKLIN

DELIVERED BY: FEDEX

DISPOSE: AFTER 07 AUG

ITEM	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
1	WP2792-1	25SLB090304	07 JUN 0858	08 JUN	SL
	WP2792-2	25SLB100102	07 JUN 0915		
	WP2792-3	25SLB110203	07 JUN 0935		
	WP2792-6	25SLB140304	07 JUN 1055		
	WP2792-7	25SLB160304	07 JUN 1330		
	WP2792-8	25SLB170304	07 JUN 1355		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Polynuclear Aromatic Hydrocarbons	EPA 8270	6	135.00	810.00
Volatile Organics by 8260B	SW8260	6	85.00	510.00
Solids-Total Residue (TS)	CLP/CIP SO	6	0.00	0.00
Lead, Total	6010	6	20.00	120.00
TOTALS		6	240.00	1440.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
2	WP2792-9	25SLB120203	07 JUN 1015	08 JUN	SL

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Polynuclear Aromatic Hydrocarbons	EPA 8270	1	135.00	135.00
Volatile Organics by 8260B	SW8260	1	85.00	85.00
Solids-Total Residue (TS)	CLP/CIP SO	1	0.00	0.00
Lead, Total	6010	1	20.00	20.00
Wet Lab Subcontract		1	110.00	110.00
TOTALS		1	350.00	350.00

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
3	WP2792-10	25SLB120708	07 JUN	08 JUN	SL

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Wet Lab Subcontract		1	110.00	110.00

LABORATORY ORDER CONTINUED ON PAGE 2

0000008

no initiation

ORDER NO WP-2792

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 06/08/99  
PHONE: 850/385-9899  
FAX: 850/385- 0  
DUE: 08 JUL  
FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
661 ANDERSEN DRIVE, FOSTER PLAZA VII  
PITTSBURGH, PA 15220-2745

PHONE: 412/921-7090  
PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: ROGER FRANKLIN

DELIVERED BY: FEDEX

DISPOSE: AFTER 07 AUG

LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
4 WP2792-11	25TL00501	07 JUN	08 JUN	SL

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Volatile Organics by 8260B	SW8260	1	85.00	85.00

LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
5 WP2792-12	25SLB150304	07 JUN 1115	08 JUN	SL

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Polynuclear Aromatic Hydrocarbons	EPA 8270	1	135.00	135.00
Solids-Total Residue (TS)	CLP/CIP SO	1	0.00	0.00
Volatile Organics by 8260B	SW8260	1	85.00	85.00
Lead, Total	6010	1	20.00	20.00
Total Combustible Organics	ASTM D2974	1	30.00	30.00
Wet Lab Subcontract		1	60.00	60.00

TOTALS		1	330.00	330.00
--------	--	---	--------	--------

LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
6 WP2792-4	25SLB130203	07 JUN 1040	08 JUN	SL
WP2792-5	25SLB130203D	07 JUN 1040		

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Polynuclear Aromatic Hydrocarbons	EPA 8270	2	135.00	270.00
Volatile Organics by 8260B	SW8260	2	85.00	170.00
Solids-Total Residue (TS)	CLP/CIP SO	2	0.00	0.00
Lead, Total	6010	2	20.00	40.00
Wet Lab Subcontract		2	75.00	150.00

TOTALS		2	315.00	630.00
--------	--	---	--------	--------

0000009

4/11 4/14/90

ORDER NO WP-2792

Project Manager: Andrea J. Colby

REPORT TO: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

ORDER DATE: 06/08/99

PHONE: 850/385-9899

FAX: 850/385-9860

DUE: 08 JUL

FAC.ID: CNC CHARLESTON

INVOICE: ACCOUNTS PAYABLE  
TETRA TECH NUS, INC.  
661 ANDERSEN DRIVE, FOSTER PLAZA VII  
PITTSBURGH, PA 15220-2745

PHONE: 412/921-7090

PO: N7912-P99264

PROJECT: CTO #68

SAMPLED BY: ROGER FRANKLIN

DELIVERED BY: FEDEX

DISPOSE: AFTER 07 AUG

	LOG NUMBER	SAMPLE DESCRIPTION	SAMPLED DATE/TIME	RECEIVED	MATRIX
7	WP2792-13	25SLB150304D	07 JUN 1115	07 JUN	SL

DETERMINATION	METHOD	QTY	PRICE	AMOUNT
Wet Lab Subcontract		1	60.00	60.00

ORDER NOTE: QC-IV NFESC-D  
DD(KAS007QC-DB3)  
CNC CHARLESTON

REPORT COPY: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.  
PITTSBURGH, PA 15220

INVOICE: With Report

TOTAL ORDER AMOUNT \$3,005.00

This is NOT an Invoice

C/BKR/WEST.AJC(dw)

06-14Please contact KATAHDIN ANALYTICAL SERVICES promptly if you have any questi

0000010

ME LABORATORY





# KATAHDIN ANALYTICAL SERVICES

## Summary of Report Notes

Report Note	Note Text
DL	'DL' flag denotes inability to calculate surrogate recovery due to sample dilution.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.

# KATAHDIN ANALYTICAL SERVICES

## Summary of Report Notes

Report Note	Note Text
#	'#' flag denotes surrogate compound recovery is out of criteria.
E	'E' flag indicates an estimated value. The analyte was detected in the sample at a concentration greater than the standard calibration range.
J	'J' flag denotes an estimated value less than the Laboratory's Practical Quantitation Level.
O-1	Sample dilution required due to matrix interference, sample viscosity or other matrix-related problem; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.
O-13	Internal standard area(s) are out of criteria. Reanalysis confirmed matrix interference.
O-2	Sample dilution required for quantitation of one or more target analytes; therefore, standard laboratory Practical Quantitation Level (PQL) could not be achieved.



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-1  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 81  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB090304	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<400	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	<400	ug/Kg	1.2	400	330
ACENAPHTHYLENE	<400	ug/Kg	1.2	400	330
ACENAPHTHENE	<400	ug/Kg	1.2	400	330
FLUORENE	<400	ug/Kg	1.2	400	330
PHENANTHRENE	<400	ug/Kg	1.2	400	330
ANTHRACENE	<400	ug/Kg	1.2	400	330
FLUORANTHENE	<400	ug/Kg	1.2	400	330
PYRENE	<400	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	<400	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	42	%	1.2		
2-FLUOROBIPHENYL	48	%	1.2		
TERPHENYL-D14	86	%	1.2		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-1  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 81  
**Method:** SW8260  
**Date Analyzed:** 6/16/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB090304	SL	6/7/99	6/8/99	6/16/99	KRT	5030	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	52	ug/Kg	1.2	6	5
TOLUENE	15	ug/Kg	1.2	6	5
1,2-DIBROMOETHANE	<6	ug/Kg	1.2	6	5
ETHYLBENZENE	<6	ug/Kg	1.2	6	5
NAPHTHALENE	J4	ug/Kg	1.2	6	5
MTBE	<6	ug/Kg	1.2	6	5
TOTAL XYLENES	<6	ug/Kg	1.2	6	5
DIBROMOFLUOROMETHANE	88	%	1.2		
1,2-DICHLOROETHANE-D4	92	%	1.2		
TOLUENE-D8	86	%	1.2		
P-BROMOFLUOROBENZENE	72	%	1.2		

**Report Notes:** J

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB090304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 80.8

Lab Sample ID: WP2792-001

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	10.5			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-1  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 1 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB090304	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	81.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-2  
SDG: WP2792  
Report Date: 8/5/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: 68  
Method: EPA 8270  
Date Analyzed: 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB100102	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	2200	ug/Kg	1.5	460	330
2-METHYLNAPHTHALENE	1600	ug/Kg	1.5	460	330
ACENAPHTHYLENE	<460	ug/Kg	1.5	460	330
ACENAPHTHENE	<460	ug/Kg	1.5	460	330
FLUORENE	<460	ug/Kg	1.5	460	330
PHENANTHRENE	<460	ug/Kg	1.5	460	330
ANTHRACENE	<460	ug/Kg	1.5	460	330
FLUORANTHENE	<460	ug/Kg	1.5	460	330
PYRENE	<460	ug/Kg	1.5	460	330
BENZO[A]ANTHRACENE	<460	ug/Kg	1.5	460	330
CHRYSENE	<460	ug/Kg	1.5	460	330
BENZO[B]FLUORANTHENE	<460	ug/Kg	1.5	460	330
BENZO[K]FLUORANTHENE	<460	ug/Kg	1.5	460	330
BENZO[A]PYRENE	<460	ug/Kg	1.5	460	330
INDENO[1,2,3-CD]PYRENE	<460	ug/Kg	1.5	460	330
DIBENZ[A,H]ANTHRACENE	<460	ug/Kg	1.5	460	330
BENZO[G,H,I]PERYLENE	<460	ug/Kg	1.5	460	330
NITROBENZENE-D5	49	%	1.5		
2-FLUOROBIPHENYL	57	%	1.5		
TERPHENYL-D14	75	%	1.5		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-2  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 68  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB100102	SL	6/7/99	6/8/99	6/11/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	6100	ug/Kgdrywt	160	800	5
TOLUENE	<800	ug/Kgdrywt	160	800	5
1,2-DIBROMOETHANE	<800	ug/Kgdrywt	160	800	5
ETHYLBENZENE	E39000	ug/Kgdrywt	160	800	5
NAPHTHALENE	21000	ug/Kgdrywt	160	800	5
MTBE	<800	ug/Kgdrywt	160	800	5
TOTAL XYLENES	1800	ug/Kgdrywt	160	800	5
DIBROMOFLUOROMETHANE	92	%	160		
1,2-DICHLOROETHANE-D4	104	%	160		
TOLUENE-D8	108	%	160		
P-BROMOFLUOROBENZENE	120	%	160		

Report Notes: E



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-2DL  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 68  
**Method:** SW8260  
**Date Analyzed:** 6/14/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB100102	SL	6/7/99	6/8/99	6/14/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	9100	ug/Kgdrywt	320	1600	5
TOLUENE	<1600	ug/Kgdrywt	320	1600	5
1,2-DIBROMOETHANE	<1600	ug/Kgdrywt	320	1600	5
ETHYLBENZENE	63000	ug/Kgdrywt	320	1600	5
NAPHTHALENE	30000	ug/Kgdrywt	320	1600	5
MTBE	<1600	ug/Kgdrywt	320	1600	5
TOTAL XYLENES	3000	ug/Kgdrywt	320	1600	5
DIBROMOFLUOROMETHANE	95	%	320		
1,2-DICHLOROETHANE-D4	96	%	320		
TOLUENE-D8	106	%	320		
P-BROMOFLUOROBENZENE	109	%	320		

Report Notes: O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB100102

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 68.5

Lab Sample ID: WP2792-002

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	34.7			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

FORM I - IN

0000033

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-2  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WICH: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 2 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25SLB100102	Solid			ROGER FRANKLIN		06/07/99	06/08/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Solids-Total Residue (TS)	69.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99	JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc (dw) /msm  
PF11TSS7

CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7

661 ANDERSEN DR.  
340 County Road No. 5  
P.O. Box 720, Westbrook, ME 04098  
Tel: (207) 874-2400 Fax: (207) 775-4029

<http://katahdinlab.com>

210 West Road No. 5, Portsmouth, NH 03801  
Tel: (603) 431-5777 Fax: (603) 436-3356

0000043

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-3  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 87  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB110203	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	J250	ug/Kg	1.1	360	330
2-METHYLNAPHTHALENE	<360	ug/Kg	1.1	360	330
ACENAPHTHYLENE	<360	ug/Kg	1.1	360	330
ACENAPHTHENE	<360	ug/Kg	1.1	360	330
FLUORENE	<360	ug/Kg	1.1	360	330
PHENANTHRENE	<360	ug/Kg	1.1	360	330
ANTHRACENE	<360	ug/Kg	1.1	360	330
FLUORANTHENE	<360	ug/Kg	1.1	360	330
PYRENE	<360	ug/Kg	1.1	360	330
BENZO[A]ANTHRACENE	<360	ug/Kg	1.1	360	330
CHRYSENE	<360	ug/Kg	1.1	360	330
BENZO[B]FLUORANTHENE	<360	ug/Kg	1.1	360	330
BENZO[K]FLUORANTHENE	<360	ug/Kg	1.1	360	330
BENZO[A]PYRENE	<360	ug/Kg	1.1	360	330
INDENO[1,2,3-CD]PYRENE	<360	ug/Kg	1.1	360	330
DIBENZ[A,H]ANTHRACENE	<360	ug/Kg	1.1	360	330
BENZO[G,H,I]PERYLENE	<360	ug/Kg	1.1	360	330
NITROBENZENE-D5	53	%	1.1		
2-FLUOROBIPHENYL	60	%	1.1		
TERPHENYL-D14	81	%	1.1		

**Report Notes:** J

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-3  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 87  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB110203	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	J6	ug/Kg	1.1	6	5
TOLUENE	<6	ug/Kg	1.1	6	5
1,2-DIBROMOETHANE	<6	ug/Kg	1.1	6	5
ETHYLBENZENE	14	ug/Kg	1.1	6	5
NAPHTHALENE	66	ug/Kg	1.1	6	5
MTBE	<6	ug/Kg	1.1	6	5
TOTAL XYLENES	19	ug/Kg	1.1	6	5
DIBROMOFLUOROMETHANE	82	%	1.1		
1,2-DICHLOROETHANE-D4	92	%	1.1		
TOLUENE-D8	94	%	1.1		
P-BROMOFLUOROBENZENE	88	%	1.1		

**Report Notes:** J

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB110203

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 87.4

Lab Sample ID: WP2792-003

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	125			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

FORM I - IN

0000034

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-3  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 3 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25SLB110203	Solid			ROGER FRANKLIN		06/07/99	06/08/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Solids-Total Residue (TS)	87.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99	JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-4  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 85  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	E14000	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	E9600	ug/Kg	1.2	400	330
ACENAPHTHYLENE	<400	ug/Kg	1.2	400	330
ACENAPHTHENE	<400	ug/Kg	1.2	400	330
FLUORENE	<400	ug/Kg	1.2	400	330
PHENANTHRENE	<400	ug/Kg	1.2	400	330
ANTHRACENE	<400	ug/Kg	1.2	400	330
FLUORANTHENE	<400	ug/Kg	1.2	400	330
PYRENE	J280	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	<400	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	47	%	1.2		
2-FLUOROBIPHENYL	71	%	1.2		
TERPHENYL-D14	75	%	1.2		

**Report Notes:** J, E





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-4DL  
SDG: WP2792  
Report Date: 8/5/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 85  
Method: EPA 8270  
Date Analyzed: 7/26/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	15000	ug/Kg	5.9	1900	330
2-METHYLNAPHTHALENE	10000	ug/Kg	5.9	1900	330
ACENAPHTHYLENE	<1900	ug/Kg	5.9	1900	330
ACENAPHTHENE	<1900	ug/Kg	5.9	1900	330
FLUORENE	<1900	ug/Kg	5.9	1900	330
PHENANTHRENE	<1900	ug/Kg	5.9	1900	330
ANTHRACENE	<1900	ug/Kg	5.9	1900	330
FLUORANTHENE	<1900	ug/Kg	5.9	1900	330
PYRENE	<1900	ug/Kg	5.9	1900	330
BENZO(A)ANTHRACENE	<1900	ug/Kg	5.9	1900	330
CHRYSENE	<1900	ug/Kg	5.9	1900	330
BENZO(B)FLUORANTHENE	<1900	ug/Kg	5.9	1900	330
BENZO(K)FLUORANTHENE	<1900	ug/Kg	5.9	1900	330
BENZO(A)PYRENE	<1900	ug/Kg	5.9	1900	330
INDENO(1,2,3-CD)PYRENE	<1900	ug/Kg	5.9	1900	330
DIBENZ(A,H)ANTHRACENE	<1900	ug/Kg	5.9	1900	330
BENZO(G,H,I)PERYLENE	<1900	ug/Kg	5.9	1900	330
NITROBENZENE-D5	37	%	5.9		
2-FLUOROBIPHENYL	63	%	5.9		
TERPHENYL-D14	60	%	5.9		

Report Notes: O-2

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-4  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 85  
**Method:** SW8260  
**Date Analyzed:** 6/9/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203	SL	6/7/99	6/8/99	6/9/99	HMP	5035	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	5000	ug/Kgdrywt	120	600	5
TOLUENE	8400	ug/Kgdrywt	120	600	5
1,2-DIBROMOETHANE	<600	ug/Kgdrywt	120	600	5
ETHYLBENZENE	E84000	ug/Kgdrywt	120	600	5
NAPHTHALENE	E43000	ug/Kgdrywt	120	600	5
MTBE	<600	ug/Kgdrywt	120	600	5
TOTAL XYLENES	140000	ug/Kgdrywt	120	600	5
DIBROMOFLUOROMETHANE	88	%	120		
1,2-DICHLOROETHANE-D4	106	%	120		
TOLUENE-D8	89	%	120		
P-BROMOFLUOROBENZENE	98	%	120		

**Report Notes:** E



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-4DL  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 85  
**Method:** SW8260  
**Date Analyzed:** 6/10/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203	SL	6/7/99	6/8/99	6/10/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	J5000	ug/Kgdrywt	1200	6000	5
TOLUENE	7600	ug/Kgdrywt	1200	6000	5
1,2-DIBROMOETHANE	<6000	ug/Kgdrywt	1200	6000	5
ETHYLBENZENE	73000	ug/Kgdrywt	1200	6000	5
NAPHTHALENE	70000	ug/Kgdrywt	1200	6000	5
MTBE	<6000	ug/Kgdrywt	1200	6000	5
TOTAL XYLENES	160000	ug/Kgdrywt	1200	6000	5
DIBROMOFLUOROMETHANE	92	%	1200		
1,2-DICHLOROETHANE-D4	87	%	1200		
TOLUENE-D8	103	%	1200		
P-BROMOFLUOROBENZENE	104	%	1200		

**Report Notes:** J, O-1, O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB130203

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 85.4

Lab Sample ID: WP2792-004

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	6.2			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

FORM I - IN

0000035



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-4  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 9 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB130203	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	85.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS

340 County Road No. 7  
P.O. Box 20, ANDERSON, ME 04098  
Tel: (207) 874-1400 Fax: (207) 775-4029

<http://katahdinlab.com>

210 West Road No. 5, Portsmouth, NH 03801  
Tel: (603) 431-5777 Fax: (603) 436-3356

0000045

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-5  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No.:** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 81  
  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203D	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	E86000	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	E62000	ug/Kg	1.2	400	330
ACENAPHTHYLENE	420	ug/Kg	1.2	400	330
ACENAPHTHENE	560	ug/Kg	1.2	400	330
FLUORENE	420	ug/Kg	1.2	400	330
PHENANTHRENE	1100	ug/Kg	1.2	400	330
ANTHRACENE	J330	ug/Kg	1.2	400	330
FLUORANTHENE	450	ug/Kg	1.2	400	330
PYRENE	750	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	J240	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	53	%	1.2		
2-FLUOROBIPHENYL	77	%	1.2		
TERPHENYL-D14	84	%	1.2		

**Report Notes:** J, E

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

Client: Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-5DL  
SDG: WP2792  
Report Date: 8/5/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 81  
Method: EPA 8270  
Date Analyzed: 7/26/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203D	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	88000	ug/Kg	120	40000	330
2-METHYLNAPHTHALENE	65000	ug/Kg	120	40000	330
ACENAPHTHYLENE	<40000	ug/Kg	120	40000	330
ACENAPHTHENE	<40000	ug/Kg	120	40000	330
FLUORENE	<40000	ug/Kg	120	40000	330
PHENANTHRENE	<40000	ug/Kg	120	40000	330
ANTHRACENE	<40000	ug/Kg	120	40000	330
FLUORANTHENE	<40000	ug/Kg	120	40000	330
PYRENE	<40000	ug/Kg	120	40000	330
BENZO[A]ANTHRACENE	<40000	ug/Kg	120	40000	330
CHRYSENE	<40000	ug/Kg	120	40000	330
BENZO[B]FLUORANTHENE	<40000	ug/Kg	120	40000	330
BENZO[K]FLUORANTHENE	<40000	ug/Kg	120	40000	330
BENZO[A]PYRENE	<40000	ug/Kg	120	40000	330
INDENO[1,2,3-CD]PYRENE	<40000	ug/Kg	120	40000	330
DIBENZ[A,H]ANTHRACENE	<40000	ug/Kg	120	40000	330
BENZO[G,H,I]PERYLENE	<40000	ug/Kg	120	40000	330
NITROBENZENE-D5	DL	%	120		
2-FLUOROBIPHENYL	DL	%	120		
TERPHENYL-D14	DL	%	120		

Report Notes: O-2, DL

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-5  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 81  
**Method:** SW8260  
**Date Analyzed:** 6/9/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203D	SL	6/7/99	6/8/99	6/9/99	HMP	5035	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	10000	ug/Kgdrywt	110	550	5
TOLUENE	18000	ug/Kgdrywt	110	550	5
1,2-DIBROMOETHANE	<550	ug/Kgdrywt	110	550	5
ETHYLBENZENE	E150000	ug/Kgdrywt	110	550	5
NAPHTHALENE	E74000	ug/Kgdrywt	110	550	5
MTBE	<550	ug/Kgdrywt	110	550	5
TOTAL XYLENES	220000	ug/Kgdrywt	110	550	5
DIBROMOFLUOROMETHANE	99	%	110		
1,2-DICHLOROETHANE-D4	#150	%	110		
TOLUENE-D8	88	%	110		
P-BROMOFLUOROBENZENE	106	%	110		

**Report Notes:** E, #



**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-SDL  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No.:** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 81  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB130203D	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<28000	ug/Kgdrywt	5600	28000	5
TOLUENE	115000	ug/Kgdrywt	5600	28000	5
1,2-DIBROMOETHANE	<28000	ug/Kgdrywt	5600	28000	5
ETHYLBENZENE	130000	ug/Kgdrywt	5600	28000	5
NAPHTHALENE	90000	ug/Kgdrywt	5600	28000	5
MTBE	<28000	ug/Kgdrywt	5600	28000	5
TOTAL XYLENES	300000	ug/Kgdrywt	5600	28000	5
DIBROMOFLUOROMETHANE	100	%	5600		
1,2-DICHLOROETHANE-D4	90	%	5600		
TOLUENE-D8	100	%	5600		
P-BROMOFLUOROBENZENE	100	%	5600		

**Report Notes:** J, O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB130203D

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 80.6

Lab Sample ID: WP2792-005

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	10.4			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-5  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 10 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB130203D	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	81.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7

CC: MS. LEE LECK  
TETRA TECH NUS

340 Cambridge St., Box 7  
P.O. Box 720, Westbrook, ME 04098  
Tel: (207) 874-2400 Fax: (207) 779-4029

<http://katahdinlab.com>

210 West Road No. 5, Portsmouth, NH 03801  
Tel: (603) 431-5777 Fax: (603) 436-3356

0000046

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-6  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 84  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB140304	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<400	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	<400	ug/Kg	1.2	400	330
ACENAPHTHYLENE	<400	ug/Kg	1.2	400	330
ACENAPHTHENE	<400	ug/Kg	1.2	400	330
FLUORENE	<400	ug/Kg	1.2	400	330
PHENANTHRENE	<400	ug/Kg	1.2	400	330
ANTHRACENE	<400	ug/Kg	1.2	400	330
FLUORANTHENE	<400	ug/Kg	1.2	400	330
PYRENE	<400	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	<400	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	57	%	1.2		
2-FLUOROBIPHENYL	63	%	1.2		
TERPHENYL-D14	91	%	1.2		

Report Notes:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-6  
SDG: WP2792  
Report Date: 8/2/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 84  
Method: SW8260  
Date Analyzed: 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB140304	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/Kg	0.98	5	5
TOLUENE	12	ug/Kg	0.98	5	5
1,2-DIBROMOETHANE	<5	ug/Kg	0.98	5	5
ETHYLBENZENE	13	ug/Kg	0.98	5	5
NAPHTHALENE	60	ug/Kg	0.98	5	5
MTBE	<5	ug/Kg	0.98	5	5
TOTAL XYLENES	12	ug/Kg	0.98	5	5
DIBROMOFLUOROMETHANE	119	%	0.98		
1,2-DICHLOROETHANE-D4	#182	%	0.98		
TOLUENE-D8	96	%	0.98		
P-BROMOFLUOROBENZENE	100	%	0.98		

Report Notes: #

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2972-6RE  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** -  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB140304	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	7	ug/Kg	1.1	6	5
TOLUENE	<6	ug/Kg	1.1	6	5
1,2-DIBROMOETHANE	<6	ug/Kg	1.1	6	5
ETHYLBENZENE	6	ug/Kg	1.1	6	5
NAPHTHALENE	J4	ug/Kg	1.1	6	5
MTBE	<6	ug/Kg	1.1	6	5
TOTAL XYLENES	J5	ug/Kg	1.1	6	5
DIBROMOFLUOROMETHANE	114	%	1.1		
1,2-DICHLOROETHANE-D4	118	%	1.1		
TOLUENE-D8	103	%	1.1		
P-BROMOFLUOROBENZENE	124	%	1.1		

**Report Notes:** J, O-13

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB140304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 84.4

Lab Sample ID: WP2792-006

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	4.9			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-6  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 4 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB140304	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	84.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-7  
SDG: WP2792  
Report Date: 8/5/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 85  
Method: EPA 8270  
Date Analyzed: 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB160304	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<400	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	<400	ug/Kg	1.2	400	330
ACENAPHTHYLENE	<400	ug/Kg	1.2	400	330
ACENAPHTHENE	<400	ug/Kg	1.2	400	330
FLUORENE	<400	ug/Kg	1.2	400	330
PHENANTHRENE	<400	ug/Kg	1.2	400	330
ANTHRACENE	<400	ug/Kg	1.2	400	330
FLUORANTHENE	<400	ug/Kg	1.2	400	330
PYRENE	<400	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	<400	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	56	%	1.2		
2-FLUOROBIPHENYL	57	%	1.2		
TERPHENYL-D14	83	%	1.2		

Report Notes:

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-7  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 85  
**Method:** SW8260  
**Date Analyzed:** 6/16/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB160304	SL	6/7/99	6/8/99	6/16/99	KRT	5030	KRT

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	8	ug/Kg	1.0	5	5
TOLUENE	<5	ug/Kg	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/Kg	1.0	5	5
ETHYLBENZENE	<5	ug/Kg	1.0	5	5
NAPHTHALENE	J4	ug/Kg	1.0	5	5
MTBE	<5	ug/Kg	1.0	5	5
TOTAL XYLENES	<5	ug/Kg	1.0	5	5
DIBROMOFLUOROMETHANE	115	%	1.0		
1,2-DICHLOROETHANE-D4	118	%	1.0		
TOLUENE-D8	125	%	1.0		
p-BROMOFLUOROBENZENE	103	%	1.0		

**Report Notes:** J

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB160304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 85.3

Lab Sample ID: WP2792-007

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	6.5			P	1

Color Before: BROWN

Texture: FINE

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-7  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 5 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB160304	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	85.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm

PF11TSS7

CC: MS. LEE LECK

TETRA TECH NUS

FOSTER PALZA 7

661 ANDERSEN DR.



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-8  
SDG: WP2792  
Report Date: 8/5/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 84  
Method: EPA 8270  
Date Analyzed: 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB170304	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	2600	ug/Kg	1.2	400	330
2-METHYLNAPHTHALENE	2000	ug/Kg	1.2	400	330
ACENAPHTHYLENE	<400	ug/Kg	1.2	400	330
ACENAPHTHENE	<400	ug/Kg	1.2	400	330
FLUORENE	<400	ug/Kg	1.2	400	330
PHENANTHRENE	<400	ug/Kg	1.2	400	330
ANTHRACENE	<400	ug/Kg	1.2	400	330
FLUORANTHENE	<400	ug/Kg	1.2	400	330
PYRENE	<400	ug/Kg	1.2	400	330
BENZO[A]ANTHRACENE	<400	ug/Kg	1.2	400	330
CHRYSENE	<400	ug/Kg	1.2	400	330
BENZO[B]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[K]FLUORANTHENE	<400	ug/Kg	1.2	400	330
BENZO[A]PYRENE	<400	ug/Kg	1.2	400	330
INDENO[1,2,3-CD]PYRENE	<400	ug/Kg	1.2	400	330
DIBENZ[A,H]ANTHRACENE	<400	ug/Kg	1.2	400	330
BENZO[G,H,I]PERYLENE	<400	ug/Kg	1.2	400	330
NITROBENZENE-D5	55	%	1.2		
2-FLUOROBIPHENYL	65	%	1.2		
TERPHENYL-D14	82	%	1.2		

Report Notes:

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-8  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 84  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB170304	SL	6/7/99	6/8/99	6/11/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	E24000	ug/Kgdrywt	110	550	5
TOLUENE	E85000	ug/Kgdrywt	110	550	5
1,2-DIBROMOETHANE	<550	ug/Kgdrywt	110	550	5
ETHYLBENZENE	E37000	ug/Kgdrywt	110	550	5
NAPHTHALENE	16000	ug/Kgdrywt	110	550	5
MTBE	4300	ug/Kgdrywt	110	550	5
TOTAL XYLENES	180000	ug/Kgdrywt	110	550	5
DIBROMOFLUOROMETHANE	101	%	110		
1,2-DICHLOROETHANE-D4	132	%	110		
TOLUENE-D8	101	%	110		
P-BROMOFLUOROBENZENE	96	%	110		

**Report Notes:** E

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-8DL  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 84  
**Method:** SW8260  
**Date Analyzed:** 6/15/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB170304	SL	6/7/99	6/8/99	6/15/99	DJP	5030	DJP

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	32000	ug/Kgdrywt	2300	12000	5
TOLUENE	240000	ug/Kgdrywt	2300	12000	5
1,2-DIBROMOETHANE	<12000	ug/Kgdrywt	2300	12000	5
ETHYLBENZENE	49000	ug/Kgdrywt	2300	12000	5
NAPHTHALENE	14000	ug/Kgdrywt	2300	12000	5
MTBE	<12000	ug/Kgdrywt	2300	12000	5
TOTAL XYLENES	250000	ug/Kgdrywt	2300	12000	5
DIBROMOFLUOROMETHANE	96	%	2300		
1,2-DICHLOROETHANE-D4	94	%	2300		
TOLUENE-D8	109	%	2300		
P-BROMOFLUOROBENZENE	104	%	2300		

Report Notes: O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB170304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 83.8

Lab Sample ID: WP2792-008

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	7.4			P	1

Color Before: BROWN

Texture: FINE

Color After: YELLOW

Clarity After: CLEAR

Comments:

FORM I - IN

0000039



CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-8  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 6 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25SLB170304	Solid			ROGER FRANKLIN		06/07/99	06/08/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Solids-Total Residue (TS)	84.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99	JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-9  
SDG: WP2792  
Report Date: 8/5/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 76  
Method: EPA 8270  
Date Analyzed: 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB120203	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	E10000	ug/Kg	1.3	430	330
2-METHYLNAPHTHALENE	E7400	ug/Kg	1.3	430	330
ACENAPHTHYLENE	<430	ug/Kg	1.3	430	330
ACENAPHTHENE	<430	ug/Kg	1.3	430	330
FLUORENE	<430	ug/Kg	1.3	430	330
PHENANTHRENE	540	ug/Kg	1.3	430	330
ANTHRACENE	<430	ug/Kg	1.3	430	330
FLUORANTHENE	<430	ug/Kg	1.3	430	330
PYRENE	J240	ug/Kg	1.3	430	330
BENZO[A]ANTHRACENE	<430	ug/Kg	1.3	430	330
CHRYSENE	<430	ug/Kg	1.3	430	330
BENZO[B]FLUORANTHENE	<430	ug/Kg	1.3	430	330
BENZO[K]FLUORANTHENE	<430	ug/Kg	1.3	430	330
BENZO[A]PYRENE	<430	ug/Kg	1.3	430	330
INDENO[1,2,3-CD]PYRENE	<430	ug/Kg	1.3	430	330
DIBENZ[A,H]ANTHRACENE	<430	ug/Kg	1.3	430	330
BENZO[G,H,I]PERYLENE	<430	ug/Kg	1.3	430	330
NITROBENZENE-D5	50	%	1.3		
2-FLUOROBIPHENYL	63	%	1.3		
TERPHENYL-D14	80	%	1.3		

Report Notes: J, E

**KATAHDIN ANALYTICAL SERVICES  
REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-9DL  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 76  
**Method:** EPA 8270  
**Date Analyzed:** 7/26/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB120203	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	11000	ug/Kg	6.6	2200	330
2-METHYLNAPHTHALENE	7900	ug/Kg	6.6	2200	330
ACENAPHTHYLENE	<2200	ug/Kg	6.6	2200	330
ACENAPHTHENE	<2200	ug/Kg	6.6	2200	330
FLUORENE	<2200	ug/Kg	6.6	2200	330
PHENANTHRENE	<2200	ug/Kg	6.6	2200	330
ANTHRACENE	<2200	ug/Kg	6.6	2200	330
FLUORANTHENE	<2200	ug/Kg	6.6	2200	330
PYRENE	<2200	ug/Kg	6.6	2200	330
BENZO[A]ANTHRACENE	<2200	ug/Kg	6.6	2200	330
CHRYSENE	<2200	ug/Kg	6.6	2200	330
BENZO[B]FLUORANTHENE	<2200	ug/Kg	6.6	2200	330
BENZO[K]FLUORANTHENE	<2200	ug/Kg	6.6	2200	330
BENZO[A]PYRENE	<2200	ug/Kg	6.6	2200	330
INDENO[1,2,3-CD]PYRENE	<2200	ug/Kg	6.6	2200	330
DIBENZ[A,H]ANTHRACENE	<2200	ug/Kg	6.6	2200	330
BENZO[G,H,I]PERYLENE	<2200	ug/Kg	6.6	2200	330
NITROBENZENE-D5	41	%	6.6		
2-FLUOROBIPHENYL	59	%	6.6		
TERPHENYL-D14	74	%	6.6		

**Report Notes:** O-2

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-9  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 76  
**Method:** SW8260  
**Date Analyzed:** 6/9/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB120203	SL	6/7/99	6/8/99	6/9/99	HMP	5035	HMP

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	E100000	ug/Kgdrywt	150	750	5
TOLUENE	E320000	ug/Kgdrywt	150	750	5
1,2-DIBROMOETHANE	<750	ug/Kgdrywt	150	750	5
ETHYLBENZENE	E380000	ug/Kgdrywt	150	750	5
NAPHTHALENE	E160000	ug/Kgdrywt	150	750	5
MTBE	<750	ug/Kgdrywt	150	750	5
TOTAL XYLENES	740000	ug/Kgdrywt	150	750	5
DIBROMOFLUOROMETHANE	93	%	150		
1,2-DICHLOROETHANE-D4	#251	%	150		
TOLUENE-D8	101	%	150		
P-BROMOFLUOROBENZENE	#127	%	150		

**Report Notes:** E, #

**KATAHDIN ANALYTICAL SERVICES**  
**REPORT OF ANALYTICAL RESULTS**

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-9DL  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No.:** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 76  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB120203	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	120000	ug/Kgdrywt	15000	75000	5
TOLUENE	360000	ug/Kgdrywt	15000	75000	5
1,2-DIBROMOETHANE	<75000	ug/Kgdrywt	15000	75000	5
ETHYLBENZENE	560000	ug/Kgdrywt	15000	75000	5
NAPHTHALENE	210000	ug/Kgdrywt	15000	75000	5
MTBE	<75000	ug/Kgdrywt	15000	75000	5
TOTAL XYLENES	2200000	ug/Kgdrywt	15000	75000	5
DIBROMOFLUOROMETHANE	102	%	15000		
1,2-DICHLOROETHANE-D4	91	%	15000		
TOLUENE-D8	101	%	15000		
P-BROMOFLUOROBENZENE	101	%	15000		

**Report Notes:** O-2

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB120203

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 76.0

Lab Sample ID: WP2792-009

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	26.2			P	1

Color Before: BROWN

Texture: MEDIUM

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-9  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 7 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED		
25SLB120203	Solid			ROGER FRANKLIN		06/07/99	06/08/99	
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED	BY	NOTES
Solids-Total Residue (TS)	76.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99	JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11TSS7  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-11  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** -  
**Method:** SW8260  
**Date Analyzed:** 6/10/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25TL00501	SL	6/7/99	6/8/99	6/10/99	JSS	5030	JSS

Compound	Result	Units	BF	Sample PQL	Method PQL
BENZENE	<5	ug/Kgdrywt	1.0	5	5
TOLUENE	<5	ug/Kgdrywt	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/Kgdrywt	1.0	5	5
ETHYLBENZENE	<5	ug/Kgdrywt	1.0	5	5
NAPHTHALENE	<5	ug/Kgdrywt	1.0	5	5
MTBE	<5	ug/Kgdrywt	1.0	5	5
TOTAL XYLENES	<5	ug/Kgdrywt	1.0	5	5
DIBROMOFLUOROMETHANE	104	%	1.0		
1,2-DICHLOROETHANE-D4	101	%	1.0		
TOLUENE-D8	108	%	1.0		
P-BROMOFLUOROBENZENE	99	%	1.0		

**Report Notes:**



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: WP2792-12  
SDG: WP2792  
Report Date: 8/5/99  
PO No. : N7912-P99264  
Project: CTO #68  
% Solids: 92  
Method: EPA 8270  
Date Analyzed: 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB150304	SL	6/7/99	6/8/99	6/16/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<360	ug/Kg	1.1	360	330
2-METHYLNAPHTHALENE	<360	ug/Kg	1.1	360	330
ACENAPHTHYLENE	<360	ug/Kg	1.1	360	330
ACENAPHTHENE	<360	ug/Kg	1.1	360	330
FLUORENE	<360	ug/Kg	1.1	360	330
PHENANTHRENE	<360	ug/Kg	1.1	360	330
ANTHRACENE	<360	ug/Kg	1.1	360	330
FLUORANTHENE	<360	ug/Kg	1.1	360	330
PYRENE	<360	ug/Kg	1.1	360	330
BENZO[A]ANTHRACENE	<360	ug/Kg	1.1	360	330
CHRYSENE	<360	ug/Kg	1.1	360	330
BENZO[B]FLUORANTHENE	<360	ug/Kg	1.1	360	330
BENZO[K]FLUORANTHENE	<360	ug/Kg	1.1	360	330
BENZO[A]PYRENE	<360	ug/Kg	1.1	360	330
INDENO[1,2,3-CD]PYRENE	<360	ug/Kg	1.1	360	330
DIBENZ[A,H]ANTHRACENE	<360	ug/Kg	1.1	360	330
BENZO[G,H,I]PERYLENE	<360	ug/Kg	1.1	360	330
NITROBENZENE-D5	46	%	1.1		
2-FLUOROBIPHENYL	56	%	1.1		
TERPHENYL-D14	77	%	1.1		

Report Notes:

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** WP2792-12  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 92  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
25SLB150304	SL	6/7/99	6/8/99	6/11/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<6	ug/Kg	1.2	6	5
TOLUENE	<6	ug/Kg	1.2	6	5
1,2-DIBROMOETHANE	<6	ug/Kg	1.2	6	5
ETHYLBENZENE	<6	ug/Kg	1.2	6	5
NAPHTHALENE	<6	ug/Kg	1.2	6	5
MTBE	<6	ug/Kg	1.2	6	5
TOTAL XYLENES	<6	ug/Kg	1.2	6	5
DIBROMOFLUOROMETHANE	121	%	1.2		
1,2-DICHLOROETHANE-D4	118	%	1.2		
TOLUENE-D8	112	%	1.2		
P-BROMOFLUOROBENZENE	87	%	1.2		

**Report Notes:**

## INORGANIC ANALYSIS DATA SHEET

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB150304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 91.7

Lab Sample ID: WP2792-012

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

CAS No.	Analyte	Concentration	C	Q	M	DF
7439-92-1	LEAD	5.9			P	1

Color Before: BROWN

Texture: COARSE

Color After: YELLOW

Clarity After: CLEAR

Comments:

CLIENT: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr., Suite 102  
Tallahassee, FL 32308

Lab Number : WP-2792-12  
Report Date: 08/11/99  
PO No. : N7912-P99264  
Project : CTO #68

WIC#: CNC CHARLESTON

REPORT OF ANALYTICAL RESULTS

Page 8 of 10

SAMPLE DESCRIPTION	MATRIX			SAMPLED BY		SAMPLED DATE RECEIVED	
25SLB150304	Solid			ROGER FRANKLIN		06/07/99	06/08/99
PARAMETER	RESULT	UNITS	DF	*PQL	METHOD	ANALYZED BY	NOTES
Solids-Total Residue (TS)	91.	wt %	1.0	0.10	CLP/CIP SOW	06/14/99 JF	1
Total Combustible Organics	1.4	wt %	1.0	0.1	ASTM D2974-8	06/14/99 JF	1

\* PQL (Practical Quantitation Level) represents laboratory reporting limits and may not reflect sample-specific reporting limits. Sample-specific limits are indicated by results annotated with '<' values.  
(1) Sample Preparation on 06/11/99 by JF

08/11/99

LJO/baeajc(dw)/msm  
PF11VSS8  
CC: MS. LEE LECK  
TETRA TECH NUS  
FOSTER PALZA 7  
661 ANDERSEN DR.

2A  
SOIL SEMIVOLATILE SYSTEM MONITORING COMPOUND RECOVERY

Lab Name: Katahdin Analytical Services

SDG No.: WP2792

Matrix: SOIL

Client Sample ID	Lab Sample ID	SMC1 (NBZ) #	SMC2 (FBP) #	SMC3 (TPH) #	Total Out
SBLK;061599	SBLK;061599	70	71	88	0
25SLB090304	WP2792-1	42	48	86	0
25SLB140304	WP2792-6	57	63	91	0
25SLB160304	WP2792-7	56	57	83	0
25SLB170304	WP2792-8	55	65	82	0
25SLB150304	WP2792-12	46	56	77	0
25SLB100102	WP2792-2	49	57	75	0
25SLB110203	WP2792-3	53	60	81	0
25SLB130203	WP2792-4	47	71	75	0
25SLB130203D	WP2792-5	53	77	84	0
25SLB120203	WP2792-9	50	63	80	0
LCS;061699	LCS;061699	71	80	86	0
25SLB130203DL	WP2792-4DL	37	63	60	0
25SLB130203DDL	WP2792-5DL	0*	74	39	1
25SLB120203DL	WP2792-9DL	41	59	74	0

QC LIMITS

SMC1 (NBZ)	=	NITROBENZENE-D5	(14-107)
SMC2 (FBP)	=	2-FLUOROBIPHENYL	(32-109)
SMC3 (TPH)	=	TERPHENYL-D14	(26-116)

# Column to be used to flag recovery value

\* Values are outside of QC limits

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** SBLK061599  
**SDG:** WP2792  
**Report Date:** 8/5/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 100  
**Method:** EPA 8270  
**Date Analyzed:** 7/23/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
SBLK061599	SL	-	-	6/15/99	PMM	EPA 3550	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
NAPHTHALENE	<330	ug/Kg	1.0	330	330
2-METHYLNAPHTHALENE	<330	ug/Kg	1.0	330	330
ACENAPHTHYLENE	<330	ug/Kg	1.0	330	330
ACENAPHTHENE	<330	ug/Kg	1.0	330	330
FLUORENE	<330	ug/Kg	1.0	330	330
PHENANTHRENE	<330	ug/Kg	1.0	330	330
ANTHRACENE	<330	ug/Kg	1.0	330	330
FLUORANTHENE	<330	ug/Kg	1.0	330	330
PYRENE	<330	ug/Kg	1.0	330	330
BENZO[A]ANTHRACENE	<330	ug/Kg	1.0	330	330
CHRYSENE	<330	ug/Kg	1.0	330	330
BENZO[B]FLUORANTHENE	<330	ug/Kg	1.0	330	330
BENZO[K]FLUORANTHENE	<330	ug/Kg	1.0	330	330
BENZO[A]PYRENE	<330	ug/Kg	1.0	330	330
INDENO[1,2,3-CD]PYRENE	<330	ug/Kg	1.0	330	330
DIBENZ[A,H]ANTHRACENE	<330	ug/Kg	1.0	330	330
BENZO[G,H,I]PERYLENE	<330	ug/Kg	1.0	330	330
NITROBENZENE-D5	70	%	1.0		
2-FLUOROBIPHENYL	71	%	1.0		
TERPHENYL-D14	88	%	1.0		

Report Notes:

# Katahdin Analytical Services

## 8270 LCS Recovery Sheet

Lab File: I3932

Sample ID: LCS;061699

Date Run: 7/26/99

Analyst: KRT

Time Injected 9:35:00 AM

Matrix: SL

Compound Name	Spike Amt (ug/Kg)	Result (ug/Kg)	Rec (%)	Limits (%)
2-METHYLNAPHTHALENE	1667	1460	88	60-140
ACENAPHTHENE	1667	1220	73	60-140
ACENAPHTHYLENE	1667	1220	73	60-140
ANTHRACENE	1667	1220	73	60-140
BENZO[A]ANTHRACENE	1667	1240	74	60-140
BENZO[A]PYRENE	1667	1200	72	60-140
BENZO[B]FLUORANTHENE	1667	1320	79	60-140
BENZO[G,H,I]PERYLENE	1667	1320	79	60-140
BENZO[K]FLUORANTHENE	1667	1320	79	60-140
CHRYSENE	1667	1410	84	60-140
DIBENZ[A,H]ANTHRACENE	1667	1210	72	60-140
FLUORANTHENE	1667	1220	73	60-140
FLUORENE	1667	1220	73	60-140
INDENO[1,2,3-CD]PYRENE	1667	1320	79	60-140
NAPHTHALENE	1667	1210	73	60-140
PHENANTHRENE	1667	1340	80	60-140
PYRENE	1667	1370	82	60-140

\* Out of Limits

1

2A  
WATER VOLATILE SYSTEM MONITORING COMPOUND RECOVERY

Lab Name: Katahdin Analytical Services

SDG No.: WP2792

Matrix: WATER

Client Sample ID	Lab Sample ID	SMC1 (DFM) #	SMC2 (DCA) #	SMC3 (TOL) #	SMC4 (BFB) #	Total Out
LCSF10A	LCSF10A	93	87	103	106	0
VLKF10A	VLKF10A	94	87	103	98	0
LCSF11A	LCSF11A	102	86	101	103	0
VLKF11B	VLKF11B	97	86	101	98	0
LCSF14A	LCSF14A	98	80	103	101	0
VLKF14A	VLKF14A	98	84	102	96	0
LCSF15A	LCSF15A	96	87	107	106	0
VLKF15B	VLKF15B	94	93	106	96	0
LCSM10A	LCSM10A	102	94	105	99	0
VLKM10B	VLKM10B	104	96	108	98	0
LCSQ09A	LCSQ09A	86	84	88	84	0
VLKQ09A	VLKQ09A	83	81	90	88	0

**QC LIMITS**

SMC1 (DFM) = DIBROMOFLUOROMETHANE (75-129)  
 SMC2 (DCA) = 1,2-DICHLOROETHANE-D4 (65-135)  
 SMC3 (TOL) = TOLUENE-D8 (82-120)  
 SMC4 (BFB) = P-BROMOFLUOROBENZENE (69-125)

# Column to be used to flag recovery value

\* Values are outside of QC limits





# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKF10A  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No.:** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 6/10/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKF10A	AQ	-	-	6/10/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	94	%	1.0		
1,2-DICHLOROETHANE-D4	87	%	1.0		
TOLUENE-D8	103	%	1.0		
P-BROMOFLUOROBENZENE	98	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: F0891**

**Sample ID: LCSF10A**

**Date Run: 6/10/99**

**Analyst: DJP**

**Time Injected 8:12:00 PM**

**Matrix: AQ**

<b>Compound Name</b>	<b>Spike Amt (ug/L)</b>	<b>Result (ug/L)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	55.7	111	60-140
BENZENE	50	54.0	108	60-140
ETHYLBENZENE	50	54.4	109	60-140
MTBE	50	50.7	101	60-140
NAPHTHALENE	50	50.9	102	60-140
TOLUENE	50	55.4	111	60-140
TOTAL XYLENES	150	162	108	60-140

**\* Out of Limits**

**1**



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: VBLKF11B  
SDG: WP2792  
Report Date: 8/2/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: N/A  
Method: SW8260  
Date Analyzed: 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKF11B	AQ	-	-	6/11/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	LS	ug/L	1.0	5	5
TOLUENE	LS	ug/L	1.0	5	5
1,2-DIBROMOETHANE	LS	ug/L	1.0	5	5
ETHYLBENZENE	LS	ug/L	1.0	5	5
NAPHTHALENE	LS	ug/L	1.0	5	5
MTBE	LS	ug/L	1.0	5	5
TOTAL XYLENES	LS	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	97	%	1.0		
1,2-DICHLOROETHANE-D4	86	%	1.0		
TOLUENE-D8	101	%	1.0		
P-BROMOFLUOROBENZENE	98	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

Lab File: F0909

Sample ID: LCSF11A

Date Run: 6/11/99

Analyst: JSS

Time Injected 11:39:00 AM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	51.1	102	60-140
BENZENE	50	54.0	108	60-140
ETHYLBENZENE	50	53.0	106	60-140
MTBE	50	51.8	104	60-140
NAPHTHALENE	50	50.9	102	60-140
TOLUENE	50	54.6	109	60-140
TOTAL XYLENES	150	157	105	60-140

\* Out of Limits

1

1000547

# Katahdin Analytical Services

## 8260 LCS Recovery Sheet

Lab File: F0944

Sample ID: LCSF14A

Date Run: 6/14/99

Analyst: DJP

Time Injected 11:07:00 AM

Matrix: AQ

Compound Name	Spike Amt (ug/L)	Result (ug/L)	Rec (%)	Limits (%)
1,2-DIBROMOETHANE	50	49.4	99	60-140
BENZENE	50	51.5	103	60-140
ETHYLBENZENE	50	51.9	104	60-140
MTBE	50	46.8	94	60-140
NAPHTHALENE	50	49.9	100	60-140
TOLUENE	50	53.1	106	60-140
TOTAL XYLENES	150	156	104	60-140

\* Out of Limits

1

1000559

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKF15B  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 6/15/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKF15B	AQ	-	-	6/15/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	94	%	1.0		
1,2-DICHLOROETHANE-D4	93	%	1.0		
TOLUENE-D8	106	%	1.0		
P-BROMOFLUOROBENZENE	96	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: F0977**

**Sample ID: LCSF15A**

**Date Run: 6/15/99**

**Analyst: DJP**

**Time Injected 9:26:00 AM**

**Matrix: AQ**

<b>Compound Name</b>	<b>Spike Amt (ug/L)</b>	<b>Result (ug/L)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	51.1	102	60-140
BENZENE	50	54.7	109	60-140
ETHYLBENZENE	50	55.0	110	60-140
MTBE	50	49.4	99	60-140
NAPHTHALENE	50	49.3	98	60-140
TOLUENE	50	56.0	112	60-140
TOTAL XYLENES	150	162	108	60-140

**\* Out of Limits**

**1**

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKM10B  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** N/A  
**Method:** SW8260  
**Date Analyzed:** 6/10/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKM10B	AQ	-	-	6/10/99	JSS	5030	JSS

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	104	%	1.0		
1,2-DICHLOROETHANE-D4	96	%	1.0		
TOLUENE-D8	108	%	1.0		
P-BROMOFLUOROBENZENE	98	%	1.0		

Report Notes:



**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: M0599**

**Sample ID: LCSM10A**

**Date Run: 6/10/99**

**Analyst: JSS**

**Time Injected 9:52:00 AM**

**Matrix: AQ**

<b>Compound Name</b>	<b>Spike Amt (ug/L)</b>	<b>Result (ug/L)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	44.2	88	60-140
BENZENE	50	51.5	103	60-140
ETHYLBENZENE	50	51.0	102	60-140
MTBE	50	45.3	91	60-140
NAPHTHALENE	50	45.7	91	60-140
TOLUENE	50	51.6	103	60-140
TOTAL XYLENES	150	149	99	60-140

**\* Out of Limits**

**1**

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
 Proj. ID: CNC CHARLESTON

Lab Number: VBLKQ09A  
 SDG: WP2792  
 Report Date: 8/2/99  
 PO No.: N7912-P99264  
 Project: CTO #68  
 % Solids: N/A  
 Method: SW8260  
 Date Analyzed: 6/9/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKQ09A	AQ	-	-	6/9/99	HMP	5030	HMP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/L	1.0	5	5
TOLUENE	<5	ug/L	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/L	1.0	5	5
ETHYLBENZENE	<5	ug/L	1.0	5	5
NAPHTHALENE	<5	ug/L	1.0	5	5
MTBE	<5	ug/L	1.0	5	5
TOTAL XYLENES	<5	ug/L	1.0	5	5
DIBROMOFLUOROMETHANE	83	%	1.0		
1,2-DICHLOROETHANE-D4	81	%	1.0		
TOLUENE-D8	90	%	1.0		
P-BROMOFLUOROBENZENE	88	%	1.0		

Report Notes:

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: Q5423**

**Sample ID: LCSQ09A**

**Date Run: 6/9/99**

**Analyst: HMP**

**Time Injected 11:36:00 AM**

**Matrix: AQ**

<b>Compound Name</b>	<b>Spike Amt (ug/L)</b>	<b>Result (ug/L)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	48.7	97	60-140
BENZENE	50	49.6	99	60-140
ETHYLBENZENE	50	57.1	114	60-140
MTBE	50	43.1	86	60-140
NAPHTHALENE	50	48.0	96	60-140
TOLUENE	50	50.4	101	60-140
TOTAL XYLENES	150	149	99	60-140

**\* Out of Limits**

**1**

2A  
SOIL VOLATILE SYSTEM MONITORING COMPOUND RECOVERY

Lab Name: Katahdin Analytical Services

SDG No.: WP2792

Matrix: SOIL

Client Sample ID	Lab Sample ID	SMC1 (DFM) #	SMC2 (DCA) #	SMC3 (TOL) #	SMC4 (BFB) #	Total Out
MBLK061099	MBLK061099	92	86	102	95	0
25SLB130203DL	WP2792-4DL	92	87	103	104	0
25SLB130203DDL	WP2792-5DL	100	90	100	100	0
25SLB120203DL	WP2792-9DL	102	91	101	101	0
25SLB100102	WP2792-2	92	104	108	120	0
25SLB170304	WP2792-8	101	132	101	96	0
25SLB100102DL	WP2792-2DL	95	96	106	109	0
25SLB170304DL	WP2792-8DL	96	94	109	104	0
25TL00501	WP2792-11	104	101	108	99	0
25SLB130203	WP2792-4	88	106	89	98	0
25SLB130203D	WP2792-5	99	150*	88	106	1
25SLB120203	WP2792-9	93	251*	101	127	1
LCSZ11A	LCSZ11A	100	100	100	95	0
VBLKZ11B	VBLKZ11B	130	126	119	88	0
25SLB110203	WP2792-3	82	92	94	88	0
25SLB140304	WP2792-6	119	182*	96	100	1
25SLB150304	WP2792-12	121	118	112	87	0
25SLB140304RE	WP2972-6RE	114	118	103	124	0
LCSZ16A	LCSZ16A	101	112	107	103	0
VBLKZ16B	VBLKZ16B	125	127	120	105	0
25SLB090304	WP2792-1	88	92	86	72	0
25SLB160304	WP2792-7	115	118	125	103	0

**QC LIMITS**

SMC1 (DFM) = DIBROMOFLUOROMETHANE (69-148)  
 SMC2 (DCA) = 1,2-DICHLOROETHANE-D4 (66-149)  
 SMC3 (TOL) = TOLUENE-D8 (68-147)  
 SMC4 (BFB) = P-BROMOFLUOROBENZENE (64-152)

# Column to be used to flag recovery value

\* Values are outside of QC limits



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

Client: Paul Calligan  
Tetra Tech NUS  
1401 Oven Park Dr.  
Suite 102  
Tallahassee, FL 32308  
Proj. ID: CNC CHARLESTON

Lab Number: MBLK061099  
SDG: WP2792  
Report Date: 8/2/99  
PO No.: N7912-P99264  
Project: CTO #68  
% Solids: 100  
Method: SW8260  
Date Analyzed: 6/10/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
MBLK061099	SL	-	-	6/10/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<600	ug/Kgdrywt	120	600	5
TOLUENE	<600	ug/Kgdrywt	120	600	5
1,2-DIBROMOETHANE	<600	ug/Kgdrywt	120	600	5
ETHYLBENZENE	<600	ug/Kgdrywt	120	600	5
NAPHTHALENE	<600	ug/Kgdrywt	120	600	5
MTBE	<600	ug/Kgdrywt	120	600	5
TOTAL XYLENES	<600	ug/Kgdrywt	120	600	5
DIBROMOFLUOROMETHANE	92	%	120		
1,2-DICHLOROETHANE-D4	86	%	120		
TOLUENE-D8	102	%	120		
P-BROMOFLUOROBENZENE	95	%	120		

Report Notes:



# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
Tetra Tech NUS  
1401 Owen Park Dr.  
Suite 102  
Tallahassee, FL 32308

**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKZ11B  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 100  
**Method:** SW8260  
**Date Analyzed:** 6/11/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKZ11B	SL	-	-	6/11/99	DJP	5030	DJP

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	<5	ug/Kg	1.0	5	5
TOLUENE	<5	ug/Kg	1.0	5	5
1,2-DIBROMOETHANE	<5	ug/Kg	1.0	5	5
ETHYLBENZENE	<5	ug/Kg	1.0	5	5
NAPHTHALENE	<5	ug/Kg	1.0	5	5
MTBE	<5	ug/Kg	1.0	5	5
TOTAL XYLENES	<5	ug/Kg	1.0	5	5
DIBROMOFLUOROMETHANE	130	%	1.0		
1,2-DICHLOROETHANE-D4	126	%	1.0		
TOLUENE-D8	119	%	1.0		
P-BROMOFLUOROBENZENE	88	%	1.0		

**Report Notes:**

**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: Z1075**

**Sample ID: LCSZ11A**

**Date Run: 6/11/99**

**Analyst: DJP**

**Time Injected 2:41:00 PM**

**Matrix: SL**

<b>Compound Name</b>	<b>Spike Amt (ug/Kg)</b>	<b>Result (ug/Kg)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	50.0	100	60-140
BENZENE	50	51.8	104	60-140
ETHYLBENZENE	50	66.1	132	60-140
MTBE	50	50.7	101	60-140
NAPHTHALENE	50	62.2	124	60-140
TOLUENE	50	50.9	102	60-140
TOTAL XYLENES	150	202	135	60-140

**\* Out of Limits**

**1**

# KATAHDIN ANALYTICAL SERVICES

## REPORT OF ANALYTICAL RESULTS

**Client:** Paul Calligan  
 Tetra Tech NUS  
 1401 Oven Park Dr.  
 Suite 102  
 Tallahassee, FL 32308  
  
**Proj. ID:** CNC CHARLESTON

**Lab Number:** VBLKZ16B  
**SDG:** WP2792  
**Report Date:** 8/2/99  
**PO No. :** N7912-P99264  
**Project:** CTO #68  
**% Solids:** 100  
**Method:** SW8260  
**Date Analyzed:** 6/16/99

Sample Description	Matrix	Sampled Date	Rec'd Date	Ext. Date	Ext'd By	Ext. Method	Analyst
VBLKZ16B	SL	-	-	6/16/99	KRT	5030	KRT

Compound	Result	Units	DF	Sample PQL	Method PQL
BENZENE	5	ug/Kg	1.0	5	5
TOLUENE	5	ug/Kg	1.0	5	5
1,2-DIBROMOETHANE	5	ug/Kg	1.0	5	5
ETHYLBENZENE	5	ug/Kg	1.0	5	5
NAPHTHALENE	5	ug/Kg	1.0	5	5
MTBE	5	ug/Kg	1.0	5	5
TOTAL XYLENES	5	ug/Kg	1.0	5	5
DIBROMOFLUOROMETHANE	125	%	1.0		
1,2-DICHLOROETHANE-D4	127	%	1.0		
TOLUENE-D8	120	%	1.0		
P-BROMOFLUOROBENZENE	105	%	1.0		

Report Notes:



**Katahdin Analytical Services**  
**8260 LCS Recovery Sheet**

**Lab File: Z1119**

**Sample ID: LCSZ16A**

**Date Run: 6/16/99**

**Analyst: KRT**

**Time Injected 2:17:00 PM**

**Matrix: SL**

<b>Compound Name</b>	<b>Spike Amt (ug/Kg)</b>	<b>Result (ug/Kg)</b>	<b>Rec (%)</b>	<b>Limits (%)</b>
1,2-DIBROMOETHANE	50	51.8	104	60-140
BENZENE	50	53.8	108	60-140
ETHYLBENZENE	50	64.3	129	60-140
MTBE	50	53.9	108	60-140
NAPHTHALENE	50	63.2	126	60-140
TOLUENE	50	52.5	105	60-140
TOTAL XYLENES	150	201	134	60-140

**\* Out of Limits**

**1**

**1000571**

5A  
SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB090304S

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 80.8

Lab Sample ID: WP2792-001S

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	Spiked		Sample		Spike Added	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
LEAD		64.6423	10.4929		53.82	100.6		75	125	P

Comments:

## SPIKE SAMPLE RECOVERY

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB090304S

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 80.8

Lab Sample ID: WP2792-001P

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg

Analyte	Spiked		Sample		Spike	%R	Q	Control Limits (%R)		M
	Sample	Result	Result	C				Low	High	
LEAD		61.0438	10.4929		50.32	100.5		75	125	P

Comments:

5D  
SPIKE DUPLICATES

Lab Name: Katahdin Analytical Services

Client Field ID: 25SLB090304

Matrix: SOIL

SDG Name: WP2792

Percent Solids: 80.8

Lab Sample ID: WP2792-001

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg								
Analyte	Control Limits	Spike Result	C	Spike Dup. Result	C	RPD	Q	M
LEAD		64.6423		61.0438		5.7		P

Comments:

## LABORATORY CONTROL SAMPLES

Lab Name: Katahdin Analytical Services

Sample ID: LCSSPG07ICS0

Matrix: SOIL

SDG Name: WP2792

QC Batch ID: PG07ICS0

Concentration Units (ug/L or mg/Kg dry weight): mg/Kg					
Analyte	TRUE	FOUND	% R	LIMITS (%)	
LEAD	66.0	71.20	107.9	68	132

8/4/99

**Karatidin Analytical Services, Inc.**  
**Quality Control Report**

**Method Blank and Laboratory Control Sample Results**

Client:	Tetra Tech NUS
Work Order:	WP2792

Parameter	Date of Prep	Date of Analysis	METHOD BLANK RESULTS				LABORATORY CONTROL SAMPLE RESULTS				
			Units	Concentration Measured in Blank	Acceptance Range	Practical Quantitation Level**	Units	True Value	Measured Value	Percent Recovered	Acceptance Range (%)
TS -Total Residue	11-Jun-99	14-Jun-99	wt %	< 0.10	< 0.10	0.10	wt %	90	89.6	99.6	80-120
	11-Jun-99	14-Jun-99	wt %	< 0.10	< 0.10	0.10					
TCO-Total Combustible Organics	11-Jun-99	14-Jun-99	wt %	< 0.10	< 0.10	0.10					

\*\* Practical quantitation level is the lowest concentration measurable for samples with normal chemical and physical composition during routine laboratory operations.

**DATA QUALITY COMMENTS:**

Results of all quality control measurements are within the laboratory and method specified acceptance range except as noted.

5000003



## Duplicate and Matrix Spike/Matrix Spike Duplicate Results

Client:	Tetra Tech NUS
Work Order:	WP2792

## DUPLICATE RESULTS

## MATRIX SPIKE/MATRIX SPIKE DUPLICATE RESULTS

Parameter	Sample No	Sample Measurements		Mean Conc	Acceptance Range		Concentration or Quantity Units	Matrix Spike Recovery (%)						Acceptance RPD (%)	Acceptance Range (%)
		Units	Rep 1	Rep 2	RPD (%)	for RPD (%)		Sample Only	Sample Spike Added	Sample +Spike	Sample +Spike	Sample +Spike	Sample +Spike		
								Dup 1	Dup 2	Dup 1	Dup 2	Dup 1	Dup 2		
TS	WP2792-8	mg/L	83.9	83.8	83.9	0.1	0-20	mg/L	NA					75-125	0-20
	WP2792-12	mg/L	91.3	91.7	91.5	0.4	0-20	mg/L	NA					75-125	0-20
TCO	WP2792-12	mg/L	1.40	1.37	1.39	2.2	0-20	mg/L	NA					75-125	0-20

RPD = Relative percent difference, which is the absolute value of the difference between two replicate results divided by the mean concentration then multiplied by 100%.

NA = Not applicable.

## DATA QUALITY COMMENTS:

Results of all quality control measurements are within the laboratory or contract specified acceptance range except as noted. The laboratory does not use the sample duplicate and matrix spike acceptance ranges as acceptance criteria for a specific analysis. Sample duplicate and matrix spike data are used to evaluate method performance in the environmental sample matrix only. Please refer to LCS data for assessment of quality control for each parameter.

CASE NARRATIVE  
for  
Katahdin Analytical  
Westbrook, ME  
Former Charleston Naval Complex Site  
SDG #96242

June 29, 1999

**Laboratory Identification:**

General Engineering Laboratories, Inc. (GEL)

**Mailing Address:**

P.O. Box 30712  
Charleston, SC 29417

**Express Mail Delivery and Shipping Address:**

2040 Savage Rd  
Charleston, SC 29414

**Telephone Number:**

(843) 556-8171

**Summary:**

**Sample receipt**

The samples from the former Charleston Naval Complex site arrived at General Engineering Laboratories, Inc., Charleston, SC on June 7, 1999, for environmental analyses. All sample containers arrived without any visible signs of tampering or breakage. The samples were delivered with chain of custody documentation and signatures.

The following samples were received by the laboratory:

<b><u>Laboratory Identification</u></b>	<b><u>Sample Description</u></b>
9906242-01	25SLB130203
9906242-02	25SLB130203D
9906242-03	25SLB50304
9906242-04	25SLB150304D





## Case Narrative

Sample analyses were conducted using methodology as outlined in General Engineering Laboratories Standard Operating Procedures. Any technical or administrative problems during analysis, data review, and reduction are listed below by analytical parameter.

## Internal Chain of Custody:

Custody was maintained for all samples.

## Data Package:

The enclosed data package contains the following sections: Case Narrative, Chain of Custody, Cooler Receipt Checklist, and General Chemistry.

The following are definitions of reporting limits used at General Engineering Laboratories:

**DL**            Detection Limit: The minimum level of an analyte that can be determined (identified not quantified) with 99% confidence. The values are normally achieved by preparing and analyzing seven aliquots of laboratory water spiked 1 to 5 times the estimated MDL, taking the standard deviation and multiplying it against the one-tailed t-statistic at 99%. This computed value is then verified for reasonableness by repeating the study using the concentration found in the initial study, calculating an F-ratio, and computing the final limit. Sample specific preparation and dilution factors are applied to these limits when they are reported.

The detection limit is the minimum concentration of a substance that can be identified, measured, and reported with 99% confidence that the analyte concentration is above zero. It answers the question "Is It Present."


**QL**            Quantitation Limit: The lowest concentration that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operating conditions. The QL is generally 5 to 10 times the MDL. However, it may be nominally chosen within these guidelines to simplify data reporting. For many analytes the QL analyte concentration is selected as the lowest non-zero standard in the calibration curve.

Sample QL's are highly matrix-dependent. Sample specific preparation and dilution factors are applied to these limits when they are reported.

The QL is always  $\geq$  DL.



This data package, to the best of my knowledge, is in compliance with technical and administrative requirements.



Valerie S. Davis  
Project Manager

fc:saic9906242%



**Case Narrative for  
KATA  
SDG# 96242**

**TOTAL ORGANIC CARBON**

**Analytical Batch Number:** 151981

**Analytical Method:** SW846 9060 Modified

<u>Laboratory Number</u>	<u>Sample Description</u>
9906242-03	25SLB50304
9906242-04	25SLB150304D
QC622750	Blank
QC622751	Duplicate of 9906242-03
QC622752	Post Spike of 9906242-03
QC622753	Laboratory Control Sample

**Sample Preparation:**

All samples were prepared in accordance with accepted procedures. The method quoted is only for liquid samples. It is modified to handle soils analysis.

**Instrument Calibration:**

The instrument used was a Dohrmann DC-190 high temperature combustion TOC analyzer with a Dohrmann solids boat sampler. The instrument was properly calibrated on the day of the analysis.

**Sample Preparation:**

All samples were prepared in accordance with accepted procedures.

**Instrument Calibration:**

The instrument used was a Dohrmann DC-80 TOC analyzer. The instrument was properly calibrated.

**Holding Time:**

All samples were analyzed within the required holding time.

**Blanks:**

No target analytes were detected in the method blank above the required acceptance limit.

**Spike Analyses:**

The post spike was run on the following Sample Number.

9906242-03

All analyte recoveries in the post spike were within the required acceptance limits.

**Laboratory Control Samples:**

All analyte recoveries in the laboratory control sample were within the required acceptance limits.

**Sample Duplicates:**

All sample duplicate results were within the required acceptance limits.

**Dilutions:**

None of the samples were diluted.

**Non Conformance Reports:**

There were no Nonconformance Reports associated with this batch.

**Additional Comments:**

TOC solid samples are are tested to determine if inorganic carbon such as carbonates and bicarbonates are present in the sample. If so, the sample is acidified to remove the inorganic carbon, then dried in a low temperature oven. Because the sample portion is dried before analysis, the percent moisture correction is not applied to the TOC solid result.

## TOTAL PETROLEUM HYDROCARBONS

Analytical Batch Number: 151686

Analytical Method: SW846 9071A

<u>Laboratory Number</u>	<u>Sample Description</u>
9906242-01	25SLB130203
9906242-02	25SLB130203D
QC621595	Blank
QC621596	Laboratory Control Sample
QC621599	Duplicate of 9906242-01
QC621600	Matrix Spike of 9906242-01

### Instrument Calibration:

The balance was properly calibrated.

### Holding Time:

All samples were analyzed within the required holding time.

### Blanks:

No target analytes were detected in the method blank above the required acceptance limit.

### Spike Analyses:

The matrix spike was run on the following Sample Number.

9906242-01

All analyte recoveries in the matrix spike were within the required acceptance limits.

### Laboratory Control Samples:

All analyte recoveries in the laboratory control sample were within the required acceptance limits.

### Sample Duplicates:

All sample duplicate results were within the required acceptance limits.

**Dilutions:**

None of the samples were diluted.

**Non Conformance Reports:**

There were no Nonconformance Reports associated with this batch.

The preceding narratives have been reviewed by: Jan 19. Carl Date: 05/28/19

9906242%

[illegible]

GENERAL ENGINEERING  
LABORATORIES, INC.

# INDUSTRIAL SAMPLE RECEIPT REVIEW

Client Alpha Tech  
GEL COOLER

Received by GCC Date 6-5-99  
GENERAL ENGINEERING LABORATORIES  
Meeting today's needs with a vision for tomorrow.  
GEL POLY COOLER CLIENT COOLER OTHER ☒

SAMPLE REVIEW CRITERIA	YES	NO	COMMENTS/QUALIFIERS
1. Were shipping containers received intact and sealed? Call Project Manager if No	<input checked="" type="checkbox"/>		
2. Is the shipment identified as RADIOACTIVE and/or from a DOE site or subcontainer (see list in EPI SOP S-007)? If YES, was the shipment screened following the radiochemistry survey procedure (EPI SOP S-007)?	<input checked="" type="checkbox"/>		
Were the survey results negative? Call Project Manager if No	<input checked="" type="checkbox"/>		
3. Were chain of custody documents included?	<input checked="" type="checkbox"/>		
4. Were chain of custody documents completed properly? (Ink, signed, match containers)	<input checked="" type="checkbox"/>		
5. Did all samples container arrive intact? (sealed, unbroken)? Call Project Manager if No	<input checked="" type="checkbox"/>		
6. Were all sample containers properly labeled?	<input checked="" type="checkbox"/>		
7. Were proper sample containers received?	<input checked="" type="checkbox"/>		
8. Preserved samples checked for proper pH?	<input checked="" type="checkbox"/>		
9. Were samples preserved properly? If no, list samples & tests	<input checked="" type="checkbox"/>		
10. Shipping container temperature checked?	<input checked="" type="checkbox"/>		
11. Was shipping container temperature within specifications (+/-2C)? If no, Call Project Manager	<input checked="" type="checkbox"/>		4°C
12. Were samples received within holding time? if No, Call Project Manager	<input checked="" type="checkbox"/>		
13. Were VOA vials free of headspace?	<input checked="" type="checkbox"/>		

REVIEW Justin Hand DATE 6-5-99 SA - SEALS ATTACHED NSA NO SEALS ATTACHED



Client: Katahdin Analytical  
340 County Road  
Westbrook, Maine 04092  
Contact: Ms. Andrea Colby  
Project Description: Former Naval Complex

cc: KATA00199

Report Date: June 24, 1999

Page 1 of 1

Sample ID : 25SLB130203  
Lab ID : 9906242-01  
Matrix : Soil  
Date Collected : 06/07/99  
Date Received : 06/07/99  
Priority : Routine  
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		1560	59.0	118	mg/kg	1.0	AAT	06/22/99	0950	151686	
Evaporative Loss @ 105 C		15.0	1.00	1.00	wt%	1.0	GJ	06/08/99	1455	150962	

M = Method	Method-Description
M 1	SW846 9071A
M 2	EPA 3550

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).


U indicates that the analyte was not detected at a concentration greater than the detection limit.

" indicates that a quality control analyte recovery is outside of specified acceptance criteria.

Data reported in mass/mass units is reported as 'dry weight'.

This data report has been prepared and reviewed  
in accordance with General Engineering Laboratories  
standard operating procedures. Please direct  
any questions to your Project Manager, Valerie Davis at (843) 769-7391.

Reviewed By



1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52

Client: Katahdin Analytical  
340 County Road  
Westbrook, Maine 04092  
Contact: Ms. Andrea Colby  
Project Description: Former Naval Complex

cc: KATA00199

Report Date: June 24, 1999

Page 1 of 1

Sample ID : 25SLB130203D  
Lab ID : 9906242-02  
Matrix : Soil  
Date Collected : 06/07/99  
Date Received : 06/07/99  
Priority : Routine  
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		426	56.0	112	mg/kg	1.0	AAT	06/22/99	0950	151686	1
Evaporative Loss @ 105 C		11.0	1.00	1.00	wt%	1.0	GJ	06/08/99	1455	150962	2

M = Method	Method-Description
M 1	SW846 9071A
M 2	EPA 3550

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).


U indicates that the analyte was not detected at a concentration greater than the detection limit.

\* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

Data reported in mass/mass units is reported as 'dry weight'.

This data report has been prepared and reviewed  
in accordance with General Engineering Laboratories  
standard operating procedures. Please direct  
any questions to your Project Manager, Valerie Davis at (843) 769-7391.

Reviewed By



1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52

Client: Katahdin Analytical  
340 County Road  
Westbrook, Maine 04092  
Contact: Ms. Andrea Colby  
Project Description: Former Naval Complex

25SLB150304  
↑

cc: KATA00199

Report Date: June 24, 1999

Page 1 of 1

Sample ID : 25SLB50304  
Lab ID : 9906242-03  
Matrix : Soil  
Date Collected : 06/07/99  
Date Received : 06/07/99  
Priority : Routine  
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
<b>General Chemistry</b>											
Evaporative Loss @ 105 C		10.0	1.00	1.00	wt%	1.0	GJ	06/08/99	1455	150962	1
Total Organic Carbon		771	43.1	100	mg/kg	1.0	LIB	06/23/99	1452	151981	

**M = Method**

**Method-Description**

M 1 EPA 3550  
M 2 SW846 9060 Modified

**Notes:**

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).


U indicates that the analyte was not detected at a concentration greater than the detection limit.

\* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

Data reported in mass/mass units is reported as 'dry weight'.

This data report has been prepared and reviewed  
in accordance with General Engineering Laboratories  
standard operating procedures. Please direct  
any questions to your Project Manager, Valerie Davis at (843) 769-7391.

Reviewed By





Client: Katahdin Analytical  
340 County Road  
Westbrook, Maine 04092  
Contact: Ms. Andrea Colby  
Project Description: Former Naval Complex

771  
460  
1,231

cc: KATA00199

Report Date: June 24, 1999

Page 1 of 1

Sample ID : 25SLB150304D  
Lab ID : 9906242-04  
Matrix : Soil  
Date Collected : 06/07/99  
Date Received : 06/07/99  
Priority : Routine  
Collector : Client

AVG. 615.5

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Evaporative Loss @ 105 C		10.0	1.00	1.00	wt%	1.0	GJ	06/08/99	1455	150962	1
Total Organic Carbon		460	43.1	100	mg/kg	1.0	LS	06/23/99	1558	151981	2

M = Method

Method-Description

M 1  
M 2

EPA 3550  
SW846 9060 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

\* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

Data reported in mass/mass units is reported as 'dry weight'.


This data report has been prepared and reviewed  
in accordance with General Engineering Laboratories  
standard operating procedures. Please direct  
any questions to your Project Manager, Valerie Davis at (843) 769-7391.

Reviewed By

*Jan 9 91*


1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

# GRAIN SIZE ANALYSIS



PLOT	SOURCE	SAMP.	DEPTH	CLASSIFICATION	W
•	W27R29	23			

# GRAIN SIZE ANALYSIS



PLOT	SOURCE	SAMP.	DEPTH	CLASSIFICATION	W
•	W27R29	24			

SLB12  
0203

SLB12  
0708

S. W. COLE ENGINEERING, INC.

REPORT OF GRADATION  
ASTM C-117, C-136

Project No. 99008  
Date 06/09/1999

Project MISCELLANEOUS

Client KATAHDIN ANALYTICAL

Sample No. 23, SILTY SAND, WP2792-9 25SLB120203

<u>Sieve Size</u>	<u>Percent Passing</u>	<u>PROJECT</u> <u>Specifications %</u>
1/2 "	100.0	
1/4 "	98.0	
# 4	97.0	
# 10	94.2	
# 20	91.4	
# 40	88.5	
# 60	79.6	
# 100	30.2	
# 200	11.8	

S. W. COLE ENGINEERING, INC.

REPORT OF GRADATION  
ASTM C-117, C-136

Project No. 99008  
Date 06/09/1999

Project MISCELLANEOUS

Client KATAHDIN ANALYTICAL

Sample No. 24, SILTY SAND, WP2792-10

25SLB120708

<u>Sieve Size</u>	<u>Percent Passing</u>	<u>PROJECT</u> <u>Specifications %</u>
# 4	100.0	
# 10	99.9	
# 20	99.7	
# 40	99.0	
# 60	91.0	
# 100	23.6	
# 200	3.4	

## **APPENDIX C**

### **AQUIFER CHARACTERIZATION DATA**



**SUMMARY OF SLUG TEST**  
**SOUTH CAROLINA**  
**Department of Health and Environmental Control (DHEC)**

**Site Data**

**SITE ID #:** 01782                      **COUNTY:** North Charleston, South Carolina  
**FACILITY NAME:** Former Charleston Naval Complex

**Slug Data**

See *Zone F RCRA Facility Investigation Report, E/A&H, 1996* for all data measurements.

Water Level Recovery Data was measured by a Hermit Data Logger.

Slug Test Conducted in well(s) number	613004	613004	620002	620002
Initial Rise/Drawdown in well (feet)	Rise=4.1	Fall=1.5	Rise=3.8	Fall=2.0
Radius of Well Casing (feet)	0.083	0.083	0.083	0.083
Effective Radius of Well (feet)	--	--	--	--
Static Saturated Aquifer Thickness (feet)	6	6	6.5	6.5
Length of Well Screen (feet)	9.4	9.4	9.4	9.4
Static Height of Water Column in Well (ft)	6	6	6.5	6.5

**Calculations**

The method for aquifer calculations was: Bouwer-Rice

Calculated values by well were as follows:

Slug Test Conducted in well(s) number	613004	62002
Hydraulic Conductivity (ft/day) (geometric mean)	0.32	0.41

Thickness of the aquifer used to calculate hydraulic conductivity was 5 to 6 feet.

The aquifer is water table.

The estimated seepage velocity is 6.8 feet per year based on a hydraulic conductivity of 0.7 ft/day (for Quaternary sand aquifer), a hydraulic gradient of 0.0096 (from 9/11/99 Site 25 potentiometric data), and a porosity of 36 per cent for the Quaternary sandy soil.

**SUMMARY OF SLUG TEST**  
**SOUTH CAROLINA**  
**Department of Health and Environmental Control (DHEC)**

**Site Data**

**SITE ID #:** 01782                      **COUNTY:** North Charleston, South Carolina  
**FACILITY NAME:** Former Charleston Naval Complex

**Slug Data**

See Zone F RCRA Facility Investigation Report for all data measurements.

Water Level Recovery Data was measured by a Hermit Data Logger.

**Slug Test Conducted in well(s) number**

**Initial Rise/Drawdown in well (feet)**

**Radius of Well Casing (feet)**

**Effective Radius of Well (feet)**

**Static Saturated Aquifer Thickness (feet)**

**Length of Well Screen (feet)**

**Static Height of Water Column in Well (ft)**

607001	607001	613001	613001
Rise=1.4	Fall=1.5	Rise=3.2	Fall=1.5
0.083	0.083	0.083	0.083
--	--	--	--
5	5	4	4
1.9	1.9	9.4	9.4
5	5	4	4

**Calculations**

The method for aquifer calculations was: Bouwer-Rice

Calculated values by well were as follows:

**Slug Test Conducted in well(s) number**

**Hydraulic Conductivity (ft/day) (geometric mean)**

607001	613001	Geo. Mean of 4 Wells
1.8	1.0	0.7

# EnSafe/Allen & Hoshall

## Monitoring Well NBCF613004

Project: ZONE F - Naval Base Charleston

Coordinates: 2319622.98 E, 373823.70 N

Location: Charleston, SC

Surface Elevation: 8.8 feet msl

Started at 12:30 on 10-22-98

TOC Elevation: 8.44 feet msl

Completed at 13:30 on 10-22-98

Depth to Groundwater: 7.01 feet TOC

Measured: 12/18/98

Drilling Method: 4.25" ID (7.5" OD) HSA with split spoon sampler

Groundwater Elevation: 2.43 feet msl

Drilling Company: Alliance Environmental (SC cert. # 889)

Total Well Depth: 13.5 feet bgs

Geologist: B. Blythe

Well Screen: 3.7 to 13.1 feet bgs

DEPTH IN FEET	LITHOLOGIC SAMPLE	ANALYTICAL SAMPLE	SAMPLE NO.	% RECOVERY	PTD (bgs)	GRAPHIC LOG	SOIL CLASS	GEOLOGIC DESCRIPTION	ELEV. (ft-msl)	WELL DIAGRAM
								Surface conditions: Asphalt		
5			1	20	2.4		SP SC	Poor recovery: most is mottled CaCO <sub>3</sub> sand with ROC and trace amounts of black to green mottled clay; moist; soft; some sandy shell hash seen on bottom of spoon; pepper color.	8.8 8.3	
			2	100	0			Shelby tube: Top: CaCO <sub>3</sub> gravel on top; tan; dry; Bottom: tan and brown red mottled; moist to wet; clayey sand to sandy clay; soft; medium plasticity.		
10			3	40	0		SP SC	Clayey sand; same as bottom of shelby tube above.	16 8	
			4	75	0		SC SP	Clay: gray to mottled red and brown; fat; stiff; medium plasticity; alternates to wet sands at bottom of spoon.	14 3	
15										
20										


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## FALLING HEAD SLUG TEST NBCF613004



DATA SET:  
61304FAL.AQT  
04/15/97

AQUIFER MODEL:  
Unconfined

SOLUTION METHOD:  
Bower-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 6. ft  
b = 6. ft  
H = 6. ft

PARAMETER ESTIMATES:  
K = 0.0002619 ft/min  
y0 = 0.391 ft


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## RISING HEAD SLUG TEST NBCF613004



DATA SET:  
61304RIS.AQT  
04/15/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 6. ft  
b = 6. ft  
H = 6. ft

PARAMETER ESTIMATES:  
K = 0.0001895 ft/min  
y0 = 0.384 ft

# EnSafe/Allen & Hoshall

## Monitoring Well NBCF620002

Project: ZONE F - Naval Base Charleston

Coordinates: 2320270.09 E, 373259.77 N

Location: Charleston, SC

Surface Elevation: 8.8 feet msl

Started at 14:30 on 09-03-96

TOC Elevation: 8.58 feet msl

Completed at 18:15 on 09-03-96

Depth to Groundwater: 5.60 feet TOC Measured: 12/8/96

Drilling Method: 4.25" ID (7.5" OD) HSA with split spoon sampler





Groundwater Elevation: 3.88 feet msl

Drilling Company: Alliance Environmental (SC cert. #8889)

Total Well Depth: 12.6 feet bgs

Geologist: D. Doyle

Well Screen: 2.6 to 12.0 feet bgs

DEPTH IN FEET	LITHOLOGIC SAMPLE	ANALYTICAL SAMPLE	SAMPLE NO.	% RECOVERY	PID (bpm)	GRAPHIC LOG	SOIL CLASS	GEOLOGIC DESCRIPTION	ELEV. (ft-MSL)	WELL DIAGRAM
								Surface conditions: Asphalt.		
5			1	100	2		CL	Clay: gray w/ red-brown; fine to medium sand; stiff; moist.	4.8	
			2	100			CL SC	Sand and clay: gray w/ some red-brown; fine to medium; stiff; moist.	3.8	
10								Shelby Tube (7-8' bgs): bottom: Sand: gray; fine to coarse; dense; saturated.		
			3	100	0		SW	Sand: gray; fine to coarse; dense; saturated.	2	
15									22	
20										


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## FALLING HEAD SLUG TEST NBCF620002



DATA SET:  
62002FAL.AQT  
04/16/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 6.5 ft  
b = 6.5 ft  
H = 6.5 ft

PARAMETER ESTIMATES:  
K = 0.0002918 ft/min  
y0 = 0.4329 ft


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## RISING HEAD SLUG TEST NBCF620002



DATA SET:  
62002RIS.AQT  
04/16/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 6.5 ft  
b = 6.5 ft  
H = 6.5 ft

PARAMETER ESTIMATES:  
K = 0.000283 ft/min  
y0 = 0.419 ft



# EnSafe/Allen & Hoshall

Monitoring Well NBCF607001

Project: ZONE F - Naval Base Charleston

Coordinates: 2317609.15 E, 374168.33 N

Location: Charleston, SC

Surface Elevation: 8.5 feet msl

Started at 14:05 on 11-02-96

TOC Elevation: 12.78 feet msl

Completed at 14:30 on 11-02-96

Depth to Groundwater: 8.67 feet TOC Measured: 12/18/96

Drilling Method: 4.25" ID (7.5" OD) HSA with split spoon sampler

Groundwater Elevation: 2.11 feet msl

Drilling Company: Alliance Environmental (SC cert. #889)

Total Well Depth: 10.0 feet bgs

Geologist: B. Blythe

Well Screen: 7.7 to 8.6 feet bgs

DEPTH IN FEET	LITHOLOGIC SAMPLE	ANALYTICAL SAMPLE	SAMPLE NO.	% RECOVERY	PID (ppm)	GRAPHIC LOG	SOIL CLASS	GEOLOGIC DESCRIPTION	ELEV. (ft-msl)	WELL DIAGRAM
5								<p>Surface: Asphalt.</p> <p>Note: No split spoon samples were taken at this location due to detailed lithologic sampling in NBCF60701D located approximately 25 ft east-northeast. Please refer to log of NBCF60701D for specific lithologic details.</p>		
10										
15										
20										


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## FALLING HEAD SLUG TEST NBCF607001



DATA SET:  
60701FAL.AQT  
04/11/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bower-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 5. ft  
b = 5. ft  
H = 5. ft

PARAMETER ESTIMATES:  
K = 0.001209 ft/min  
y0 = 1.457 ft


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## RISING HEAD SLUG TEST NBCF607001



DATA SET:  
60701RIS.AGT  
04/11/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 5. ft  
b = 5. ft  
H = 5. ft

PARAMETER ESTIMATES:  
K = 0.001418 ft/min  
y0 = 1.581 ft

# EnSafe/Allen & Hoshall

## Monitoring Well NBCF613001

Project: ZONE F - Naval Base Charleston

Coordinates: 238224.29 E, 374017.05 N

Location: Charleston, SC

Surface Elevation: 8.5 feet msl

Started at 1400 on 10-21-88

TOC Elevation: 8.48 feet msl

Completed at 1530 on 10-21-88

Depth to Groundwater: 8.90 feet TOC Measured: 12/18/98

Drilling Method: 4.25" ID (7.5" OD) HSA with split spoon sampler


Groundwater Elevation: 0.58 feet msl

Drilling Company: Alliance Environmental (SC cert. # 889)

Total Well Depth: 13.3 feet bgs

Geologist: B. Blythe

Well Screen: 3.3 to 12.7 feet bgs




Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## FALLING HEAD SLUG TEST NBCF613001



DATA SET:  
61301FAL.AQT  
04/15/97

AQUIFER MODEL:  
Unconfined

SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 4. ft  
b = 4. ft  
H = 4. ft

PARAMETER ESTIMATES:  
K = 0.0005749 ft/min  
y0 = 0.4125 ft


Client: CLEAN

Company: E/A&H

Location: NAVAL BASE CHARLESTON

Project: 2906-08450

## RISING HEAD SLUG TEST NBCF613001



DATA SET:  
61301RIS.AQT  
04/15/97

AQUIFER MODEL:  
Unconfined  
SOLUTION METHOD:  
Bouwer-Rice

PROJECT DATA:  
test date: January 1997

TEST DATA:  
H0 = 1. ft  
rc = 0.083 ft  
rw = 0.3125 ft  
L = 4. ft  
b = 4. ft  
H = 4. ft

PARAMETER ESTIMATES:  
K = 0.0009022 ft/min  
y0 = 0.4989 ft

## **APPENDIX D**

### **RBCA CALCULATIONS**


**Minimum Construction Worker RBSLs**

---

	Dermal	Incidental Ingestion	Inhalation	Minimum
	RBSL	RBSL	RBSL	RBSL
	mg/L	mg/L	mg/L	mg/L
Benzene	0.85	68.52	0.15	0.15
Toluene	23.98	5677.78	5.38	5.38
Ethylbenzene	6.05	2838.89	14.50	6.05
Xylene	102.33	56777.78	NA*	102.33
Naphthalene	1.63	1135.56	2.63	1.63
MTBE	25.92	141.94	293.44	25.92

\*No inhalation reference dose is available for xylenes; therefore, no inhalation RBSL can be calculated.

Prepared By: \_\_\_\_\_



Reviewed By: \_\_\_\_\_





# Construction Worker Dermal RBSLs

	Kow	MW	Kp	B	$\tau_{event}$	c	b	t*	$t_{event}$	DAevent
			cm/hr	unitless	hr/event			hr	hr/event	
Benzene	199.5262315	78.1	0.11551543	0.392637855	2.87E-01	6.32E-01	6.03E-01	6.90E-01	1	eq 3.3
Toluene	537.0317964	92.1	0.259561335	0.958068292	3.44E-01	1.13E+00	1.31E+00	1.33E+00	1	eq 3.2
Ethylbenzene	1412.537545	106.2	0.569219802	2.256154884	4.13E-01	2.36E+00	4.39E+00	1.70E+00	1	eq 3.2
Xylene*	1584.893192	106.2	0.638675123	2.531447415	4.13E-01	2.63E+00	5.31E+00	1.72E+00	1	eq 3.2
Naphthalene	1995.262315	128.2	0.605452393	2.636638957	5.48E-01	2.73E+00	5.69E+00	2.29E+00	1	eq 3.2
MTBE	15.136	88.15	0.00769788	0.027797704	3.27E-01	3.52E-01	3.20E-01	7.85E-01	1	eq 3.3

	BW	AT	EV	ED	EF	SA	CSF derm	Rfd derm	Target	RBSL	RBSL
	kg	day	events/day	hrs	days/yr	cm <sup>2</sup>	(mg/kg-day) <sup>-1</sup>	mg/kg-day	Risk or HQ	mg/L	mg/L
Benzene	70	25550	1	1	90	4500	2.99E-02	NA	1.00E-06		8.52E-01
Toluene	70	365	1	1	90	4500	NA	1.60E-01	1.0	2.40E+01	
Ethylbenzene	70	365	1	1	90	4500	NA	9.70E-02	1.0	6.05E+00	
Xylene*	70	365	1	1	90	4500	NA	1.84E+00	1.0	1.02E+02	
Naphthalene	70	365	1	1	90	4500	NA	3.20E-02	1.0	1.63E+00	
MTBE	70	365	1	1	90	4500	NA	5.00E-03	1.0	2.59E+01	

\* Kow and MW values for xylene, m-

Prepared By: \_\_\_\_\_

*Periasangari*

Reviewed By: \_\_\_\_\_

*Allan T. Jenkins*

**Construction Worker Incidental Ingestion RBSLs**

	BW	AT	IR	ED	EF	Target	CSF oral	Rfd oral	RBSL
	kg	day	L/day	yrs	days/yr	Risk or HQ			mg/L
Benzene	70	25550	0.01	1	90	1.00E-06	2.90E-02		6.85E+01
Toluene	70	365	0.01	1	90	1.0	NA	2.00E-01	5677.778
Ethylbenzene	70	365	0.01	1	90	1.0	NA	1.00E-01	2838.889
Xylene	70	365	0.01	1	90	1.0	NA	2.00E+00	56777.78
Naphthalene	70	365	0.01	1	90	1.0	NA	4.00E-02	1135.556
MTBE	70	365	0.01	1	90	1.0	NA	5.00E-03	141.9444

Prepared By: \_\_\_\_\_

*P. Asungari*

Reviewed By: \_\_\_\_\_

*Allan T. Jenkins*

Construction Worker Inhalation RBSLs

Chemical			Dair cm <sup>2</sup> /s	Dwater cm <sup>2</sup> /s	H cm <sup>3</sup> /cm <sup>3</sup>	$\theta_{cap}$ cm <sup>3</sup> /cm <sup>3</sup>	$\theta_{wcap}$ cm <sup>3</sup> /cm <sup>3</sup>	$\theta_{as}$ cm <sup>3</sup> /cm <sup>3</sup>	$\theta_{ws}$ cm <sup>3</sup> /cm <sup>3</sup>	$\theta_T$ cm <sup>3</sup> /cm <sup>3</sup>	Deff-cap cm <sup>2</sup> /s	Deff-s cm <sup>2</sup> /s
Benzene			0.093	1.10E-05	2.26E-01	0.038	0.342	0.33	0.15	0.48	1.35E-05	1.01E-02
Toluene			0.085	9.40E-06	3.01E-01	0.038	0.342	0.33	0.15	0.48	1.07E-05	9.20E-03
Ethylbenzene			0.076	8.50E-06	2.80E-01	0.038	0.342	0.33	0.15	0.48	9.85E-06	8.22E-03
Xylenes			0.072	8.50E-06	2.78E-01	0.038	0.342	0.33	0.15	0.48	9.55E-06	7.79E-03
Naphthalene			0.072	9.40E-06	2.00E-03	0.038	0.342	0.33	0.15	0.48	5.79E-04	7.83E-03
MTBE			0.102	1.05E-05	4.16E-02	0.038	0.342	0.33	0.15	0.48	3.90E-05	1.10E-02

Chemical			hcap cm	hv cm	Deff-ws cm <sup>2</sup> /s	Uair cm/sec	$\delta$ air cm	Lgw cm	W cm	VFwamb mg/m <sup>3</sup> /mg/L	TR (carc)	HI (nonc)
Benzene			5	117	3.18E-04	225	200	122	1500	1.97E-05	1.00E-06	NA
Toluene			5	117	2.54E-04	225	200	122	1500	2.09E-05	NA	1
Ethylbenzene			5	117	2.34E-04	225	200	122	1500	1.79E-05	NA	1
Xylenes			5	117	2.27E-04	225	200	122	1500	1.72E-05	NA	1
Naphthalene			5	117	5.17E-03	225	200	122	1500	2.83E-06	NA	1
MTBE			5	117	8.79E-04	225	200	122	1500	9.99E-06	NA	1

Chemical	TR (carc)	HI (nonc)	BWadult kg	AT yr	Sfi (carc) [mg/kg-day] <sup>-1</sup>	RfD (nonc) [mg/kg-day]	IR air m <sup>3</sup> /day	EF day/yr	ED yr	RBSLair mg/m <sup>3</sup>	H cm <sup>3</sup> /cm <sup>3</sup>	RBSLwater mg/L
Benzene	1.00E-06	NA	70	70	2.90E-02	NA	20	90	1	3.43E-02	2.26E-01	0.15
Toluene	NA	1	70	1	NA	1.14E-01	20	90	1	1.62E+00	3.01E-01	5.38
Ethylbenzene	NA	1	70	1	NA	2.86E-01	20	90	1	4.06E+00	2.80E-01	14.50
Xylenes	NA	1	70	1	NA	NA*	20	90	1	NA*	2.78E-01	NA*
Naphthalene	NA	1	70	1	NA	3.71E-04	20	90	1	5.27E-03	2.00E-03	2.63
MTBE	NA	1	70	1	NA	8.60E-01	20	90	1	1.22E+01	4.16E-02	293.443

\*No inhalation reference dose is available for xylenes; therefore, no RBSL can be calculated for xylene.

Prepared By:

*P. Vasungani*

Reviewed By:

*Allan K. Jenkins*

# IN-SITU SOIL RISK EVALUATION

## SOUTH CAROLINA

Department of Health and Environmental Control (DHEC)

### Site Data

SITE ID # 01782 COUNTY Columbia  
 FACILITY NAME Site 25, Building 1346  
 STREET ADDRESS Charleston Naval Complex, North Charleston, SC

### Soil Risk Evaluation Data

Figure

TPH	993 mg/kg	
Soil % SAND (Estimated)	88 %	
Soil % CLAY (Estimated)	7 %	
Worst Case Benzene	120 mg/kg	Cs
Soil Analyses Toluene	360 mg/kg	Cs
Ethylbenzene	560 mg/kg	Cs
Xylenes	2200 mg/kg	Cs
Naphthalene	217.9 mg/kg	Cs
MTBE	4.3 mg/kg	Cs
Natural Organic Carbon Content	616 mg/kg	foc
Average Annual Recharge	25 cm	Hw
Distance from highest Soil Impact to water table	46 cm	L
Bulk Density of Soil	1.6 g/cc	Bd
Wetting Front Suction	10 cm	Hf
Soil Hydraulic Conductivity	5.60E-03 cm/sec	Kf
Porosity	0.45 decimal %	Φ
Residual Water Content	0.04 decimal %	Wr

List possible human exposure pathways from surface soil.  
 Soil leaching to groundwater - utility worker in utility trench.

# IN-SITU SOIL RISK EVALUATION

# SOIL LEACHABILITY MODEL FOR MTBE

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

### SITE INFORMATION:

Site:	Site 25, Building 1346
Location:	Charleston Naval Complex, North Charleston, SC

### REFERENCES:

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

### INPUT:

COC Chemical of Concern	MTBE
Bd Soil Bulk Density (1)	g/cm3 1.6
Crsbl Risk Based Screening Level	mg/L 25.92
Cs Concentration of COC in soil	mg/kg 217.9
DAF Dilution/Attenuation Factor (2)	unitless 8
foc Organic Carbon Content in Soil (3)	mg/kg 616
H' Henry's Law Constant (4)	unitless 0.04
Hf Wetting front suction head (always negative) (5)	cm -10
Hw Average Annual Recharge (3)	cm 25
Kf Soil Hydraulic Conductivity (6)	cm/s 0.0056
Koc Soil/Water Partitioning Coefficient (2)	ml/g 12
L Depth between soil sample with greatest COC concentration to groundwater.	cm 46
Ø Porosity (7)	unitless 0.45
t1/2 Biodegradation "half life" (2)	days 183
TPH Total Petroleum Hydrocarbons, EPA Method 3550	mg/kg 993
Wr Residual Water Content (8)	volume fraction 0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning ( $C_w$ ).

Step 1 - Calculate the total organic carbon content ( $f_{cs}$ ) of the soil.

$$f_{cs} = (f_{oc} + \text{TPH}/1.724) * 1\text{E-}6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water ( $C_w$ ) directly in contact with the contaminate soil.

$$C_w = C_s * ((W_r * 1\text{g/cc} + B_d) / ((B_d * K_{oc} * f_{cs}) + W_r + ((\theta - W_r) * H'))) = \underline{176.55} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water ( $V_w$ )

Step 1 - Calculate the air filled porosity ( $f$ ) in decimal percent.

$$f = \theta - W_r = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/K_f) * (L - (H_w - H_f)) * (\ln(H_w + ((L - H_f)/(H_w - H_f)))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water ( $V_w$ ) in feet per year.

$$V_w = (L/30.48\text{cm/ft}) / (t/31,500,000\text{sec/year}) = \underline{39042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect ( $V_c$ ) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient ( $K_d$ ) (ml/g) for uncontaminated soil.

$$K_d = K_{oc} * f_{oc} * 1\text{E-}6 = \underline{0.007084} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$V_c = V_w * (1 + ((B_d * K_d)/\theta)) = \underline{38,082} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$T_c = 365 \text{ day/yr} * ((L/30.48\text{cm/ft})/V_c) = \underline{\underline{0.01}} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$C_p = 10^{(\log(C_{rsbl}) + ((T_c/2.3) * (0.693/t_{1/2})))} = \underline{\underline{25.92}} \text{ mg/l}$$

*COC concentration in soil pore water (Cp) is greater than Crsbl, therefore the SSTL must be calculated.*

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for} \quad \text{MTBE} \\ \text{in soil} \end{array} = C_p * DAF * (((Bd * Koc * fcs) + Wr + (F * H''')) / (Wr * 1\text{g/cc} + Bd)) = \underline{\underline{9.987784}} \text{ mg/kg}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

## SOUTH CAROLINA

Department of Health and Environmental Control (DHEC)

### Site Data

SITE ID # 01782  
 FACILITY NAME Site 25, Building 1346

### Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

### Data

List Constituent: MTBE  
 (BTEX, Naph.)

Bioremediation "half-life"	<u>183</u>	days	t 1/2	Table
Soil/water partitioning coefficient	<u>12</u>	ml/g	K oc	C2

### Results

			Equation Set	Step
Total Organic Carbon Content	<u>0.0012</u>	decimal %	f cs	I 1
Leachate Concentration	<u>176.552</u>	mg/l	C w	I 2
Air Filled Porosity	<u>0.41</u>	decimal %	f	II 1
Infiltration Rate Time	<u>1,218</u>	seconds	t	II 2
Velocity of Water	<u>39,042</u>	ft/year	V w	II 3
Soil/Water Distribution Coefficient	<u>0.01</u>	ml/g	K d	III 1
Contaminant Percolation Rate	<u>38,082</u>	ft/year	V c	III 2
Time to Reach Groundwater	<u>0</u>	days	T c	IV 1
Concentration reaching Groundwater	<u>25.92</u>	mg/l	C p	IV 2
Site Specific Target Level	<u>9.9878</u>	mg/kg	C sstl	V

### Conclusions

Does concentration of chemical of concern in soil exceed SSTL? YES

Risk of Human Exposure due to contaminated soil.

X YES NO

# IN-SITU SOIL RISK EVALUATION



# SOIL LEACHABILITY MODEL FOR BENZENE

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

### SITE INFORMATION:

Site: Site 25, Building 1346  
 Location: Charleston Naval Complex, North Charleston, SC

### REFERENCES:

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

### INPUT:

COC Chemical of Concern  
 Bd Soil Bulk Density (1)  
 Crsbl Risk Based Screening Level  
 Cs Concentration of COC in soil  
 DAF Dilution/Attenuation Factor (2)  
 foc Organic Carbon Content in Soil (3)  
 H' Henry's Law Constant (4)  
 Hf Wetting front suction head (always negative) (5)  
 Hw Average Annual Recharge (3)  
 Kf Soil Hydraulic Conductivity (6)  
 Koc Soil/Water Partitioning Coefficient (2)  
 L Depth between soil sample with  
 greatest COC concentration to groundwater.  
 $\Phi$  Porosity (7)  
 $t_{1/2}$  Biodegradation "half life" (2)  
 TPH Total Petroleum Hydrocarbons, EPA Method 3550  
 Wr Residual Water Content (8)

BENZENE	
g/cm <sup>3</sup>	1.6
mg/L	0.15
mg/kg	120
unitless	8
mg/kg	616
unitless	0.23
cm	-10
cm	25.00
cm/s	5.60E-03
ml/g	81
cm	46
unitless	0.45
days	16
mg/kg	993
volume fraction	0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning (Cw).

Step 1 - Calculate the total organic carbon content (fcs) of the soil.

$$fcs = (foc + TPH/1.724) * 1E-6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water (Cw) directly in contact with the contaminate soil.

$$Cw = Cs * ((Wr * 1g/cc + Bd) / ((Bd * Koc * fcs) + Wr + ((\phi - Wr) * H))) = \underline{685.3766} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water (Vw)

Step 1 - Calculate the air filled porosity (f) in decimal percent.

$$f = \phi - Wr = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/Kf) * (L - ((Hw - Hf) * (\ln((Hw + L - Hf)/(Hw - Hf))))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water (Vw) in feet per year.

$$Vw = (L/30.48cm/ft) / (t/31,500,000sec/year) = \underline{39,042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect (Vc) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient (Kd) (ml/g) for uncontaminated soil.

$$Kd = Koc * foc * 1E-6 = \underline{0.049896} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$Vc = Vw / (1 + ((Bd * Kd) / \phi)) = \underline{33,159} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$Tc = 365 \text{ day/yr} * ((L/30.48cm/ft) / Vc) = \underline{0.02} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$Cp = 10^{(\log(Crsbl) + ((Tc/2.3) * (0.693/t^{1/2})))} = \underline{0.1501} \text{ mg/l}$$

COC concentration in soil pore water (Cw) is less than concentration necessary to protect groundwater (Cp). Not necessary to calculate SSTL

11/18/1999

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for BENZENE} \\ \text{in soil} \end{array} = C_p * DAF * ((Bd * Koc * fcs) + Wr + (F * 'H''')) / (Wr * 1g/cc + Bd) = \underline{\underline{0.210255 \text{ mg/kg}}}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

## SOUTH CAROLINA

Department of Health and Environmental Control (DHEC)

### Site Data

SITE ID # 01782

FACILITY NAME Site 25, Building 1346

### Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

### Data

List Constituent: BENZENE

(BTEX, Napth.)

Table

Bioremediation "half-life"	<u>16</u>	days	t 1/2	C2
Soil/water partitioning coefficient	<u>81</u>	ml/g	K oc	C2

### Results

			Equation Set	Step
Total Organic Carbon Content	<u>0.0012</u>	decimal %	f cs	I 1
Leachate Concentration	<u>685.377</u>	mg/l	C w	I 2
Air Filled Porosity	<u>0.41</u>	decimal %	f	II 1
Infiltration Rate Time	<u>1,218</u>	seconds	t	II 2
Velocity of Water	<u>39,042</u>	ft/year	V w	II 3
Soil/Water Distribution Coefficient	<u>0.0499</u>	ml/g	K d	III 1
Contaminant Percolation Rate	<u>33,159</u>	ft/year	V c	III 2
Time to Reach Groundwater	<u>0.02</u>	days	T c	IV 1
Concentration reaching Groundwater	<u>0.1501</u>	mg/l	C p	IV 2
Site Specific Target Level	<u>0.2103</u>	mg/kg	C sstl	V

### Conclusions

Does concentration of chemical of concern in soil exceed SSTL?

YES

Risk of Human Exposure due to contaminated soil.

X YES

NO

# IN-SITU SOIL RISK EVALUATION

# SOIL LEACHABILITY MODEL FOR NAPHTHALENE

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

### SITE INFORMATION:

Site: Site 25, Building 1346  
 Location: Charleston Naval Complex, North Charleston, SC

### REFERENCES:

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

### INPUT:

COC Chemical of Concern  
 Bd Soil Bulk Density (1)  
 Crsbl Risk Based Screening Level  
 Cs Concentration of COC in soil  
 DAF Dilution/Attenuation Factor (2)  
 foc Organic Carbon Content in Soil (3)  
 H' Henry's Law Constant (4)  
 Hf Wetting front suction head (always negative) (5)  
 Hw Average Annual Recharge (3)  
 Kf Soil Hydraulic Conductivity (6)  
 Koc Soil/Water Partioning Coefficient (2)  
 L Depth between soil sample with  
 greatest COC concentration to groundwater.  
 Ø Porosity (7)  
 t1/2 Biodegradation "half life" (2)  
 TPH Total Petroleum Hydrocarbons, EPA Method 3550  
 Wr Residual Water Content (8)

NAPHTHALENE	
g/cm3	1.6
mg/L	1.63
mg/kg	217.9
unitless	8
mg/kg	616
unitless	0.002
cm	-10
cm	25
cm/s	0.0056
ml/g	1543
cm	46
unitless	0.45
days	48
mg/kg	993
volume fraction	0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning (Cw).

Step 1 - Calculate the total organic carbon content (fcs) of the soil.

$$fcs = (foc + TPH/1.724) * 1E-6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water (Cw) directly in contact with the contaminate soil.

$$Cw = Cs * ((Wr * 1g/cc + Bd) / ((Bd * Koc * fcs) + Wr + ((\theta - Wr) * H'))) = \underline{4.67} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water (Vw)

Step 1 - Calculate the air filled porosity (f) in decimal percent.

$$f = \theta - Wr = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/Kf) * (L - (Hw - Hf)) * (\ln(Hw + ((L - Hf)/(Hw - Hf)))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water (Vw) in feet per year.

$$Vw = (L/30.48cm/ft) / (t/31,500,000sec/year) = \underline{39042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect (Vc) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient (Kd) (ml/g) for uncontaminated soil.

$$Kd = Koc * foc * 1E-6 = \underline{0.950488} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$Vc = Vw * (1 + ((Bd * Kd)/\theta)) = \underline{8,915} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$T_c = 365 \text{ day/yr} * ((L/30.48 \text{ cm/ft})/V_c) = \underline{0.06} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$C_p = 10^{(\log(C_{rsbl}) + ((T_c/2.3) * (0.693/t_{1/2})))} = \underline{1.63} \text{ mg/l}$$

*COC concentration in soil pore water (Cp) is greater than Crsbl, therefore the SSTL must be calculated.*

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for IAPHTHALENE} \\ \text{in soil} \end{array} = C_p * DAF * (((Bd * K_{oc} * f_{cs}) + W_r + (F * H''')) / (W_r * 1 \text{ g/cc} + Bd)) = \underline{\underline{23.744418}} \text{ mg/kg}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

SOUTH CAROLINA  
Department of Health and Environmental Control (DHEC)

## Site Data

SITE ID # 01782  
FACILITY NAME Site 25, Building 1346

## Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

## Data

List Constituent: NAPHTHALENE

(BTEX, Naph.)

					Table
Bioremediation "half-life"	<u>48</u>	days	t 1/2		C2
Soil/water partitioning coefficient	<u>1543</u>	ml/g	K oc		C2

## Results

				Equation Set	Step
Total Organic Carbon Content	<u>0.0012</u>	decimal %	f cs	I	1
Leachate Concentration	<u>4.674</u>	mg/l	C w	I	2
Air Filled Porosity	<u>0.41</u>	decimal %	f	II	1
Infiltration Rate Time	<u>1,218</u>	seconds	t	II	2
Velocity of Water	<u>39,042</u>	ft/year	V w	II	3
Soil/Water Distribution Coefficient	<u>0.95</u>	ml/g	K d	III	1
Contaminant Percolation Rate	<u>8,915</u>	ft/year	V c	III	2
Time to Reach Groundwater	<u>0</u>	days	T c	IV	1
Concentration reaching Groundwater	<u>1.63</u>	mg/l	C p	IV	2
Site Specific Target Level	<u>24</u>	mg/kg	C sstl	V	

## Conclusions

Does concentration of chemical of concern in soil exceed SSTL? YES

Risk of Human Exposure due to contaminated soil.

X YES                      NO

# IN-SITU SOIL RISK EVALUATION



# SOIL LEACHABILITY MODEL FOR TOLUENE

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

**SITE INFORMATION:**

Site: Site 25, Building 1346  
 Location: Charleston Naval Complex, North Charleston, SC

**REFERENCES:**

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

**INPUT:**

COC Chemical of Concern  
 Bd Soil Bulk Density (1)  
 Crsbl Risk Based Screening Level  
 Cs Concentration of COC in soil  
 DAF Dilution/Attenuation Factor (2)  
 foc Organic Carbon Content in Soil (3)  
 H' Henry's Law Constant (4)  
 Hf Wetting front suction head (always negative) (5)  
 Hw Average Annual Recharge (3)  
 Kf Soil Hydraulic Conductivity (6)  
 Koc Soil/Water Partitioning Coefficient (2)  
 L Depth between soil sample with  
 greatest COC concentration to groundwater.  
 Ø Porosity (7)  
 t1/2 Biodegradation "half life" (2)  
 TPH Total Petroleum Hydrocarbons, EPA Method 3550  
 Wr Residual Water Content (8)

TOLUENE	
g/cm3	1.6
mg/L	5.38
mg/kg	360
unitless	8
mg/kg	616
unitless	0.30
cm	-10
cm	25
cm/s	0.0056
ml/g	133
cm	46
unitless	0.45
days	22
mg/kg	993
volume fraction	0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning (Cw).

Step 1 - Calculate the total organic carbon content (fcs) of the soil.

$$fcs = (foc + TPH/1.724) * 1E-6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water (Cw) directly in contact with the contaminate soil.

$$Cw = Cs * ((Wr * 1g/cc + Bd) / ((Bd * Koc * fcs) + Wr + ((\theta - Wr) * H'))) = \underline{55} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water (Vw)

Step 1 - Calculate the air filled porosity (f) in decimal percent.

$$f = \theta - Wr = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/Kf) * (L - (Hw - Hf)) * (\ln(Hw + ((L - Hf)/(Hw - Hf)))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water (Vw) in feet per year.

$$Vw = (L/30.48cm/ft) / (t/31,500,000sec/year) = \underline{39,042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect (Vc) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient (Kd) (ml/g) for uncontaminated soil.

$$Kd = Koc * foc * 1E-6 = \underline{0.081928} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$Vc = Vw * (1 + ((Bd * Kd) / \theta)) = \underline{30,234} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$T_c = 365 \text{ day/yr} * ((L/30.48\text{cm/ft})/V_c) = \underline{0.02} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$C_p = 10^{(\log(C_{rsbl}) + ((T_c/2.3) * (0.693/t_{1/2})))} = \underline{5.3831} \text{ mg/l}$$

*COC concentration in soil pore water (Cp) is greater than Crsbl, therefore the SSTL must be calculated.*

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for TOLUENE} \\ \text{in soil} \end{array} = C_p * DAF * (((Bd * K_{oc} * f_{cs}) + W_r + (F * H''')) / (W_r * 1\text{g/cc} + Bd)) = \underline{\underline{10.951686 \text{ mg/kg}}}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

## SOUTH CAROLINA

Department of Health and Environmental Control (DHEC)

### Site Data

SITE ID # 01782

FACILITY NAME Site 25, Building 1346

### Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

### Data

List Constituent: TOLUENE

(BTEX, Naph.)

Bioremediation "half-life"

22

days

t 1/2

Table

C2

Soil/water partitioning coefficient

133

ml/g

K oc

C2

### Results

			Equation Set	Step
Total Organic Carbon Content	<u>0.0012</u> decimal %	f cs	I	1
Leachate Concentration	<u>55.243</u> mg/l	C w	I	2
Air Filled Porosity	<u>0.41</u> decimal %	f	II	1
Infiltration Rate Time	<u>1,218</u> seconds	t	II	2
Velocity of Water	<u>39,042</u> ft/year	V w	II	3
Soil/Water Distribution Coefficient	<u>0.0819</u> ml/g	K d	III	1
Contaminant Percolation Rate	<u>30,234</u> ft/year	V c	III	2
Time to Reach Groundwater	<u>0</u> days	T c	IV	1
Concentration reaching Groundwater	<u>5</u> mg/l	Cp	IV	2
Site Specific Target Level	<u>11</u> mg/kg	C sstl	V	

### Conclusions

Does concentration of chemical of concern in soil exceed SSTL?

YES

Risk of Human Exposure due to contaminated soil.

X

YES

NO

# IN-SITU SOIL RISK EVALUATION

# SOIL LEACHABILITY MODEL FOR ETHYLBENZENE

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

### SITE INFORMATION:

Site: **Site 25, Building 1346**  
 Location: **Charleston Naval Complex, North Charleston, SC**

### REFERENCES:

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

### INPUT:

COC Chemical of Concern

Bd Soil Bulk Density (1)

Crsbl Risk Based Screening Level

Cs Concentration of COC in soil

DAF Dilution/Attenuation Factor (2)

foc Organic Carbon Content in Soil (3)

H' Henry's Law Constant (4)

Hf Wetting front suction head (always negative) (5)

Hw Average Annual Recharge (3)

Kf Soil Hydraulic Conductivity (6)

Koc Soil/Water Partitioning Coefficient (2)

L Depth between soil sample with  
greatest COC concentration to groundwater.

Ø Porosity (7)

t1/2 Biodegradation "half life" (2)

TPH Total Petroleum Hydrocarbons, EPA Method 3550

Wr Residual Water Content (8)

### ETHYLBENZENE

g/cm <sup>3</sup>	1.6
mg/L	6.05
mg/kg	560
unitless	8
mg/kg	616
unitless	0.28
cm	-10
cm	25
cm/s	0.0056
ml/g	176
cm	46
unitless	0.45
days	10
mg/kg	993
volume fraction	0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning ( $C_w$ ).

Step 1 - Calculate the total organic carbon content ( $f_{cs}$ ) of the soil.

$$f_{cs} = (f_{oc} + TPH/1.724) * 1E-6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water ( $C_w$ ) directly in contact with the contaminate soil.

$$C_w = C_s * ((W_r * 1g/cc + B_d) / ((B_d * K_{oc} * f_{cs}) + W_r + ((\phi - W_r) * H'))) = \underline{73.0737682} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water ( $V_w$ )

Step 1 - Calculate the air filled porosity ( $f$ ) in decimal percent.

$$f = \phi - W_r = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/K_f) * (L - (H_w - H_f)) * (\ln(H_w + ((L - H_f)/(H_w - H_f)))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water ( $V_w$ ) in feet per year.

$$V_w = (L/30.48cm/ft) / (t/31,500,000sec/year) = \underline{39,042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect ( $V_c$ ) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient ( $K_d$ ) (ml/g) for uncontaminated soil.

$$K_d = K_{oc} * f_{oc} * 1E-6 = \underline{0.108416} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$V_c = V_w * (1 + ((B_d * K_d) / \phi)) = \underline{28,179} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$T_c = 365 \text{ day/yr} * ((L/30.48 \text{ cm/ft})/V_c) = \underline{0.02} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$C_p = 10^{(\log(C_{rsbl}) + ((T_c/2.3) * (0.693/t_{1/2})))} = \underline{6.06} \text{ mg/l}$$

*COC concentration in soil pore water (Cp) is greater than Crsbl, therefore the SSTL must be calculated.*

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for THYLBENZENE} \\ \text{in soil} \end{array} = C_p * DAF * (((Bd * Koc * fcs) + Wr + (F * 'H''')) / (Wr * 1 \text{ g/cc} + Bd)) = \underline{\underline{14.494292 \text{ mg/kg}}}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

SOUTH CAROLINA  
Department of Health and Environmental Control (DHEC)

## Site Data

SITE ID # 01782  
FACILITY NAME Site 25, Building 1346

## Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

## Data

List Constituent: ETHYLBENZENE

(BTEX, Naphth.)

Table

Bioremediation "half-life"	<u>10</u> days	t 1/2	C2
Soil/water partitioning coefficient	<u>176</u> ml/g	K oc	C2

## Results

			Equation Set	Step
Total Organic Carbon Content	<u>0.0012</u> decimal %	f cs	I	1
Leachate Concentration	<u>7.31E+01</u> mg/l	C w	I	2
Air Filled Porosity	<u>0.41</u> decimal %	f	II	1
Infiltration Rate Time	<u>1,218</u> seconds	t	II	2
Velocity of Water	<u>39,042</u> ft/year	V w	II	3
Soil/Water Distribution Coefficient	<u>0.1084</u> ml/g	K d	III	1
Contaminant Percolation Rate	<u>28,179</u> ft/year	V c	III	2
Time to Reach Groundwater	<u>0</u> days	T c	IV	1
Concentration reaching Groundwater	<u>6</u> mg/l	C p	IV	2
Site Specific Target Level	<u>14</u> mg/kg	C sstl	V	

## Conclusions

Does concentration of chemical of concern in soil exceed SSTL?

YES

Risk of Human Exposure due to contaminated soil.

X

YES

NO

IN-SITU SOIL RISK EVALUATION



# SOIL LEACHABILITY MODEL FOR XYLENES

## RISK-BASED CORRECTIVE ACTION FOR PETROLEUM RELEASES

**SITE INFORMATION:**

<b>Site:</b>	Site 25, Building 1346
<b>Location:</b>	Charleston Naval Complex, North Charleston, SC

**REFERENCES:**

- (1) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 1.
- (2) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 2.
- (3) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Input Parameters.
- (4) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Table 1.
- (5) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 2.
- (6) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 3.
- (7) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 4.
- (8) SCDHEC, RBCA For Petroleum Releases, June 1995, Appendix B, Figure 5.

**INPUT:**

COC Chemical of Concern  
 Bd Soil Bulk Density (1)  
 Crsbl Risk Based Screening Level  
 Cs Concentration of COC in soil  
 DAF Dilution/Attenuation Factor (2)  
 foc Organic Carbon Content in Soil (3)  
 H' Henry's Law Constant (4)  
 Hf Wetting front suction head (always negative) (5)  
 Hw Average Annual Recharge (3)  
 Kf Soil Hydraulic Conductivity (6)  
 Koc Soil/Water Partitioning Coefficient (2)  
 L Depth between soil sample with  
 greatest COC concentration to groundwater.  
 Ø Porosity (7)  
 t1/2 Biodegradation "half life" (2)  
 TPH Total Petroleum Hydrocarbons, EPA Method 3550  
 Wr Residual Water Content (8)

XYLENES	
g/cm3	1.6
mg/L	102.33
mg/kg	2200
unitless	8
mg/kg	616
unitless	0.28
cm	-10
cm	25
cm/s	0.0056
ml/g	639
cm	46
unitless	0.45
days	28
mg/kg	993
volume fraction	0.04

**CALCULATIONS:**

Equation Set I - Determine soil pore water concentration resulting from physical partitioning (Cw).

Step 1 - Calculate the total organic carbon content (fcs) of the soil.

$$fcs = (foc + TPH/1.724) * 1E-6 = \underline{0.0012} \text{ decimal \%}$$

Step 2 - Calculate the concentration of COC in soil pore water (Cw) directly in contact with the contaminate soil.

$$Cw = Cs * ((Wr * 1g/cc + Bd) / ((Bd * Koc * fcs) + Wr + ((\theta - Wr) * H))) = \underline{103} \text{ mg/l}$$

Equation Set II - Determine the velocity of the soil pore water (Vw)

Step 1 - Calculate the air filled porosity (f) in decimal percent.

$$f = \theta - Wr = \underline{0.41} \text{ decimal \%}$$

Step 2 - Determine the time for water to percolate through the vadose zone soil (from depth of worst case soil sample to the water table at site).

$$t = (f/Kf) * (L - (Hw - Hf)) * (\ln(Hw + ((L - Hf)/(Hw - Hf)))) = \underline{1,218} \text{ seconds}$$

Step 3 - Determine the velocity of the water (Vw) in feet per year.

$$Vw = (L/30.48cm/ft) / (t/31,500,000sec/year) = \underline{39,042} \text{ ft/year}$$

Equation Set III - Determine the organic retardation effect (Vc) of the contaminant.

Step 1 - Calculate the soil/water distribution coefficient (Kd) (ml/g) for uncontaminated soil.

$$Kd = Koc * foc * 1E-6 = \underline{0.393624} \text{ ml/g}$$

Step 2 - Calculate the retardation effect of natural soil organic matter on COC migration.

$$Vc = Vw * (1 + ((Bd * Kd) / \theta)) = \underline{16,270} \text{ ft/year}$$

Equation Set IV - Determine biodegradation rates and provide final COC concentration (Cf) at depth of concern.

Step 1 - Calculate the time (Tc) in days required for the COC to reach groundwater.

$$T_c = 365 \text{ day/yr} * ((L/30.48\text{cm/ft})/V_c) = \underline{\underline{0.03}} \text{ days}$$

Step 2 - Calculate estimated concentration of COC in the soil pore water (Cp) necessary to protect groundwater.

$$C_p = 10^{(\log(C_{rsbl}) + ((T_c/2.3) * (0.693/t_{1/2})))} = \underline{\underline{102.42}} \text{ mg/l}$$

*COC concentration in soil pore water (Cp) is greater than Crsbl, therefore the SSTL must be calculated.*

Equation Set V - Calculate the Site Specific Target Level (SSTL) for the COC in soil.

$$\begin{array}{l} \text{Csstl for XYLENES} \\ \text{in soil} \end{array} = C_p * DAF * (((Bd * Koc * f_{cs}) + W_r + (F * H''')) / (W_r * 1\text{g/cc} + Bd)) = \underline{\underline{685.770015}} \text{ mg/kg}$$

PREPARED BY: \_\_\_\_\_

Date

CHECKED BY: \_\_\_\_\_

Date

# IN-SITU SOIL RISK EVALUATION

SOUTH CAROLINA  
Department of Health and Environmental Control (DHEC)

## Site Data

SITE ID # 01782

FACILITY NAME Site 25, Building 1346

## Instructions

Provide results, separately, for each constituent in the worst case soil analysis.

## Data

List Constituent: XYLENES

(BTEX, Napth.)

Bioremediation "half-life"

28

days

t 1/2

Table

C2

Soil/water partitioning coefficient

639

ml/g

K oc

C2

## Results

			Equation	Step
			Set	
Total Organic Carbon Content	<u>0.0012</u> decimal %	f cs	I	1
Leachate Concentration	<u>102.5741</u> mg/l	C w	I	2
Air Filled Porosity	<u>0.41</u> decimal %	f	II	1
Infiltration Rate Time	<u>1,218</u> seconds	t	II	2
Velocity of Water	<u>39,042</u> ft/year	V w	II	3
Soil/Water Distribution Coefficient	<u>0.3936</u> ml/g	K d	III	1
Contaminant Percolation Rate	<u>16,270</u> ft/year	V c	III	2
Time to Reach Groundwater	<u>0</u> days	T c	IV	1
Concentration reaching Groundwater	<u>102</u> mg/l	C p	IV	2
Site Specific Target Level	<u>686</u> mg/kg	C sstl	V	

## Conclusions

Does concentration of chemical of concern in soil exceed SSTL?

YES

Risk of Human Exposure due to contaminated soil.

X

YES

NO

IN-SITU SOIL RISK EVALUATION

**Site Specific Target Level Calculations for Soil: Construction Worker Inhalation of Volatiles from Soil**

Parameter Descriptions:	Units	Parameter Descriptions:	Units
ABS = Absorption Fraction		ET = Exposure Time	hours/day
AF = Adherence Factor of Soil to Skin	mg/cm <sup>2</sup>	FI = Fraction Ingested	
AT = Averaging Time	days	HQ = Hazard Quotient	
BW = Body Weight	kg	IR = Inhalation or Ingestion Rate	m <sup>3</sup> /hour or mg/day
CF = Conversion Factor		RBSL = Risk Based Screening Level	
CSF <sub>D</sub> = Dermal Cancer Slope Factor	(mg/kg-day) <sup>-1</sup>	RfD <sub>D</sub> = Dermal Reference Dose	mg/kg-day
CSF <sub>I</sub> = Inhalation Cancer Slope Factor	(mg/kg-day) <sup>-1</sup>	RfD <sub>I</sub> = Inhalation Reference Dose	mg/kg-day
CSF <sub>O</sub> = Oral Cancer Slope Factor	(mg/kg-day) <sup>-1</sup>	RfD <sub>O</sub> = Oral Reference Dose	mg/kg-day
ED = Exposure Duration	year	SA = Skin Surface Area Available for Contact	cm <sup>2</sup>
EF = Exposure Frequency	days/year	VF <sub>SS</sub> = Volatilization Factor	
ELCR = Excess Lifetime Cancer Risk			

**Construction Worker Inhalation of Vapor from Soil (Outdoor)**

Constituent	IR m <sup>3</sup> /hour	ET hours/day	EF days/year	ED years	AT days	BW kg
Benzene	0.83	8	90	1	25550	70
Toluene	0.83	8	90	1	87.6	70
Ethylbenzene	0.83	8	90	1	87.6	70
Xylenes	0.83	8	90	1	87.6	70
Napthalene	0.83	8	90	1	87.6	70

Constituent	CSF <sub>I</sub> (mg/kg-day) <sup>-1</sup>	RfD <sub>I</sub> mg/kg-day	Target ELCR	Target HQ	RBSL <sub>AIR</sub> mg/m <sup>3</sup>	VF <sub>SS</sub> mg/m <sup>3</sup> / mg/kg	RBSL <sub>SOIL</sub> mg/kg
Benzene	0.029	NA	1.0E-06	NA	0.102787	1.31E-05	7,853
Toluene	NA	0.11	NA	1.0E+00	1.1242	1.31E-05	85,887
Ethylbenzene	NA	0.29	NA	1.0E+00	2.9638	1.31E-05	226,430
Xylenes	NA	NA	NA	1.0E+00	NA	1.31E-05	NA
Napthalene	NA	0.004	NA	1.0E+00	0.04088	1.31E-05	3,123

Source: ASTM (American Society for Testing and Materials), 1997. *Standard Guide for Risk-Based Corrective Action* applied at Petroleum Release Sites: E 1739 - 95E1, Annual Book of ASTM Standards, West Conshohocken, PA

## HYDROCARBON CONSTITUENT CONCENTRATIONS IN WATER BASED ON RAOULT'S LAW

### Parameter Descriptions:

$C_w$ = Aqueous Solubility of Organic Constituents Dissolved from Product	mg/L
$C_f$ = Concentration of the Constituent in the Fuel	mg/L
$K_{FW}$ = Fuel/Water Partition Coefficient	
$P_f$ = Density of the Product	g/mL
$MW_f$ = Molecular Weight of the Product	g/mol
$C_{SAT}$ = Aqueous Solubility of the Constituent	mol/L
$MW_c$ = Molecular Weight of the Constituent	g/mol
$K_{FW} = (10^3(mL/L) P_f)/(MW_f * C_{SAT}/(MW_c * 1000))$	
$C_w = C_f/K_{FW}$	mg/L

Source: "Solubility, Sorption, and Transport of Hydrophobic Organic Chemicals in Complex Mixtures," EPA Environmental Research Brief, EPA/600/M-91/009, Robert S. Kerr Environmental Research Laboratory, ADA, Oklahoma.

### Key Assumptions:

$MW_f$  : Molecular Weight of Weathered Product, Source: "A Practical Approach to the Design, Operation, and Monitoring of In-Situ Soil Venting Systems", Shell Development/Shell Oil Company, Houston, Texas.

$P_f$  : Density of the Product, Source: Conoco Material Safety Data Sheet for unleaded gasoline.

### Concentration of Hydrocarbon Constituents in Water Based on Molar Solubility

Constituent	$MW_f$ g/mol	$C_{SAT}$ mg/L	$MW_c$ g/mol	$P_f$ g/mL	$K_{FW}$	$C_f$ mg/L	$C_w$ mg/L
Benzene	111.00	1,750	78	0.77	309.19	18,480.0	59.77
Toluene	111.00	535	92	0.77	1192.89	115,500.0	96.82
Ethylbenzene	111.00	152	106	0.77	4837.60	15,400.0	3.18
Xylene	111.00	198	106	0.77	3713.71	92,400.0	24.88
MTBE	111.00	48,000	88.15	0.77	12.74	67,375.0	5288.71
Naphthalene	111.00	33	128.2	0.77	26948.95	5,852.0	0.22

SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA

DOMENICO'S DILUTION/ATTENUATION EQUATION FOR GROUNDWATER TRANSPORT

Predicted 10-year Migration of Constituents in Groundwater

Parameter Descriptions:

POE = Point of Exposure

SSTL = Site-Specific Target Level

SSTL<sub>SOURCE</sub> = Hydrocarbon Concentration in Plume Source Area protective of RBSLs at POE

SSTL<sub>COMP</sub> = Hydrocarbon Concentration at Compliance Point protective of RBSLs at POE

X<sub>POE</sub> = x = Distance from Plume Source to POE (along Centerline)

X<sub>COMP</sub> = x = Distance from POE to Compliance Point (along Centerline)

Y = Source Width (Perpendicular to Flow Direction)

Z = Source Depth (Perpendicular to Flow Direction in Vertical Plane)

K<sub>S</sub> = Saturated Hydraulic Conductivity

i = Groundwater Gradient

θ = Porosity in Saturated Zone

Units

mg/L

mg/L

mg/L

m

m

m

m

m/sec

cm/cm

cm<sup>3</sup>/cm<sup>3</sup>

Parameter Descriptions:

ρ<sub>S</sub> = Soil Bulk Density

f<sub>OC</sub> = Fraction Organic Carbon in Soil

α<sub>X</sub> = Longitudinal Dispersivity = x/10

α<sub>Y</sub> = Transverse Dispersivity = α<sub>X</sub>/3

α<sub>Z</sub> = Vertical Dispersivity = α<sub>X</sub>/20

k<sub>OC</sub> = Organic Carbon Partition Coefficient

k<sub>D</sub> = Soil-Water Sorption Coefficient

V = Pore Water Velocity

R<sub>C</sub> = Constituent Retardation Factor

V/R<sub>C</sub> = Maximum Transport Rate of Dissolved Constituent = (K<sub>s</sub>i)/(θR<sub>C</sub>)

RBSL = Risk-Based Screening Level in Water Provided by SCDHEC (1998)

Units

g/cm<sup>3</sup>

g-C/g-soil

m

m

m

cm<sup>3</sup>-H<sub>2</sub>O/g-C

cm<sup>3</sup>-H<sub>2</sub>O/g-soil

m/sec

m/sec

mg/L

Dilution & Attenuation without Biological Decay

Constituent	X <sub>POE</sub> ft	X <sub>POE</sub> m	Y m	Z m	t sec	K <sub>S</sub> m/sec	i m/m	θ m <sup>3</sup> /cm <sup>3</sup>	ρ <sub>S</sub> g/cm <sup>3</sup>	α <sub>X</sub> m	α <sub>Y</sub> m	α <sub>Z</sub> m	f <sub>OC</sub> g-C/g-soil	k <sub>OC</sub> cm <sup>3</sup> -H <sub>2</sub> O/g-C	k <sub>D</sub> cm <sup>3</sup> -H <sub>2</sub> O/g-soil	V m/sec	R <sub>C</sub>	C <sub>POE</sub> /C <sub>SOURCE</sub>
Benzene	202	61.5703	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	6.16	2.05	0.31	6.16E-04	81	0.049896	6.59E-08	1.240	8.355E-05
Toluene	108	32.9188	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	3.29	1.10	0.16	6.16E-04	133	0.081928	6.59E-08	1.394	9.799E-03
Ethylbenzene	56	17.069	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	1.71	0.57	0.09	6.16E-04	176	0.108416	6.59E-08	1.521	2.134E-01
Xylenes	26.1	7.95538	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	0.80	0.27	0.04	6.16E-04	639	0.393624	6.59E-08	2.892	4.047E-01
MTBE	287	87.4787	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	8.75	2.92	0.44	6.16E-04	12	0.007392	6.59E-08	1.036	7.519E-06
Naphthalene	25.5	7.77249	15	2	3.15E+08	2.47E-06	0.0096	0.36	1.73	0.78	0.26	0.04	6.16E-04	1543	0.950488	6.59E-08	5.568	4.617E-02

Source: South Carolina Department of Health and Environmental Control (SCDHEC) 1998. *Risk-Based Corrective Action for Petroleum Releases*, Bureau of Underground Storage Tank Management.

DOMENICO DILUTION/ATTENUATION MODEL WITHOUT BIOLOGICAL DECAY

$$\frac{C_X}{C_{SOURCE}} = \frac{1}{2} \operatorname{erfc} \left[ \frac{\left( x - \frac{vt}{R_c} \right)}{2 \sqrt{\alpha_X \frac{vt}{R_c}}} \right] \times \operatorname{erf} \left[ \frac{Y}{4 \sqrt{\alpha_Y x}} \right] \times \operatorname{erf} \left[ \frac{Z}{2 \sqrt{\alpha_Z x}} \right]$$

Constituent	C <sub>SOURCE</sub> mg/L	C <sub>X</sub> mg/L	RBSL mg/L
Benzene	59.77	0.005	0.005
Toluene	96.82	0.949	1.000
Ethylbenzene	3.18	0.679	0.700
Xylenes	24.88	10.069	10.000
MTBE	5288.71	0.040	0.040
Naphthalene	0.217	0.010	0.010

Prepared By:

*Gregory F. Sizco*

Reviewed By:

*Albert J. Jenkins*

SITE 25, BUILDING 1346  
ZONE F, CHARLESTON NAVAL COMPLEX  
NORTH CHARLESTON, SOUTH CAROLINA

DOMENICO'S DILUTION/ATTENUATION EQUATION FOR GROUNDWATER TRANSPORT

Predicted 20-year Migration of Constituents in Groundwater

Parameter Descriptions:	Units	Parameter Descriptions:	Units
POE = Point of Exposure		$\rho_s$ = Soil Bulk Density	g/cm <sup>3</sup>
SSTL = Site-Specific Target Level	mg/L	$f_{OC}$ = Fraction Organic Carbon in Soil	g-C/g-soil
SSTL <sub>SOURCE</sub> = Hydrocarbon Concentration in Plume Source Area protective of RBSLs at POE	mg/L	$\alpha_x$ = Longitudinal Dispersivity = $x/10$	m
SSTL <sub>COMP</sub> = Hydrocarbon Concentration at Compliance Point protective of RBSLs at POE	mg/L	$\alpha_y$ = Transverse Dispersivity = $\alpha_x/3$	m
X <sub>POE</sub> = x = Distance from Plume Source to POE (along Centerline)	m	$\alpha_z$ = Vertical Dispersivity = $\alpha_x/20$	m
X <sub>COMP</sub> = x = Distance from POE to Compliance Point (along Centerline)	m	$k_{OC}$ = Organic Carbon Partition Coefficient	cm <sup>3</sup> -H <sub>2</sub> O/g-C
Y = Source Width (Perpendicular to Flow Direction)	m	$k_D$ = Soil-Water Sorption Coefficient	cm <sup>3</sup> -H <sub>2</sub> O/g-soil
Z = Source Depth (Perpendicular to Flow Direction in Vertical Plane)	m	V = Pore Water Velocity	m/sec
K <sub>s</sub> = Saturated Hydraulic Conductivity	m/sec	R <sub>C</sub> = Constituent Retardation Factor	
i = Groundwater Gradient	cm/cm	V/R <sub>C</sub> = Maximum Transport Rate of Dissolved Constituent = (K <sub>s</sub> i)/(θR <sub>C</sub> )	m/sec
θ = Porosity in Saturated Zone	cm <sup>3</sup> /cm <sup>3</sup>	RBSL = Risk-Based Screening Level in Water Provided by SCDHEC (1998)	mg/L

Dilution & Attenuation without Biological Decay

Constituent	X <sub>POE</sub> ft	X <sub>POE</sub> m	Y m	Z m	t sec	K <sub>s</sub> m/sec	i m/m	θ m <sup>3</sup> /cm <sup>3</sup>	ρ <sub>s</sub> g/cm <sup>3</sup>	α <sub>x</sub> m	α <sub>y</sub> m	α <sub>z</sub> m	f <sub>OC</sub> g-C/g-soil	k <sub>OC</sub> cm <sup>3</sup> -H <sub>2</sub> O/g-C	k <sub>D</sub> cm <sup>3</sup> -H <sub>2</sub> O/g-soil	V m/sec	R <sub>C</sub>	C <sub>POE</sub> /C <sub>SOURCE</sub>
Benzene	355	108.205	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	10.82	3.61	0.54	6.16E-04	81	0.049896	6.59E-08	1.240	8.597E-05
Toluene	159	48.4638	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	4.85	1.62	0.24	9.78E-04	133	0.130074	6.59E-08	1.625	1.052E-02
Ethylbenzene	76.9	23.4394	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	2.34	0.78	0.12	9.78E-04	176	0.172128	6.59E-08	1.827	2.251E-01
Xylenes	36.5	11.1253	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	1.11	0.37	0.06	9.78E-04	639	0.624942	6.59E-08	4.003	4.029E-01
MTBE	507	154.535	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	15.45	5.15	0.77	9.78E-04	12	0.011736	6.59E-08	1.056	7.300E-06
Naphthalene	34	10.3633	15	2	6.31E+08	2.47E-06	0.0096	0.36	1.73	1.04	0.35	0.05	9.78E-04	1543	1.509054	6.59E-08	8.252	4.661E-02

Source: South Carolina Department of Health and Environmental Control (SCDHEC) 1998. Risk-Based Corrective Action for Petroleum Releases, Bureau of Underground Storage Tank Management.

DOMENICO DILUTION/ATTENUATION MODEL WITHOUT BIOLOGICAL DECAY

$$\frac{C_X}{C_{SOURCE}} = \frac{1}{2} \operatorname{erfc} \left[ \frac{\left( x - \frac{vt}{R_c} \right)}{2 \sqrt{\alpha_x \frac{vt}{R_c}}} \right] \times \operatorname{erf} \left[ \frac{Y}{4 \sqrt{\alpha_y x}} \right] \times \operatorname{erf} \left[ \frac{Z}{2 \sqrt{\alpha_z x}} \right]$$

Constituent	C <sub>SOURCE</sub> mg/L	C <sub>X</sub> mg/L	RBSL mg/L
Benzene	60	0.005	0.005
Toluene	97	1.019	1.000
Ethylbenzene	3	0.716	0.700
Xylenes	25	10.023	10.000
MTBE	5289	0.039	0.040
Naphthalene	0.217	0.010	0.010

Prepared By: Gregory F. Sisco

Reviewed By: Alvin T. Jenkins